

**THIS IS THE TRACKED CHANGE DOCUMENT  
FROM SIS V02.00 to SIS V03.00!**

This is intended to show you the differences between the versions.

Due to the extra tracked text, pages number may not match the actual JADE\_FSW4\_SIS\_V03.PDF SIS document.

Minor changes have already been accepted so as to not clutter this document, e.g. analyse changed to analyze, “level 2” to “Level 2” or a comma added after a “However”. Likewise, the tracked change routine thought figures had altered; they had not, so have already been accepted in this version. Any other odd formatting in this document is due to the tracked changes.

**Please use JADE\_FSW4\_SIS\_V03.PDF for reference, not this document.**

**Juno  
Jovian Auroral Distributions Experiment**

**JADE Standard Product  
Data Record and Archive Volume  
Software Interface Specification**

Version ~~02~~03.00  
2018-~~August-07~~Nov-01

Prepared by

R. J. Wilson

**Juno**

**Jovian Auroral Distributions Experiment**

**JADE Standard Product  
Data Record and Archive Volume  
Software Interface Specification**

Custodian:

\_\_\_\_\_  
Rob J. Wilson  
JADE Archivist

\_\_\_\_\_  
Date

Approved:

\_\_\_\_\_  
Frédéric Allegrini  
JADE Lead

\_\_\_\_\_  
Date

\_\_\_\_\_  
William Kurth  
Juno Archivist

\_\_\_\_\_  
Date

\_\_\_\_\_  
Prachet Mokashi  
JSOC Manager

\_\_\_\_\_  
Date

\_\_\_\_\_  
Raymond J. Walker  
PDS/PPI Node Manager

\_\_\_\_\_  
Date

\_\_\_\_\_  
Reta Beebe  
PDS/ATMOS Node Manager

\_\_\_\_\_  
Date

## Table of Contents

<b>Table of Contents</b> .....	<b>iii</b>
<b>List of Figures</b> .....	<b>vi</b>
<b>List of Tables</b> .....	<b>vii</b>
<b>1 Introduction</b> .....	<b>1</b>
1.1 Distribution list .....	1
1.2 Document change log .....	2
1.3 TBD items .....	3
1.4 Abbreviations .....	4
1.5 Glossary .....	7
1.6 Juno Mission Overview .....	9
1.7 SIS Content Overview .....	9
1.8 Scope of this document .....	10
1.9 Applicable Documents .....	10
1.10 Audience .....	10
<b>2 JADE Instrument Description</b> .....	<b>11</b>
<b>3 Data Set Overview</b> .....	<b>12</b>
3.1 Data Sets .....	12
3.1.1 MCP Calibration (CAL) Data Set .....	15
3.1.2 High Rate Science (HRS) Data Set .....	16
3.1.3 High Voltage Engineering (HVE) Data Set .....	16
3.1.4 Low Rate Science (LRS) Data Set .....	16
3.1.5 Data units for Level 2 Products .....	17
3.1.6 DATA object vs. onboard data BLOB for Level 2 Products .....	17
3.1.7 Occasional jitter in reported times .....	17
3.2 Data Flow .....	18
3.3 Data Processing and Production Pipeline .....	20
3.3.1 CODMAC Level 2 Data Production Pipeline .....	20
3.3.2 CODMAC Level 3 Data Production Pipeline .....	21
3.4 Data Validation .....	21
3.4.1 Instrument Team Validation .....	21
3.4.2 Science Team Validation .....	21
<b>4 Archive volume generation</b> .....	<b>22</b>
4.1 Data transfer methods and delivery schedule .....	22
4.2 Data validation .....	23
4.3 Data product and archive volume size estimates .....	24
4.4 Backups and duplicates .....	25
4.5 Labeling and identification .....	26
<b>5 Archive volume contents</b> .....	<b>27</b>
5.1 Root directory .....	28
5.2 BROWSE directory (Not for Level 2 Volume) .....	28

5.3	CALIB directory (Level 3 Volume Only) .....	29
5.4	CATALOG directory .....	31
5.5	DATA directory .....	32
5.5.1	Contents .....	32
5.5.2	Subdirectory structure .....	32
5.5.3	Required files .....	32
5.5.4	The <i>yyyy/yyyyddd</i> subdirectory .....	33
5.5.4.1	The <i>ELECTRONS</i> subdirectory .....	34
5.5.4.2	The <i>ION_DIRECT_EVENTS</i> subdirectory .....	35
5.5.4.3	The <i>ION_LOGICALS</i> subdirectory .....	35
5.5.4.4	The <i>ION_SPECIES</i> subdirectory .....	35
5.5.4.5	The <i>ION_TOF</i> subdirectory .....	36
5.6	DOCUMENT directory .....	37
5.7	EXTRAS directory .....	38
5.8	INDEX directory .....	38
<b>6</b>	<b>Archive volume format.....</b>	<b>39</b>
6.1	Volume format .....	39
6.2	File formats .....	39
6.2.1	Document files .....	39
6.2.2	Tabular files .....	39
6.2.3	PDS labels .....	40
6.2.4	Catalog files .....	41
6.2.5	Index files.....	41
6.2.6	Binary formats of files .....	41
6.2.7	Days without Data.....	41
6.2.8	Level 2 data files .....	43
6.2.8.1	Electron Data.....	55
6.2.8.2	Ion Species Data.....	67
6.2.8.3	Ion Time of Flight Data.....	71
6.2.8.4	Ion Logicals Data .....	74
6.2.8.5	Ion Direct Events Data .....	77
6.2.9	Level 3 data files for file versions 01, 02 and 03 .....	81
6.2.9.1	Electron Data for V01, V02 and V03 .....	95
6.2.9.2	Ion Species Data for V01, V02 and V03 .....	102
6.2.9.3	Ion Time of Flight Data for V01, V02 and V03 .....	106
6.2.9.4	Ion Logicals Data for V01, V02 and V03 .....	110
6.2.9.5	Level 3 conversion of data for V01, V02 and V03 .....	113
6.2.10	Level 3 data files for file version 04+ .....	114
6.2.10.1	Electron Data for V04+ .....	130
6.2.10.2	Ion Species Data for V04+ .....	135
6.2.10.3	Ion Time of Flight Data for V04+ .....	137
6.2.10.4	Ion Logicals Data for V04+ .....	140
6.2.10.5	Level 3 conversion of data for V04+.....	143
6.2.11	Level 3 conversion of data .....	144
6.2.11.1	Remove any records where the level 2 MCP_COMMANDED_VALUE object is zero .....	144
6.2.11.2	Correct timestamps affected by the Juno time stutter.....	144
6.2.11.3	Check for FSW 4.00 LRS/CAL ion species bug (early 2015 data only).....	144
6.2.11.4	If ion data, merge ping and pong records to put all 64 energies in one record .....	144
6.2.11.5	Remap energy steps in to ascending eV/q order.....	145
6.2.11.6	Convert MCP_COMMANDED_VALUE to units of volts.....	145

6.2.11.7	Use SPICE to calculate auxiliary information.....	145
6.2.11.8	Apply any dead time corrections. ....	145
6.2.11.9	Convert level 2 counts to a more representative value and work out uncertainties.....	146
6.2.11.10	Convert Data and uncertainties to counts per second. ....	146
6.2.11.11	Remove non-DATA elements from DATA arrays .....	147
6.2.11.12	Remove an appropriate background to ‘clean’ the dataset.....	147
6.2.11.13	Assign correct energy table to the data .....	149
6.2.11.14	Populate azimuth and elevations angles in a despun frame. ....	149
6.2.11.15	If TOF data, Populate DIM3_* objects.....	149
6.2.11.16	If Electron data, despin MAG vector to same despun frame as the azimuths. ....	150
6.2.11.17	If HRS electron data at Jupiter, adjust the earlier elevation angles for the deflectors.....	150
6.2.11.18	Level 2 records that do not get converted to Level 3 .....	151
6.2.11.19	Level 3 DATA and BACKGROUND MISSING_CONSTANT (fill) values.....	152
6.2.11.20	Use SPICE to add position and orientation information .....	152
6.2.11.21	The Jupiter De-Spun-Sun (JUNO_JSS) co-ordinate System .....	153
6.2.12	Level 4 data files .....	154
6.2.13	Level 5 data files .....	154
<b>Appendix A</b>	<b>Support staff and cognizant persons.....</b>	<b>155</b>
<b>Appendix B</b>	<b>PDS label files .....</b>	<b>156</b>
B.1	Sample LBL file for JAD_L20_LRS_ELC_ANY_* .....	156
B.2	Sample LBL file for JAD_L20_LRS_ION_ANY_* .....	174
<b>Appendix C</b>	<b>Level 2 data record formats.....</b>	<b>191</b>
<b>Appendix D</b>	<b>Level 3 data record formats.....</b>	<b>192</b>
D.1	Sample FMT file for JAD_L30_HRS_ELC_TWO_CNT_V04.FMT .....	192
D.2	Sample FMT file for JAD_L30_HLS_ION_TOF_CNT_V04.FMT .....	224
<b>Appendix E</b>	<b>Level 5 data record formats.....</b>	<b>258</b>

## List of Figures

Figure 1: Juno science data flow diagram. White boxes are processes and solid arrows indicate data flow.....	19
Figure 2: JADE science data pipeline diagram.....	20
Figure 3: Duplication and dissemination of JADE standard archive volumes.....	25
Figure 4: Archive volume directory structure.....	27
Figure 5: ‘Periodic’ table comparing the different JADE products, giving their packet ID number in hex (DPID in figure key, see entry in Table 35), decimal, the PDS name fragment and information on what type of compression was used, and whether it records counts per accumulation or count rates.....	45
Figure 6: Breaking out the JADE Level 2 products in to the different Objects to allow similarities to be drawn.....	46
Figure 7: JADE-E Anodes vs. Look Directions (see Table 39 for the values).....	55
Figure 8: JADE-I Anodes.....	67
Figure 9: The Ion Spin Phase Sector mapping to ion anode and spin phase (start angles). .....	68
Figure 10: Breaking out the JADE Level 3 Version 01, 02 and 03 products in to the different PDS Objects to allow similarities to be drawn.....	85
Figure 11: Breaking out the JADE Level 3 Version 04+ products in to the different PDS Objects to allow similarities to be drawn.....	116
Figure 12: The Jupiter De-Spun-Sun (JUNO_JSS) co-ordinate system.....	153

## List of Tables

Table 1: Distribution list .....	1
Table 2: Document change log .....	2
Table 3: List of TBD items .....	3
Table 4: Abbreviations and their meaning.....	4
Table 5: CODMAC Levels of Data Descriptions and Meaning to JADE .....	8
Table 6: Relationship Between Data Sets and Standard Data Products .....	14
Table 7: Standard Data Product Contents .....	15
Table 8: Archive Schedule and Responsibilities .....	22
Table 9: Data product size and archive volume production rate (per Level (L) and version (V))	24
Table 10: PDS Data Set Volume Assignments.....	26
Table 11: Root directory contents.....	28
Table 12: BROWSE directory contents.....	28
Table 13: CALIB directory contents.....	29
Table 14: CATALOG directory contents .....	31
Table 15: DATA directory contents .....	32
Table 16: CODMAC Level 2 DATA/yyyy/yyyyddd directory contents.....	33
Table 17: CODMAC Level 3 DATA/yyyy/yyyyddd directory contents.....	33
Table 18: DATA/yyyy/yyyyddd/ELECTRONS directory contents for Level 2 data.....	34
Table 19: DATA/yyyy/yyyyddd/ELECTRONS directory contents for Level 3 data.....	34
Table 20: DATA/yyyy/yyyyddd/ION_DIRECT_EVENTS directory contents .....	35
Table 21: DATA/yyyy/yyyyddd/ION_LOGICALS directory contents for Level 2 data.....	35
Table 22: DATA/yyyy/yyyyddd/ION_LOGICALS directory contents for Level 3 data.....	35
Table 23: DATA/yyyy/yyyyddd/ION_SPECIES directory contents for Level 2 data .....	36
Table 24: DATA/yyyy/yyyyddd/ION_SPECIES directory contents for Level 3 data .....	36
Table 25: DATA/yyyy/yyyyddd/ION_TOF directory contents for Level 2 data .....	36
Table 26: DATA/yyyy/yyyyddd/ION_TOF directory contents for Level 3 data .....	36
Table 27: DOCUMENT directory contents .....	37
Table 28: EXTRAS subdirectory contents .....	38
Table 29: INDEX directory contents .....	38
Table 30: Format of index files for Level 2 .....	42
Table 31: Format of index files for Level 3 .....	42

Table 32: Size of a record of each Level 2 product. ....	44
Table 33: Data Collection types by dimensions. ....	47
Table 34: Data Collection types by units (green), lossy bit compression (red) and number of Level 2 files (purple).....	47
Table 35: Format of Level 2 data record header for all binary data files. ....	48
Table 36: Format of Level 2 data record sub-header for all binary data files of one sensor. ....	52
Table 37: Format of Level 2 data record sub-header for all binary data files of all electron sensors.....	52
Table 38: Full description of the ISSUE flag in the FMT/LBL files.....	53
Table 39: Electron anode mapping to bins and look directions. (Note: Electron spin phase sectors are over many anodes and require an equation, see section 6.2.8.1.4.).....	56
Table 40: Format of Level 2 data records for JAD_L20_CAL_ELC_ALL_* .....	58
Table 41: Format of Level 2 data records for JAD_L20_HRS_ELC_ALL_* .....	60
Table 42: Format of Level 2 data records for JAD_L20_HVE_ELC_ALL_* .....	62
Table 43: Format of Level 2 data records for JAD_L20_LRS_ELC_ANY_* .....	64
Table 44: Format of Level 2 data records for JAD_L20_HRS_ION_ANY_* .....	67
Table 45: Format of Level 2 data records for JAD_L20_HVE_ION_ALL_* .....	68
Table 46: Format of Level 2 data records for JAD_L20_LRS_ION_ANY_* and JAD_L20_CAL_ION_ANY_* .....	70
Table 47: Format of Level 2 data records for JAD_L20_HLC_ION_TOF_* .....	71
Table 48: Format of Level 2 data records for JAD_L20_HVE_ION_TOF_* .....	72
Table 49: Format of Level 2 data records for JAD_L20_HLC_ION_LOG_* .....	74
Table 50: Format of Level 2 data records for JAD_L20_HVE_ION_LOG_* .....	76
Table 51: Format of Level 2 data records for JAD_L20_ALL_ION_DER_* .....	77
Table 52: Description of DATA two-byte words for JAD_L20_ALL_ION_DER_* files to show how it is split out for the JAD_L20_ALL_ION_DES_* files. ....	78
Table 53: Format of Level 2 data records for JAD_L20_ALL_ION_DES_* .....	79
Table 54: Size of a record of each Level 3 product, by version number <sup>a,b</sup> .....	81
Table 55: Mapping Level 2 data files to Level 3 data files .....	83
Table 56: Format of Level 3 data record header for Versions 01, 02 and 03 .....	86
Table 57: Format of Level 3 data record subheader for Level 3 ion products. for V01, V02 and V03.....	93
Table 58: Format of Level 3 data record subheader for JAD_L30_HRS_ELC_ALL_* for V01, V02 and V03 .....	93



Table 59: Format of Level 3 data record subheader for JAD\_L30\_HRS\_ELC\_TWO\_\* for V01, V02 and V03 ..... 93

Table 60: Format of Level 3 data record subheader for JAD\_L30\_LRS\_ELC\_ANY\_\* for V01, V02 and V03 ..... 94

Table 61: Format of Level 3 data records for JAD\_L30\_HRS\_ELC\_ALL\_CNT for V01, V02 and V03 ..... 95

Table 62: Format of Level 3 data records for JAD\_L30\_HRS\_ELC\_TWO\_CNT for V01, V02 and V03 ..... 99

Table 63: Format of Level 3 data records for JAD\_L30\_LRS\_ELC\_ANY\_CNT for V01, V02 and V03 ..... 101

Table 64: Format of Level 3 data records for JAD\_L30\_HRS\_ION\_ANY\_CNT for V01, V02 and V03 ..... 102

Table 65: Format of Level 3 data records for JAD\_L30\_LRS\_ION\_ANY\_CNT for V01, V02 and V03 ..... 105

Table 66: Format of Level 3 data records for JAD\_L30\_HLS\_ION\_TOF\_CNT for V01, V02 and V03 ..... 107

Table 67: Format of Level 3 data records for JAD\_L30\_HLS\_ION\_LOG\_CNT for V01, V02 and V03 ..... 111

Table 68: Format of Level 3 data record header for Version 04+ ..... 118

Table 69: Format of Level 3 data record subheader for Level 3 ion products for V04+ ..... 128

Table 70: Format of Level 3 data record subheader for JAD\_L30\_HRS\_ELC\_ALL\_\* for V04+ ..... 128

Table 71: Format of Level 3 data record subheader for JAD\_L30\_HRS\_ELC\_TWO\_\* for V04+ ..... 128

Table 72: Format of Level 3 data record subheader for JAD\_L30\_LRS\_ELC\_ANY\_\* for V04+ ..... 129

Table 73: Format of Level 3 data records for JAD\_L30\_HRS\_ELC\_ALL\_CNT for V04+ ..... 130

Table 74: Format of Level 3 data records for JAD\_L30\_HRS\_ELC\_TWO\_CNT for V04+ ..... 133

Table 75: Format of Level 3 data records for JAD\_L30\_LRS\_ELC\_ANY\_CNT for V04+ ..... 134

Table 76: Format of Level 3 data records for JAD\_L30\_HRS\_ION\_ANY\_CNT for V04+ ..... 135

Table 77: Format of Level 3 data records for JAD\_L30\_LRS\_ION\_ANY\_CNT for V04+ ..... 136

Table 78: Format of Level 3 data records for JAD\_L30\_HLS\_ION\_TOF\_CNT for V04+ ..... 138

Table 79: Format of Level 3 data records for JAD\_L30\_HLS\_ION\_LOG\_CNT for V04+ ..... 141

Table 80: Format of Level 5 primary science data file records ..... 154

Table 81: Archive collection support staff ..... 155

# 1 Introduction

This software interface specification (SIS) describes the format and content of the Jovian Auroral Distributions Experiment (JADE) Planetary Data System (PDS) data archive. It includes descriptions of the Standard Data Products and associated metadata, and the volume archive format, content, and generation pipeline.

## 1.1 Distribution list

Table 1: Distribution list

Name	Organization	Email
Rob Wilson	LASP, JADE archivist	rob.wilson@lasp.colorado.edu
Chad Loeffler	SwRI, JADE FSW specialist	cloeffler@swri.edu
Frédéric Allegrini	SwRI, JADE Lead and JADE-E Scientist	fallegrini@swri.edu
Rob Ebert	SwRI, JADE-I Scientist	rebert@swri.edu
Phil Valek	SwRI	PValek@swri.edu
Bradley Trantham	SwRI	BTrantham@swri.edu
Fran Bagenal	LASP	Fran.Bagenal@lasp.colorado.edu
<del>Kyung-Chae-Eric Fattig</del>	<del>SwRI, JADE Operations Lead</del>	<del>kehaeric.fattig@swri.edu</del> <del>org</del>
Nigel Angold	JADE Operations Second	<del>nigel.angold@nasa.gov</del> <del>nangold@princeton.edu</del>
<del>Barry Birdwell</del> Jennifer R. Gale	<del>SwRI, JADE Project Manager</del>	<del>BBirdwell</del> <del>jennifer.gale@swri.edu</del> <del>org</del>
David McComas	Princeton	DMcComas@princeton.edu
Prachet Mokashi	JSOC Manager	PMokashi@swri.edu
William Kurth	Juno Archivist	william-kurth@uiowa.edu
Reta Beebe	PDS/ATMOS Node Manager	rbeebe@nmsu.edu
Steve Joy	UCLA/PDS/PPI	sjoy@igpp.ucla.edu
Joe Mafi	UCLA/PDS/PPI	jmafi@igpp.ucla.edu
Ray Walker	UCLA/PDS/PPI	rwalker@igpp.ucla.edu

## 1.2 Document change log

Table 2: Document change log

Change	Date	Affected portion
Initial template	01/15/2010	All
First draft for JADE	04/15/2013	All
Second draft for JADE	08/30/2013	All
FSW 3 Level 3 SIS parts added	06/30/2014	DPID changed to DPID_COUNT Removed Bill Knopf, Michael New and Tom Morgan from the signature list (email 20 <sup>th</sup> Nov '13) Version 02 Level 2 data: Change is an extra object (SCLKSCET_VERSION), and a bug in JAD_HRS_ION_TOF has been fixed from V01. Only V02 now provided to PDS.
FSW3 Level 2 Liens addressed. (Since accepted.)	06/30/2015	All
First draft of FSW4 (rather than FSW3 above) SIS.	12/13/2015	All previous SIS documents were for FSW 3, 2011-2014 data. In 2015 FSW 4 was uploaded, with new formats, and a new PDS Volume was started. This is the first draft of a FSW 4 only SIS. Previous FSW 3 will have its own volume in the PDS
Second draft of FSW4	11/07/2016	All. Updates to SIS for PDS peer review for Cruise Data Delivery deadline.
Third draft of FSW4	01/04/2017	Clarifying updates here and there while waiting for PDS peer review. Bit 4 and Bit 12 added to ISSUES flag in Table 38, and LRS/CAL ion species when ACCUMULATION_TIME = 30 warnings added to section 6.2.8.2.3.
Fourth draft of FSW4 to meet PDS peer review liens	05/19/2017	Clarifications and extra explanations, etc. in response to PDS peer review liens. Section 'Occasional jitter in reported times' added.
Version 01 released	07/17/2017	All – PDS peer review completed
Version 02 released	08/07/2018	An update for L3 V02 files. For differences from SIS Version 01 to SIS <del>Versions</del> Versions 02: see JADE_FSW4_SIS_V02_DIFF_V01.PDF
<a href="#">Version 03 released</a>	<a href="#">11/01/2021</a>	<a href="#">An update for L3 electron files V03 (no V03 ion files), and L3 V04 files (both electron and ion). For differences from SIS Version 02 to SIS Versions 03: see JADE_FSW4_SIS_V03_DIFF_V02.PDF</a>

**1.3 TBD items**

Table 3 lists items that are not yet finalized.

*Table 3: List of TBD items*

Item	Sections	Pages(s)

## 1.4 Abbreviations

Table 4: Abbreviations and their meaning

Abbreviation	Meaning
ASCII	American Standard Code for Information Interchange
BLOB	Binary Large OBject, i.e. a data blob is a large array of binary data
BRT	JADE Burst mode (FSW 3 only)
CAL	JADE Calibration mode
CATS	Juno version of CATS (Cassini Archive Tracking System)
CCSDS	Consultative Committee for Space Data Systems
CD-ROM	Compact Disc – Read-Only Memory
CDR	Calibrated Data Record
CFDP	CCSDS File Delivery Protocol
CHAR	Bytes representing a character string
CK	C-matrix Kernel (NAIF orientation data)
CNT	Units of counts per second, used in filenames
CODMAC	Committee on Data Management, Archiving, and Computing
CRC	Cyclic Redundancy Check
DAC	Digital to Analogue Conversion
DAP	Data Analysis Product
DAT	PDS binary file
DDR	Derived Data Record
DER	JADE Direct Events (Raw) mode
DES	JADE Direct Events (Split-out) mode
DOUBLE	An 8-byte (double-precision) real floating point value
DMAS	Data Management and Storage
DSN	Deep Space Network
DVD	Digital Versatile Disc
DVD-R	DVD – Recordable media
E&PO	Educational and Public Outreach
EDA	End of data acquisition
EDR	Experiment Data Record
EFB	Earth Fly By
EGA	Earth Gravity Assist
ELC	ELeCtron sensor
SPDR	Standard Product (Experiment and Pipeline) Data Record
FEI	File Exchange Interface
FGM	The 3-letter code for the magnetometer instrument on Juno. Also known as MAG.
FLOAT	A 4-byte (single-precision) real floating point value
FMT	PDS Format file
FOV	Field of View
FSW	Flight Software

FTP	File Transfer Protocol
GB	Gigabyte(s)
GCR	Galactic Cosmic Ray
GRAV	Orbit type focusing on gravity rather than MWR
GSFC	Goddard Space Flight Center
HK	Housekeeping
HLC	High rate, Low rate and Calibration mode
HLS	High and Low rate Science (or HLC minus Calibration)
HRS	JADE High Rate Science mode
HSK	JADE Housekeeping
HTML	Hypertext Markup Language
HV	High Voltage
HVE	High Voltage Engineering mode
HVENG	High Voltage ENGINEERING mode
HVCO	High Voltage Check Out
ICD	Interface Control Document
INT8	8-bit (1-byte) Signed Integer
INT16	16-bit (2-bytes) Signed Integer
INT32	32-bit (4-bytes) Signed Integer
IOT	Instrument Operations Team
ISO	International Standards Organization
JADE	Jovian Auroral Distributions Experiment
JEDI	Jupiter Energetic Particle Detector Instrument
JIRAM	Jupiter InfraRed Auroral Mapper
JOI	Jupiter Orbit Insertion
JPL	Jet Propulsion Laboratory
JSC	Johnson Spaceflight Center
JSOC	Juno Science Operations Center
JSS	Jupiter De-Spun-Sun co-ordinate system
LASP	Laboratory for Atmospheric and Space Physics, University of Colorado
LBL	PDS label file
LET	Lineal Energy Transport
LSB	Least Significant Byte first (also known as little endian)
LSB_INTEGER	PDS binary format: 1-, 2-, and 4- byte signed integers (little endian)
LSB_UNSIGNED_INTEGER	PDS binary format: 1-, 2-, and 4- byte unsigned integers (little endian)
LOG	LOGical counters (ion data)
LRS	JADE Low Rate Science mode
LUT	Look-Up Table(s)
MAG	Magnetometer Instrument (also known as FGM)
MB	Megabyte(s)
MCP	Micro Channel Plate

MOS	Mission Operations System
MWR	Microwave Radiometer Instrument
NAIF	Navigation and Ancillary Information Facility (JPL)
NASA	National Aeronautics and Space Administration
NSSDC	National Space Science Data Center
ODL	Object Description Language
PCK	Planetary Cartographic and Physical Constants Kernel (NAIF)
PC_REAL	PDS binary format: 4-, 8-, and 10- byte real numbers in IBM/PC format (little endian)
PDS	Planetary Data System
PPI	Planetary Plasma Interactions Node (PDS)
RDR	Reduced Data Record
RPM	Revolutions per Minute
RSSG	Radio Science System Group
SCET	Spacecraft Event Time
SCLK	Spacecraft Clock
SEU	Single Event Upset
SIS	Software Interface Specification
SOC	Science Operations Center
SPDR	Standard Product Data Record
SPE	Solar Particle Event
SPICE	Spacecraft, Planet, Instrument, C-matrix, and Events, (NAIF data format)
SPWG	Science Planning Working Group
SPK	SPICE (ephemeris) Kernel (NAIF)
SSH	Secure Shell
SwRI	Southwest Research Institute
TAR	Tape Archives (file format)
TBC	To Be Confirmed
TBD	To Be Determined
TEP	Tissue Equivalent Plastic
TOF	Time Of Flight
UINT8	8-bit (1-byte) Unsigned Integer
UINT16	16-bit (2-bytes) Unsigned Integer
UINT32	32-bit (4-bytes) Unsigned Integer
UCLA	University of California, Los Angeles
UVS	Ultraviolet Spectrometer Instrument
V-EGA	Venus-Earth Gravity Assist

## 1.5 Glossary

**Archive** – An archive consists of one or more data sets along with all the documentation and ancillary information needed to understand and use the data. An archive is a logical construct independent of the medium on which it is stored.

**Archive Volume** – A volume is a logical organization of directories and files in which data products are stored. An *archive volume* is a volume containing all or part of an archive; i.e. data products plus documentation and ancillary files.

**Archive Volume Set** – When an archive spans multiple volumes, they are called an *archive volume set*. Usually the documentation and some ancillary files are repeated on each volume of the set, so that a single volume can be used alone.

**Catalog Information** – High-level descriptive information about a data set (e.g. mission description, spacecraft description, instrument description), expressed in Object Description Language (ODL), which is suitable for loading into a PDS catalog.

**CODMAC Levels** – Descriptive data labels to inform you of the amount of processing from the original raw data product (as defined by the Committee on Data Management, Archiving, and Computing). These are different to NASA levels. Note that JADE data does not require CODMAC level 4 files; the PDS will ultimately contains JADE Level 2, 3 and 5 data. See Table 5 for the different level definitions.

**Data Product** – A labeled grouping of data resulting from a scientific observation, usually stored in one file. A product label identifies, describes, and defines the structure of the data. An example of a data product is a planetary image, a spectral table, or a time series table.

**Data Set** – A data set is an accumulation of data products together with supporting documentation and ancillary files.

**Experiment Data Record** – An accumulation of raw output data from a science instrument, in chronological order, with duplicate records removed, together with supporting documentation and ancillary files.

**Pipeline Data Record** – An accumulation of calibrated data from a science instrument, derived from experiment data records, together with supporting documentation, calibration data, and ancillary files.

**Standard Data Product** – A data product generated in a predefined way using well-understood procedures and processed in “pipeline” fashion. Data products that are generated in a non-standard way are sometimes called *special data products*.



Table 5: CODMAC Levels of Data Descriptions and Meaning to JADE

CODMAC Level	Description	Meaning for JADE	Stored JSOC / PDS	NASA Level
1 (Raw)	Telemetry data stream as received at the ground station, with science and engineering data embedded.	Packet Data (Highly Compressed)	No	Packet Data
2 (Edited)	Instrument science data (e.g., raw voltages, counts) at full resolution, time ordered, with duplicates and transmission errors removed.	Unpacked Data (Engineering Units.)	Yes	0
3 (Calibrated)	Level 2 data that have been located in space and may have been transformed (e.g., calibrated, rearranged) in a reversible manner and packaged with needed ancillary-data (e.g., radiances with the calibration equations applied).	Unpacked Data (Scientific Units.)	Yes	1-A
4 (Resampled)	Irreversibly transformed (e.g., resampled, remapped, calibrated) values of the instrument measurements (e.g., radiances, magnetic field strength).	Not used for JADE (Better for images than plasma data)	N/A	1-B
5 (Derived)	Level 3 or 4 data that have been resampled and mapped onto uniform space-time grids. The data are calibrated (i.e., radiometrically corrected) and may have additional corrections applied (e.g., terrain correction).	e.g.  Plasma Parameters,  Pitch Angle Distributions  [TBD]	Yes	1-C
	Geophysical parameters, generally derived from Level 3 or 4 data, and located in space and time commensurate with instrument location, pointing, and sampling.			2
	Geophysical parameters mapped onto uniform Space-time grids.			3
	Any product that also requires data from another instruments for its derivation. (i.e. electron pitch angle derivation requires both level 3 MAG and level 3 electron data.)			2

Table inspired by Appendix F of the Planetary Data System Archive Preparations Guide (APG), Version 1.4 (April 1, 2010) found at <https://pds.nasa.gov/documents/apg/apg.pdf>.

However they compared CODMAC Levels to NASA Levels and had a description based on NASA levels, which this author has altered in the table above to refer to CODMAC levels. This author also added the final level 5 line about products requiring additional data from other instruments.

## 1.6 Juno Mission Overview

Juno launched on the first day of its launch window, 5 August 2011. The spacecraft used a  $\Delta V$ -EGA trajectory consisting of deep space maneuvers on 08 August 2012 and 14 September 2012 followed by an Earth gravity assist (EGA) on 9 October 2013. Jupiter arrived on 5 July 2016 (UTC), using two 53-day capture orbits prior to commencing operations for a 5-(Earth) year long prime mission comprising 34 high inclination, high eccentricity orbits of Jupiter. Instead of firing the engines a second time to get to the originally intended 14-day orbits, it was decided not to, and remain in the 53-day orbital periods (altering the 34 orbit prime mission duration from the original 1 year to 5 years). The orbit is polar ( $90^\circ$  inclination) with a periapsis altitude of  $\sim 4200$  km and a semi-major axis of  $\sim 113 R_J$  ( $1 R_J$  is one Jovian radius,  $\sim 71492$  km). The primary science is acquired for  $\sim 6$  hours,  $\sim$ centered on each periapsis although fields and particles data are acquired at low rates for the remaining orbit. Of the first 9 periapses, 4 were dedicated to microwave radiometry (MWR orbits) of Jupiter's deep atmosphere, 4 were dedicated to gravity measurements (GRAV orbits) to determine the structure of Jupiter's interior, and Juno went in to Safe mode on orbit 2 resulting in no perijove data. All orbits will include fields and particles measurements of the planet's auroral regions. Juno is spin stabilized with a rotation rate of 1 to 3 revolutions per minute (RPM). For the MWR orbits the spin axis is, usually, perpendicular to the orbit plane so that the radiometer fields of view pass through the nadir, but is tilted for some orbits. For gravity passes, the spin axis is aligned to the Earth direction, allowing for Doppler measurements through the periapsis portion of the orbit. The orbit plane is initially very close to perpendicular to the Sun-Jupiter line and evolves over the mission. Data acquired during the periapsis passes are recorded and played back over the subsequent apoapsis portion of the orbit.

Juno's instrument complement includes Gravity Science using the X and Ka bands to determine the structure of Jupiter's interior; vector fluxgate magnetometer (MAG) to study the magnetic dynamo and interior of Jupiter as well as to explore the polar magnetosphere; and a microwave radiometer (MWR) experiment covering 6 wavelengths between 1.3 and 50 cm to perform deep atmospheric sounding and composition measurements. The instrument complement also includes a suite of fields and particle instruments to study the polar magnetosphere and Jupiter's aurora. This suite includes an energetic particle detector (JEDI), a Jovian auroral (plasma) distributions experiment (JADE), a radio and plasma wave instrument (Waves), an ultraviolet spectrometer (UVS), and a Jupiter infrared auroral mapping instrument (JIRAM). The JunoCam is a camera included for education and public outreach. While this is not a science instrument, we plan to capture the data and archive them in the PDS along with the other mission data. Appendix A includes Lead Co-Is and archivists for JADE, along with the associated PDS Discipline Node.

## 1.7 SIS Content Overview

Section 2 describes the JADE instrument. Section 3 describes the data sets, data flow, and validation. Section 4 describes the structure of the archive volumes and contents of each file. Section 5 describes the file formats used in the archive volumes.

Individuals responsible for generating the archive volumes are listed in Appendix A. PDS-compliant label files for all JADE standard data products are itemized and described in Appendix B, while the data products file headers and data record formats are itemized and described in section 6, Appendix C, and Appendix D respectively.

## 1.8 Scope of this document

The specifications in this SIS apply to all JADE Standard Data Record products submitted for archive to the Planetary Data System (PDS), for all phases of the Juno mission. Some sections of this document describe parts of the JADE archive and archiving process that are managed by the PDS archive team. These sections have been provided for completeness of information and are not maintained by the JADE team.

This document is not intended as a JADE Users Guide; it describes the data, not how to interpret the data for science. Seek guidance from the JADE team for how to use the data.

## 1.9 Applicable Documents

*ISO 9660-1988, Information Processing—Volume and File Structure of CD-ROM for Information Exchange*, 04/15/1988.

*Planetary Data System Archive Preparation Guide*, Version 1.1, JPL D-31224, 08/29/2006.

*Planetary Data System Standards Reference*, JPL D-7669, Part 2, Version 3.8, 02/27/2009.

*Planetary Science Data Dictionary Document*, Planetary Data System, JPL D-7116, Version 1r65, 02/2007.

*Juno Mission Operations Concept Document*, JPL D-35531, Version Preliminary, 04/30/2007.

*Juno Science Data Management and Archive Plan*, Version Final, JPL D-34032, 08/26/2009.

The JADE Instrument Paper (also see section 2):

McComas, D.J. and Alexander, N. and Allegrini, F. and Bagenal, F. and Beebe, C. and Clark, G. and Crary, F. and Desai, M.I. and De Los Santos, A. and Demkee, D. and Dickinson, J. and Everett, D. and Finley, T. and Gribanova, A. and Hill, R. and Johnson, J. and Kofoed, C. and Loeffler, C. and Louarn, P. and Maple, M. and Mills, W. and Pollock, C. and Reno, M. and Rodriguez, B. and Rouzaud, J. and Santos-Costa, D. and Valek, P. and Weidner, S. and Wilson, P. and Wilson, R.J. and White, D. (2017), The Jovian Auroral Distributions Experiment (JADE) on the Juno Mission to Jupiter, *Space Science Reviews*, **213**, 547-643, doi: 10.1007/s11214-013-9990-9

## 1.10 Audience

This document is useful to those wishing to understand the format and content of the JADE PDS data product archive collection. Typically, these individuals would include scientists, data analysts, or software engineers.

## 2 JADE Instrument Description

Rather than repeat information, we refer the reader to the **Open Access** instrument paper in Space Science Reviews (SSR) for a full description of the JADE instrument. Below we provide the DOI link to the paper, reference and the abstract that gives an overview of the instrument.

NOTE: JADE had FSW 3 when this instrument paper was written and published. Since then we use FSW 4 and the JADE products are different. This SIS is the best description of the FSW 4 products, however the actual hardware and science goals remain the same.

### Official SSR citation and DOI:

McComas, D.J., Alexander, N., Allegrini, F. et al. Space Sci Rev (2017) 213: 547.  
<https://doi.org/10.1007/s11214-013-9990-9>

### AGU style reference:

McComas, D. J., *et al.* (2017), The Jovian Auroral Distributions Experiment (JADE) on the Juno Mission to Jupiter, *Space Science Reviews*, **213**, 547-643, doi:[10.1007/s11214-013-9990-9](https://doi.org/10.1007/s11214-013-9990-9).

The paper was accepted and published online at SSR in 2013, hence some references may have that year. When the Juno special issue came out in 2017, SSR altered the year to 2017 for all Juno instruments papers, but is otherwise the same (same DOI, same paper, only the publish year altered and a printed issue volume and page numbers are now included in the citation).

### Abstract:

“The Jovian Auroral Distributions Experiment (JADE) on Juno provides the critical in situ measurements of electrons and ions needed to understand the plasma energy particles and processes that fill the Jovian magnetosphere and ultimately produce its strong aurora. JADE is an instrument suite that includes three essentially identical electron sensors (JADE-Es), a single ion sensor (JADE-I), and a highly capable Electronics Box (EBox) that resides in the Juno Radiation Vault and provides all necessary control, low and high voltages, and computing support for the four sensors. The three JADE-Es are arrayed 120° apart around the Juno spacecraft to measure complete electron distributions from ~0.1 to 100 keV and provide detailed electron pitch-angle distributions at a 1 s cadence, independent of spacecraft spin phase. JADE-I measures ions from ~5 eV to ~50 keV over an instantaneous field of view of 270° x 90° in 4 s and makes observations over all directions in space each 30 s rotation of the Juno spacecraft. JADE-I also provides ion composition measurements from 1 to 50 amu with  $m/\Delta m \sim 2.5$ , which is sufficient to separate the heavy and light ions, as well as O<sup>+</sup> vs. S<sup>+</sup>, in the Jovian magnetosphere. All four sensors were extensively tested and calibrated in specialized facilities, ensuring excellent on-orbit observations at Jupiter. This paper documents the JADE design, construction, calibration, and planned science operations, data processing, and data products. Finally, the Appendix describes the Southwest Research Institute [SwRI] electron calibration facility, which was developed and used for all JADE-E calibrations. Collectively, JADE provides remarkably broad and detailed measurements of the Jovian auroral region and magnetospheric plasmas, which will surely revolutionize our understanding of these important and complex regions.”

### 3 Data Set Overview

#### 3.1 Data Sets

The JADE data archive is divided into 3 data sets. Each data set is subdivided into different standard data product types. A basic description of each data set is provided in Table 6. The standard data product types are described in Table 7. A more detailed description of each data set is provided in the sections that follow these two tables.

The standard data product IDs for Level 2 data are a series of *five* three-letter codes (instrument, CODMAC level, telemetry mode, sensor and data type, respectively) separated by an underscore, of the form:

JAD\_L20\_aaa\_bbb\_ccc

The products filenames then append that with a date and version number, of the form:

JAD\_L20\_aaa\_bbb\_ccc\_yyyyddd\_Vnn.DAT

JAD\_L20\_aaa\_bbb\_ccc\_yyyyddd\_Vnn.LBL

JAD\_L20\_aaa\_bbb\_ccc\_Vnn.FMT

Where:

- JAD Instrument, short for JADE
- L20 CODMAC Level 2, JADE internal convention 0 (zero).
- aaa Telemetry mode type:
  - ALL = All telemetry modes
  - CAL = Calibration telemetry mode
  - HLC = High rate, low rate and calibration telemetry modes
  - HRS = High rate telemetry mode
  - HSK = Housekeeping telemetry mode*
  - HVE = High Voltage Engineering telemetry mode
  - LRS = Low rate telemetry mode
- bbb Sensor type: ALL, ELC or ION
  - ELC = electron sensor(s)
  - ION = ion sensor
  - ALL = both ion and electron sensors*
- ccc Data type:
  - ALL = all three electron sensors, or all eight ion species
  - ANY = any of the electron sensors, or any ion species
  - DER / DES = ion Direct Events Raw / Split-out
  - LOG = ion Logical counters
  - TOF = ion Time-Of-Flight
  - BHK, BMS, MEM, ERR, SHK = Not for PDS, JADE operations only*
  - OA0, OA1, OA2, OA3 = Not for PDS, JADE operations only*
- yyyy 4-digit year
- ddd 3-digit day of year
- nn 2-digit version number of file

*Values in grey italics are JADE operations products not for science and not in PDS, but listed here for completeness to benefit JADE team members. The FMT file is also within the LBL file.*

The standard data product IDs for Level 3 data are a similar series of *five* three-letter codes (instrument, CODMAC level, telemetry mode, sensor, data type and unit, respectively) separated by an underscore, of the form:

L30\_ *aaa\_bbb\_ccc\_uuu*

[The starting “JAD\_” of level 2 files has been dropped from level 3 files as a PDS requirement forbids STANDARD\_PRODUCT\_ID being more than 20 characters, however JAD\_ is still used for level 3 filenames.]

*The products filenames then append that with a date and version number, and prepend with JAD\_, of the form:*

JAD\_L30\_ *aaa\_bbb\_ccc\_uuu\_yyyyddd\_Vnn*.DAT  
JAD\_L30\_ *aaa\_bbb\_ccc\_uuu\_yyyyddd\_Vnn*.LBL  
JAD\_L30\_ *aaa\_bbb\_ccc\_uuu\_Vnn*.FMT

Where:

- JAD Instrument, short for JADE
- L30 CODMAC Level 3, JADE internal convention 0 (zero).
- aaa* Telemetry mode type:
  - CAL* = Calibration telemetry mode, Not for PDS, JADE operations only
  - HLS* = High rate and low rate telemetry mode (not including calibration)
  - HRS* = High rate telemetry mode
  - LRS* = Low rate telemetry mode
- bbb* Sensor type:
  - ELC* = electron sensor(s)
  - ION* = ion sensor
- ccc* Data type:
  - ALL* = all three electron sensors, or all eight ion species
  - TWO* = Electron sensors E060 and E180, but not E300.
  - ANY* = any of the electron sensors, or any ion species
  - LOG* = ion Logical counters
  - TOF* = ion Time-Of-Flight
- uuu* Unit type:
  - CNT* = counts per second
- yyyy* 4-digit year
- ddd* 3-digit day of year
- nn* 2-digit version number of file

Table 6: Relationship Between Data Sets and Standard Data Products

Data Set ID	CODMAC Level	Standard Data Product ID	ID
JNO-SW-JAD-2-UNCALIBRATED-V1.0 Uncalibrated science data 2011 to 2014 inclusive, using FSW 3 data.	2	See FSW 3 SIS document for details, available within that PDS volume.	P0
JNO-J/SW-JAD-2-UNCALIBRATED-V1.0 Uncalibrated science data 2015 onwards, using FSW 4 data.	2	JAD_L20_ALL_ION_DER JAD_L20_ALL_ION_DES JAD_L20_CAL_ELC_ALL JAD_L20_CAL_ION_ANY JAD_L20_HLC_ION_LOG JAD_L20_HLC_ION_TOF JAD_L20_HRS_ELC_ALL JAD_L20_HRS_ION_ANY JAD_L20_HVE_ELC_ALL JAD_L20_HVE_ION_ALL JAD_L20_HVE_ION_LOG JAD_L20_HVE_ION_TOF JAD_L20_LRS_ELC_ANY JAD_L20_LRS_ION_ANY	P0
JNO-J/SW-JAD-3-CALIBRATED-V1.0 Calibrated JADE data 2015 onwards only. All data prior to 2015 (FSW 3) was operational only and contained no science intervals.	3	L30_HLS_ION_LOG_CNT L30_HLS_ION_TOF_CNT L30_HRS_ELC_ALL_CNT L30_HRS_ELC_TWO_CNT L30_HRS_ION_ANY_CNT L30_LRS_ELC_ANY_CNT L30_LRS_ION_ANY_CNT <i>[Note: filenames start JAD_L30_* but no JAD_ in Standard Data Product ID as 20 char limit in PDS.]</i>	P1
		[TBD]	P2
		[TBD]	P3
JNO-J/SW-JAD-5-PAD-V1.0 JNO-J/SW-JAD-5-PLASMA-V1.0 JNO-J/SW-JAD-5-MOM-V1.0 [TBC] Calibrated JADE data Pitch angle data and plasma parameters/moments	5	[TBD]	P4
		[TBD]	P5

Table 7: Standard Data Product Contents

ID	Key/Physical Parameters	Processing Inputs	Product Format	Description
P0	Reformatted Engineering Data Record (REDR). Time ordered (duplicates removed) full resolution science data (counts at voltage levels). Time ordered counts (per accumulation or per second) vs. voltage level vs. direction.	JADE raw telemetry packets	Binary	Packets are uncompressed, bitmaps expanded to single objects, extra objects added to describe FSW and LUT versions, data units and a UTC timestamp.
P1	Time ordered counts per second in energy vs. look direction, with uncertainties.	JADE P0 data	Binary	Like JADE packets are combined to fewer files with position/auxiliary info necessary to calculate position or moments
P2	Time ordered {electron or ion} flux vs. direction vs. energy. TBC.	JADE P1 data	Binary	[TBD]
P3	Time ordered ion flux vs. energy vs. TOF. TBC.	JADE P1 data	Binary	[TBD]
P4	Time ordered electron pitch angle distribution vs. energy. TBC.	JADE P2 and MAG data	Binary	[TBD]
P5	Time ordered plasma moments vs. composition. TBC.	JADE P2/3 and MAG data	ASCII	[TBD]

The following sub-sections describe the different modes of JADE, but are best summarized in the periodic table inspired Figure 5.

### 3.1.1 MCP Calibration (CAL) Data Set

This is not intended for science use, but for the JADE instrument team to perform calibration tests. It occurs for a total of ~80 minutes per orbit.

The data has a minimum value removed (the MIN\_SUBTRACTED\_VALUE object), then is compressed from 4-byte values to 1-byte values, then losslessly compressed for transmission. The Direct Events products are the exception in not being compressed in any way.

There is just one electron product that contains all three electron sensors separately but within the same record.



The ion data records are split into ping and pongs, each containing half the energy sweep, which must be merged for Level 3 and higher products.

### **3.1.2 High Rate Science (HRS) Data Set**

This is the highest data rate mode, occurring for a total of ~6 hours per orbit.

The data has a minimum value removed (the MIN\_SUBTRACTED\_VALUE object), then is compressed from 2-byte values to 1-byte values, then losslessly compressed for transmission. The Direct Events products are the exception in not being compressed in any way.

There is just one electron product that contains all three electron sensors separately but within the same record.

The ion data records are split in to ping and pongs, each containing half the energy sweep, which must be merged for Level 3 and higher products.

### **3.1.3 High Voltage Engineering (HVE) Data Set**

This is not intended for science use, but for the JADE instrument team to perform tests, occurring for a total of ~1 to 2.5 hours per orbit (depending on any maneuvers).

The data is collected as total counts without any compression at all (and does not remove a minimum subtracted value).

There is just one electron product that contains all three electron sensors, and just one ion species product that contains all eight ion species.

The ion data records are split into ping and pongs, each containing half the energy sweep, which must be merged for Level 3 and higher products.

### **3.1.4 Low Rate Science (LRS) Data Set**

This is the most common mode and the lowest data rate, occurring for a total of ~327 hours per orbit, with ~19 hours of that within an intermediate (higher time cadence) LRS mode.

The data has a minimum value removed (the MIN\_SUBTRACTED\_VALUE object), then is compressed from 4-byte values to 1-byte values, then losslessly compressed for transmission. The Direct Events products are the exception in not being compressed in any way.

There are three electron products, one for each sensor. However, only one electron sensor can be active at a time while in LRS mode.

The ion data records are split into ping and pongs, each containing half the energy sweep, which must be merged for Level 3 and higher products.

### 3.1.5 Data units for Level 2 Products

The base data unit (for products with PACKETID >10) is total counts for that record (as such are integer numbers), with the exception of JAD\_L20\_CAL\_ION\_ANY\_\*, JAD\_L20\_LRS\_ION\_ANY\_\* and JAD\_L20\_LRS\_ELC\_ANY\_\* products. These are in units of count rates as these are data products related to spin phase and the spin-period may vary slightly. The count rates are total counts divided by number of views within the accumulation time, to the nearest 1/512 of a count (represented as a float).

The number of views is simply the number of times an anode has been included in the record's accumulation time; for instance if two anodes are summed together for a product, then that's two views. If the accumulation is over many spacecraft spin periods and the product is one regarding spin-phase, then every spin the number of views increases for a particular spin-phase angle. The record normalized total counts measured by total number of views, however that is rarely equivalent to units of counts per second.

To be certain you know which units, all products have had an object added to their PDS record, DATA\_UNITS, which (for Level 2 data) is either 0 or 1 for total count or rate respectively.

### 3.1.6 DATA object vs. onboard data BLOB for Level 2 Products

Many JADE products onboard JUNO remove a minimum value from the data prior to compression of the data BLOB for transmission. On the ground when we decompress these data packets we add back on this value so that the end user does not have to; with the MIN\_SUBTRACT\_VALUE object used reported in the file. If the object did not have a minimum value removed and so not object (e.g. HSK telemetry modes) then for consistency a MIN\_SUBTRACT\_VALUE object is added to the file on the ground, but if so will be set to zero, and the upper and lower valid limits for that product will be fixed at zero.

### 3.1.7 Occasional jitter in reported times

Occasionally the reported spacecraft clock value is a second out from where you would expect, e.g. in a series of records all with an ACCUMULATION\_TIME of 30 seconds, you may get times that are consistently 30 seconds apart, then (very occasionally) have one that is 29 or 31 seconds apart from its neighbor based on the spacecraft clock (used to make UTC). This is a known Juno feature related to having two spacecraft clocks, but any correction would be a level 3 data product (as it is a time calibration). The two clocks on Juno are not always synchronized, and the time message from them can occasionally have a stutter/jitter where instead of advancing 2 ticks, sometimes it advances 3 ticks, then some 2 ticks, then 1 tick, then returns to the regular 2 tick pattern. JADE Level 2 data records use the onboard reported time message as is, and has no in-situ way to know if the reported time is during this stutter. However, on the ground we add ISSUES object bit 10 to mark Level 2 records where we know that the JADE packet's TIMESTAMP\_WHOLE/SUB has been stuttered. [Note version 01+ files will have this, but version 00 file (not on PDS) are made before the time stutter intervals are known, so may not be flagged until later when we make the non-zero version file.] For Level 3 JADE files, we correct for the Juno time stutter in the TIMESTAMP\_WHOLE/SUB object, and adjust the ISSUES object: removing ISSUES bit 10 and flagging ISSUES bit 5.

This Juno time stutter affects all spacecraft clock times reported by JADE, and tends to occur every few days. While we do track the times it affects the JADE packet's `TIMESTAMP_WHOLE/SUB`, we do not track any others spacecraft clock times. For example the Electron files have `MAG_TIMESTAMP_WHOLE/SUB` objects which may also be affected, but JADE does not track these nor attempt to correct. This is because publishable work requiring MAG data should be using the MAG team's Version 01+ MAG files, rather than the uncalibrated 'quicklook' spacecraft reported MAG from JADE's files.

For JADE team operations work (files not on PDS), the OSCOPE MET times may also be affected, as could the `SPIN_TIME_WHOLE/SUB` values in SHK files, neither of which is tracked for time stutter effects. In all cases listed above, the LBL file for these objects note they may be subject to the Juno time stutter.

## 3.2 Data Flow

The Juno Data Management and Storage (DMAS) will receive packets and CCSDS File Delivery Protocol (CFDP) products from the Deep Space Network (DSN) and place these on the Project data repository system. The DMAS will provide the initial processing of the raw telemetry data bringing it to Committee on Data Management and Archive (CODMAC) Level 1 science data. The JADE Instrument Operations Team (IOT) will retrieve the CODMAC Level 1 data from the DMAS using FEI services and ancillary data from the JPL Mission Support Area (MSA) via Juno Science Operations Center (JSOC). The IOT will decompress the Level 1 data and return them to the JSOC as CODMAC Level 2 data. The JSOC will also receive and organize higher-level data products developed by the Science Investigation Teams associated with each instrument. JSOC development and operations will be carried out at SwRI, in coordination with the MOS at JPL.

The JADE Science Investigation Team will verify the content and the format will be validated. The resulting decompressed, restructured Level 2 data will constitute the lowest level of data to be archived with the PDS. JSOC will coordinate the validation of the edited (CODMAC Level 2) data archive volumes created by the IOT. The Science Investigation Team will develop higher-level data products based on the Level 2 data and ancillary data and return these to the JSOC. JSOC will support archiving the Level 2 data by building archive volumes and verifying the format of the volumes and included data and metadata. Higher-level data set archives will be coordinated through the JSOC. The Science Investigation Team will be responsible for ensuring that the metadata and documentation included with these data sets are complete and accurate. This means that both JSOC and the Science Investigation Team will need to work closely with the PDS. This coordination will be fostered via the Data Archive Working Group.

A comprehensive description of the Juno Mission System is provided in the Juno Mission Operations Concept. A data flow diagram for the downlink process is shown in Fig. 1.




Figure 1: Juno science data flow diagram. White boxes are processes and solid arrows indicate data flow.

### 3.3 Data Processing and Production Pipeline

A single pipeline generates EDR records temporarily on route to generating RDR records, with the CODMAC level 2 data being the RDR records only, as shown in Figure 2.




Figure 2: JADE science data pipeline diagram.

#### 3.3.1 CODMAC Level 2 Data Production Pipeline

New data is pushed to LASP by FEI (JPL software) subscriptions to the CODMAC Level 1 data at JPL. The FEI subscriptions permanently run on a production computer hosted at LASP, with hourly cron checks to ensure the subscriptions are still running (and re-establish if necessary). In addition, a cron does a weekly check that all data available by FEI has been downloaded locally. Ingestion scripts can be triggered by FEI or by a regular cron job that looks for new local files. The binary files can contain any number of packets of any type of JADE data (PACKETIDs > 10), which are split out such that every unique packet is written to its own file – a PDS packet-snippet. The software that does that is written in c for speed, and every object in the packet is checked that it is within an allowed range expected for that particular packet. A few extra objects are added, such as a UTC object generated from the spacecraft clock values in the packet and converted with SPICE routines. PDS packet-snippets contain the time of day in the filename and are written in to directory structures based on date (`yyyy/yyyyddd/data_type/`), and are almost PDS compliant in that the DAT files obey the FMT file descriptions for the given product, but do not have a corresponding LBL file (LBL files are only generated once daily files are created). Duplicate packets in the FEI data originally over-wrote the previous PDS packet-snippet so only one is kept, but now a duplicate packet loads in the old one first, and if identical leaves it, otherwise reports an error as being different (a situation that has never occurred to date).

Reordering the data is now merely a cron to go through each `yyyy/yyyyddd/data_type/` directory, seeing if any files were modified/created since the last time the cron ran, and if so, concatenating the files of each product to a single file (with a Linux `cat` command). Due to the time of day

being noted in the filenames, this concatenates them in the correct time order. The daily files are written to a different set of *yyyy/yyyyddd/data\_type/* directories (see Figure 4), and code run to create the LBL file for each daily file. These are then fully PDS compliant CODMAC Level 2 daily files for each product available that day, ready for upload to JSOC via FTP.

### 3.3.2 CODMAC Level 3 Data Production Pipeline

The Level 2 data (previous section) are used as input to generate the Level 3 files, together with reconstructed SPICE kernels in order to provide position and orientation information (see section 6.2.9.5 for more details about the conversion to science units). This is done in IDL, and can take several minutes to run per file, as such a cron job will run nightly (if not more often) to call IDL to create level 3 DAT files for any new level 2 files that have appeared in the last day. The same cron job then runs a python code that generates the corresponding LBL files (containing the FMT file) for the DAT file and pushes them to the appropriate *yyyy/yyyyddd/data\_type/* directories (see Figure 4). These are then fully PDS compliant CODMAC Level 3 daily files for each product available that day, ready for upload to JSOC via FTP.

## 3.4 Data Validation

General PDS syntax / formatting checks are carried out at the earliest stage of processing to ensure the data obeys the PDS standards. Periodically PDS online validation tools are run on local volumes to ensure that the CODMAC Level 2/3 product standards are met, as well as bespoke checks carried out locally. This ensures values are within acceptable ranges (or a fill value, a.k.a. MISSING\_CONSTANT), correctly ordered, and correctly labeled.

### 3.4.1 Instrument Team Validation

The JADE instrument team will be the first to see any data by monitoring trend plots and examining the data to ensure what was commanded occurred. In addition they will monitor the health of the various sensors and carry out regular calibration exercises. During these activities any inconsistencies that may arise will be investigated, corrected where possible, or noted in the ERRATA.TXT for the volume.

### 3.4.2 Science Team Validation

The JADE science team will provide validation by virtue of using the data and reporting any inconsistencies to the instrument team. Since each orbit takes [+4up to 53](#) days and there is a 3 to 6 month lag between acquiring the data and providing it to the PDS (see Table 8) there is enough time for the science team to work with the data prior to PDS submission.

## 4 Archive volume generation

The JADE Standard Data Record archive collection is produced by the JADE IOT in cooperation with the JSOC, and with the support of the PDS Planetary Plasma Interactions (PPI) Node at the University of California, Los Angeles (UCLA). The archive volume creation process described in this section sets out the roles and responsibilities of each of these groups. The assignment of tasks has been agreed by all parties. Archived data received by the PPI Node from the JADE team will be made electronically available to PDS users as soon as practical but no later than as laid out in Table 8.

### 4.1 Data transfer methods and delivery schedule

The JADE team will deliver data to the PPI Node in standard product packages containing three months of data, also adhering to the schedule set out in Table 8. Each package will comprise both data and ancillary data files organized into directory structures consistent with the volume design described in Section 5, and combined into a deliverable file(s) using file archive and compression software. When these files are unpacked at the PPI Node in the appropriate location, the constituent files will be organized into the archive volume structure.

Table 8: Archive Schedule and Responsibilities

Instrument	Data Product	Provider	Earth Flyby (EFB)	Other Cruise	Orbital Phase
JADE R. J. Wilson	P0 (Level 2)	JADE Team	<i>JADE was off throughout EFB, =&gt; No data to archive.</i>	Jupiter + 4 mo.	EDA + 3 to 6 mo.
	P1, P2, P3 (Level 3)	JADE Team		Jupiter + 4 mo.	EDA + 3 to 6 mo.
	P4, P5 (Level 5)	JADE Team		Jupiter + 4 mo.	Deorbit + 9 mo.

EDA – End of data acquisition

The archives will be sent electronically from the JADE IOT to a user account on the PPI node using the *ssh* protocol. The IOT operator will copy each volume (see Table 10) in the form of a compressed *tar* archive (a.k.a. *tarball*) to an appropriate location within the PPI file system. Only those files that have changed since the last delivery will be included. The PPI operator will decompress the data, using the *tar* checksums to verify that the archive is complete. Each step of data submission process will be tracked in a version CATS (Cassini Archive Tracking System) which has been adapted for use by Juno.

Following receipt of a data delivery, PPI will organize the data into PDS archive volume structure within its online data system. PPI will generate all of the required files associated with a PDS archive volume (index file, read-me files, etc.) as part of its routine processing of incoming JADE data. Newly delivered data will be made available publicly through the PPI online system once accompanying labels and other documentation have been validated. It is anticipated that this validation process will require no more than fourteen working days from receipt of the data by PPI. The first two data deliveries are expected to require somewhat more time for the PPI Node to process before making the data publicly available.

The Juno prime mission begins after JOI and two subsequent correction orbits, and lasts for 33 ~1453 day orbits. Table 8 formalizes the data delivery schedule for the entire Juno mission, including cruise, commissioning and prime mission phases. Data delivery from JSOC to PPI node will occur on the 15<sup>th</sup> of the month and the data will be publicly available on the 1<sup>st</sup> of the following month. Archiving of products from any extended mission period will be negotiated with the Project at a later date. [\[Juno began an extended mission in 2021, but at time of writing, specific delivery dates are still under negotiation.\]](#)

## 4.2 Data validation

The JADE standard data archive volume set will include all data acquired during the Juno mission. The archive validation procedure described in this section applies to volumes generated during both the cruise and prime phases of the mission.

PPI node staff will carefully examine the first archive volume that they receive that contains data from JADE to determine whether the archive is appropriate to meet the stated science objectives of the instrument. The PPI node will also review the archive product generation process for robustness and ability to detect discrepancies in the end products; documentation will be reviewed for quality and completeness.

As expertise with the instrument and data develops the JADE team may decide that changes to the structure or content of its standard data products are warranted. Should these changes be implemented, the new data product and archive volume will be subjected to a full PDS peer review, and this document will be revised to reflect the modified archive. Table 2 lists the history of all modifications to the archive structure and contents.



### 4.3 Data product and archive volume size estimates

JADE standard data products are organized into files that span 24 hours, breaking at 0h UTC. Files vary in size depending on the telemetry rate and allocation. Table 9 summarizes the expected sizes of the JADE standard products (as estimated in 2017, see table footnoted d and e) and are per version number of data. The extended mission orbits are shorter than 53 days so should have less data on average, although may have a similar volume of high-rate science data per orbit. Table 9 and are per version number of data. now includes the original estimates as of 2017 (top half for version 01 files) and the actual numbers as of late 2021 (bottom half) after the prime mission, which are much higher. The total size for prime mission is not as simple as the per orbit multiplied by number of orbits since the number of high rate science (HRS) hours per orbit, and the low rate science accumulation times used per orbit varied greatly (see footnote d).

All JADE standard data are organized by the PDS team onto a single archive volume. The data on the volume are organized into one-day subdirectories.

Table 9: Data product size and archive volume production rate (per Level (L) and version number (V))

Data Product	Production rate per day <sup>b</sup> (approx.)	Production rate per orbit <sup>a</sup> (approx.)	Size for primary mission (assuming 33 53-day orbits)
<del>Level 2</del> L2 Science V01	38 MB	2.0 GB (180 MB for HRS) <sup>c,d</sup>	64 <del>GB</del> GB <sup>d</sup>
<del>Level 3</del> L3 Science V01	239 MB	12.4 GB (1.8 GB for HRS) <sup>c,d</sup>	408 <del>GB</del> GB <sup>d</sup>
<del>Level 5</del> L5 Science	TBD	TBD	TBD
<b>Total</b>	<b>277 MB</b>	<b>14.4 GB</b>	<b>472 GB</b>
Data Product	Production rate per day <sup>b</sup> (approx.)	Production rate per orbit <sup>a</sup> (approx.)	Actual 'primary' mission size 2015 to PJ34 (2021-159)
L2 V01 Science	265 MB	13.7 GB <sup>d</sup>	198 GB
L3 V01, V02, V03 Science	2878 MB	149.0 GB <sup>d</sup>	Estimated 2336 GB <sup>e</sup>
L3 V04 <sup>e</sup> Science	1634 MB	84.6 GB <sup>d</sup>	1226 GB
<b>Total (L2+L3V04)</b>	<b>1899 MB<sup>b</sup></b>	<b>98.3 GB<sup>a</sup></b>	<b>1424 GB</b>

MB = Megabyte, GB = Gigabyte

- Per orbit value based on full day data from PJ4 to PJ5-1 day (2017 DOY 033-085 inclusive), which included 6 hours of HRS.
- Per day value is per orbit divided by 53 for this table.
- Typically 6 ~~hours~~hours<sup>d</sup> of HRS data per 53-day orbit, usually on the same day, hence the daily production rate (as an average or per orbit) is greater than the median daily production rate.
- [Update in 2021] In later orbits there was much more HRS data opportunity than the 6 hours we originally hoped for, hence values in this table (top half, from early prime mission) are significantly under estimated. Later Prime mission orbits often had about 17 hours of HRS on average, but could range over 12 to 31.5 hours for specific orbits.
- Level 3 (L3) Version 04 data was first created in late 2021 in time for the PJ34 delivery to complete the prime mission phase. Versions 01 to 03 all stopped at earlier dates (but after PJ5) so do not have a full prime mission dataset to measure.

Following receipt of JADE data by the PPI Node it is expected that fourteen working days will be required to validate and process the delivery before the data are made available on PPI web pages. New deliveries will be added to the existing volume structure to which they belong.

#### 4.4 Backups and duplicates

The PPI Node keeps three copies of each archive volume. One copy is the primary online archive, another is an onsite backup copy, and the final copy is an off-site backup copy. Once the archive volumes are fully validated and approved for inclusion in the archive, a copy of the data is sent to the National Space Science Data Center (NSSDC) for long-term archive in a NASA-approved deep-storage facility. The PPI Node may maintain additional copies of the archive volumes, either on or off-site as deemed necessary. The process for the dissemination, and preservation JADE archive volumes is illustrated in Figure 3




Figure 3: Duplication and dissemination of JADE standard archive volumes.

## 4.5 Labeling and identification

Each JADE data volume bears a unique volume ID using the last two components of the volume set ID [*PDS Standards Reference*, see §19]. For each physical medium, the volume IDs are USA\_NASA\_PDS\_??????\_mnnn, where ?????? is the VOLUME\_SET\_ID defined by the PDS and mnnn is the sequence number of the individual volume, where the *m* refers to the CODMAC level of the data. Hence the first JADE Level 2 volume has the volume ID JNOJAD\_2001, as shown in Table 10.

Table 10: PDS Data Set Volume Assignments

Level	DATA_SET_ID	VOLUME_ID
2	JNO-SW-JAD-2-UNCALIBRATED-V1.0 JNO-J/SW-JAD-2-UNCALIBRATED-V1.0	JNOJAD_2001 JNOJAD_2002
3	JNO-J/SW-JAD-3-CALIBRATED-V1.0	JNOJAD_3001

*Note: JNOJAD\_2001 is described in a separate SIS for FSW3 (2011-2014), found in that volume.*

## 5 Archive volume contents

This section describes the contents of the JADE standard product archive collection volumes, including the file names, file contents, file types, and the organizations responsible for providing the files. The complete directory structure is shown in Figure 4. All the ancillary files described herein appear on each JADE standard product volume, except where noted (highlighted yellow).




Figure 4: Archive volume directory structure  
(File names shown, not STANDARD\_DATA\_PRODUCT\_ID.)

## 5.1 Root directory

The files listed in Table 11 are contained in the (top-level) root directory, and are produced by the JADE team in consultation with the PPI node of the PDS. With the exception of the hypertext file and its label, all of these files are required by the PDS volume organization standards.

*Table 11: Root directory contents*

File	Description	Responsibility
AAREADME.TXT	This file completely describes the volume organization and contents (PDS label attached)	PPI
ERRATA.TXT	A text file containing a cumulative listing of comments and updates concerning all JADE standard products on all JADE volumes in the volume set published to date	JADE team
VOLDESC.CAT	A description of the contents of this volume in a PDS format readable by both humans and computers	PPI

## 5.2 BROWSE directory (Not for Level 2 Volume)

The BROWSE directory contains [TBD granularity] browse plots of the JADE data, split into [TBD] intervals. The contents of this directory and its subdirectories are described in Table 12.

*Table 12: BROWSE directory contents*

File	Description	Responsibility
BROWINFO.TXT	A description of the contents of this directory	PPI
[TBD]	[TBD]	

### 5.3 CALIB directory (Level 3 Volume Only)

The CALIB directory, which only exists on the CODMAC Levels 3 archives, contains a copy of the calibration plan and the ancillary data used to calibrate the JADE instrument performance. The contents of this directory are described in Table 13 (over two pages), where every file has a corresponding label (\*.LBL) file that is not listed in the table. Most files are comma separated variable (csv) files so that they are easy to open in a text editor or spreadsheet, and are based on the look up table (LUT) version uploaded to the spacecraft for a given time.

Table 13: CALIB directory contents

File	Description	Responsibility
CALINFO.TXT	A description of the contents of this directory.	PPI
ANODE_LOOK_ELC_DEFL_EQNS_Vvv.PDF	PDF of Electron sensor anode elevation look direction equations for when deflectors are on (HRS at Jupiter only). Version number vv. Azimuths are unaffected, in file: ANODE_LOOK_ELC_DEFL_NONE_Vvv.CSV	JADE team
ANODE_LOOK_ELC_DEFL_NONE_Vvv.CSV	Electron sensors anodes look directions in spacecraft azimuth and elevation when the deflectors are off. Version number vv. Lower, center and upper values (in degrees).	JADE team
ANODE_LOOK_ION_DEFL_NONE_Vvv.CSV	Ion sensor anodes look directions in spacecraft azimuth and elevation when the deflectors are off. Version number vv. Lower, center and upper values (in degrees).	JADE team
DATA_UNCERTAINTY_EQNS_Vvv.PDF	PDF of the method and equations used to generate the DATA_SIGMA values in the level 3 files. Version number vv.	JADE team
JADE_LEVEL3_Vmm_COMPARED_TO_Vnn_DESCRIPTION_Vvv.PDF	Describes the differences between Level 3 version mm and Level 3 version nn files. Document version number vv. Note: mm = nn + 1.	JADE team
JAD_L30_CALIB_LIST_nnnnn.TXT	List of JADE calibration files used to generate level 3 products, version nnnnn.	JADE team
JAD_L30_SPIICE_METAKERNEL_nn_nnn.TXT	SPIICE metakernel used to generate level 3 products, version nnnnn. (The individual SPIICE kernels can be downloaded from NAIF.)	JADE team
LUT_m_nn_COMPRESSION.CSV e.g. LUT_3_00_COMPRESSION.CSV	LUT m.nn (e.g. LUT 3.00), 16->8 bit and 32->8 bit compression tables. (No version number as tables uploaded to s/c.)	JADE team
LUT_m_nn_ENERGY_Vvv.CSV e.g. LUT_3_00_ENERGY_V01.CSV	LUT m.nn (e.g. LUT 3.00), Version number vv. Ion and electron sensors E and ΔE/E tables. (Note, LUT 3.08 is never used in flight.) <a href="#">Some LUTs have energy tables that vary with time, see LUT m nn T ENERGY Vvv files.</a>	JADE team

File	Description	Responsibility
<a href="#">LUT <i>m nn T</i> ENERGY <i>Vv</i>.CSV</a> e.g. <a href="#">LUT 4 01 A ENERGY V01.CSV</a>	<a href="#">LUT <i>m.nn</i> (e.g. LUT 3.00), Time Period <i>T</i> (= A,B,C,...), Version number <i>vv</i>. Ion and electron sensors E and <math>\Delta E/E</math> tables. LBL files contain the start/stop time of each period. If there is no time dependence during a LUT, use <a href="#">LUT <i>m nn</i> ENERGY <i>Vv</i> files.</a> </a>	<a href="#">JADE team</a>
LUT_ <i>m nn</i> _TOF_SPECIES_MAP.CSV e.g. LUT_3_00_TOF_SPECIES_MAP.CSV	LUT <i>m.nn</i> (e.g. LUT 3.00), which TOF channels map to ion species 3, 4 & 5 for a given energy step. (No version number as tables uploaded to s/c.)	JADE team
TOF_CHANNEL_TO_SECONDS_HL C_ <i>Vv</i> .CSV	Convert the 96 TOF channels numbers to seconds. Version number <i>vv</i> . (The Level 3 TOF data files contain these values.)	JADE team
TOF_CHANNEL_TO_SECONDS_HV E_ <i>Vv</i> .CSV	Convert the 128 TOF channels numbers to seconds. Version number <i>vv</i> . (For Level 2 HVE TOF.)	JADE team

## 5.4 CATALOG directory

The files in the CATALOG directory provide a top-level understanding of the Juno mission, spacecraft, instruments, and data sets in the form of completed PDS templates. The information necessary to create the files is provided by the JADE team and formatted into standard template formats by the PPI Node. The files in this directory are coordinated with PDS data engineers at both the PPI Node and the PDS Engineering Node.

*Table 14: CATALOG directory contents*

File	Description	Responsibility
CATINFO.TXT	A description of the contents of this directory	PPI
JADE_INST.CAT	PDS instrument catalog description of the JADE instrument	JADE team
JADE_DS.CAT	PDS data set catalog description of the JADE data files	Initial: JADE team Up-keep: PPI
JADE_REF.CAT	JADE-related references mentioned in other CAT files	JADE team
INSTHOST.CAT	A description of the Juno spacecraft	Juno Project
MISSION.CAT	PDS mission catalog description of the Juno mission	Juno Project
PERSON.CAT	PDS personnel catalog description of JADE team members and other persons involved with generation of JADE standard data products	JADE team
PROJ_REF.CAT	References mentioned in INSTHOST.CAT and MISSION.CAT	Juno Project



## 5.5 DATA directory

### 5.5.1 Contents

The DATA directory contains the data files produced by the JADE team. In the Level 2 archive, these files contain the raw binary instrument EDR's, organized into correct time sequence, time tagged, and edited to remove obviously bad data. In the higher level archives, the contents of the DATA directory are binary files that result from passing the corresponding Level 2 files through the processing pipeline.

The data files are of the highest quality possible. Any residual issues are documented in AAREADME.TXT and ERRATA.TXT files in the volume's root directory, or in JADE\_DS.CAT in the CATALOG directory. Users are referred to these files for a detailed description of any outstanding matters associated with the archived data.

Table 15: DATA directory contents

File	Description	Responsibility
yyyy	Subdirectories containing JADE data acquired in year yyyy	JADE team

### 5.5.2 Subdirectory structure

In order to manage files in an archive volume more efficiently the DATA directory is divided into subdirectories. The two levels of division are based on time; data are organized into yearly subdirectories, which are further divided into a number of daily sub-subdirectories. The naming convention for the yearly directories is yyyy, and for the daily directories it is yyyyddd, where ddd is the three-digit day of year. For example, all data for the year 2015 are contained below the directory 2015, with data for Jan 1 2015 UTC found in the subdirectory 2015/2015001, and so on.

'Daily' files are from UTC midnight to midnight, where the day of year at the start of each JADE record defines which day of year that record is assigned to; e.g. if a JADE record had a 30 second accumulation time starting at 2015-015T23:59:54, then the record is considered to be part of 2015-015, despite the center time being 2015-016T00:00:09, or end time being 2015-016T00:00:24. Level 2 records UTC times are always start times. Level 3 records provide start (lower), center and end (upper) UTC times separately.

### 5.5.3 Required files

A PDS label describes each file in the DATA path of an archive volume. Text documentation files have attached (internal) PDS labels and data files have detached labels. Detached PDS label files have the same root name as the file they describe but have the extension LBL. The label files contain both data file content and record structure information.

### 5.5.4 The *yyyy/yyyyddd* subdirectory

This directory contains JADE data files and their corresponding PDS labels. As shown in Table 16 and Table 17 for CODMAC levels 2 and 3 respectively, the data in these files span a time interval of one day, the particular day being identified from both the file name and the name of the parent directory. The names also contain a 2-digit version. The initial version is V01.

Table 16: CODMAC Level 2 *DATA/yyyy/yyyyddd* directory contents

Filename	Description
<i>ELECTRONS</i>	Subdirectories containing JADE electron data (all electron sensors) acquired for year/doy <i>yyyyddd</i> .
<i>ION_DIRECT_EVENTS</i>	Subdirectories containing JADE ion Direct Event data acquired for year/doy <i>yyyyddd</i> .
<i>ION_LOGICALS</i>	Subdirectories containing JADE ion Logicals data acquired for year/doy <i>yyyyddd</i> .
<i>ION_SPECIES</i>	Subdirectories containing JADE ion species data (for various ion species) acquired for year/doy <i>yyyyddd</i> .
<i>ION_TOF</i>	Subdirectories containing JADE ion time of flight data acquired for year/doy <i>yyyyddd</i> .

Table 17: CODMAC Level 3 *DATA/yyyy/yyyyddd* directory contents

Filename	Description
<i>ELECTRONS</i>	Subdirectories containing JADE electron data (all electron sensors) acquired for year/doy <i>yyyyddd</i> .
<i>ION_LOGICALS</i>	Subdirectories containing JADE ion Logicals data acquired for year/doy <i>yyyyddd</i> .
<i>ION_SPECIES</i>	Subdirectories containing JADE ion species data (for various ion species) acquired for year/doy <i>yyyyddd</i> .
<i>ION_TOF</i>	Subdirectories containing JADE ion time of flight data acquired for year/doy <i>yyyyddd</i> .

Binary data file names have the “DAT” file extension. Each file is accompanied by a PDS label (LBL) describing its contents. The labels permit the contents of most of the products to be browsed by PDS software, e.g., *NASAView*, etc.

### 5.5.4.1 The *ELECTRONS* subdirectory

This directory contains JADE data files from the electron sensors and their corresponding PDS labels. As shown in Table 18 and Table 19, the data in these files span a time interval of one day, the particular day being identified from both the file name and the name of the parent directory. The names also contain a 2-digit version. The initial version is V01. This directory exists in both CODMAC level 2 and 3 volumes.

Table 18: *DATA/yyyy/yyyyddd/ELECTRONS* directory contents for Level 2 data

Filename	Description
JAD_L20_CAL_ELC_ALL_YYYYddd_Vnn.DAT	MCP calibration mode electron counts, all 3 sensor.
JAD_L20_HRS_ELC_ALL_YYYYddd_Vnn.DAT	High Rate Science electron counts, all 3 sensors.
JAD_L20_HVE_ELC_ALL_YYYYddd_Vnn.DAT	High Voltage Engineering electron counts, all 3 sensors.
JAD_L20_LRS_ELC_ANY_YYYYddd_Vnn.DAT	Low Rate Science electron count rate, any of the 3 electron sensor.

Table 19: *DATA/yyyy/yyyyddd/ELECTRONS* directory contents for Level 3 data

Filename	Description
JAD_L30_HRS_ELC_ALL_CNT_YYYYddd_Vnn.DAT	High Rate Science electron counts per second, all 3 sensors per record.
JAD_L30_HRS_ELC_TWO_CNT_YYYYddd_Vnn.DAT	High Rate Science electron counts per second, for E060 and E180, not E300.
JAD_L30_LRS_ELC_ANY_CNT_YYYYddd_Vnn.DAT	Low Rate Science electron counts per second, just one of the 3 sensors per record (see record for which one).

[JADE-E300 was turned off in early 2016. The Level 3 JAD\\_HRS\\_ELC\\_ALL\\_CNT\\_\\* files exist for all HRS data in file versions 01, 02 and 03. However, from Level 3 Version 04, these JAD\\_HRS\\_ELC\\_ALL\\_CNT\\_\\* files will only exist for days when JADE-E300 was on.](#)

#### 5.5.4.2 The *ION\_DIRECT\_EVENTS* subdirectory

This directory contains JADE data files from ion direct events and their corresponding PDS labels. As shown in Table 20, the data in these files span a time interval of one day, the particular day being identified from both the file name and the name of the parent directory. The names also contain a 2-digit version. The initial version is V01. This is a CODMAC level 2 only directory.

Table 20: *DATA/yyyy/yyyyddd/ION\_DIRECT\_EVENTS* directory contents

Filename	Description
JAD_L20_ALL_ION_DER_YYYYddd_Vnn.DAT	Direct events (raw), for high and low rate science, calibration and high voltage engineering modes.
JAD_L20_ALL_ION_DES_YYYYddd_Vnn.DAT	Direct events (split out), for high and low rate science, calibration and high voltage engineering modes.

#### 5.5.4.3 The *ION\_LOGICALS* subdirectory

This directory contains JADE data files from ion Logicals and their corresponding PDS labels. As shown in Table 21 and Table 22, the data in these files span a time interval of one day, the particular day being identified from both the file name and the name of the parent directory. The names also contain a 2-digit version. The initial version is V01. This directory exists in both CODMAC level 2 and 3 volumes.

Table 21: *DATA/yyyy/yyyyddd/ION\_LOGICALS* directory contents for Level 2 data

Filename	Description
JAD_L20_HLC_ION_LOG_YYYYddd_Vnn.DAT	Ion Logical counts, for high and low rate science plus calibration modes.
JAD_L20_HVE_ION_LOG_YYYYddd_Vnn.DAT	Ion Logical counts, for the high voltage-engineering mode.

Table 22: *DATA/yyyy/yyyyddd/ION\_LOGICALS* directory contents for Level 3 data

Filename	Description
JAD_L30_HLS_ION_LOG_CNT_YYYYddd_Vnn.DAT	Ion Logical counts per second, for high and low rate modes.

#### 5.5.4.4 The *ION\_SPECIES* subdirectory

This directory contains JADE data files and their corresponding PDS labels. As shown in Table 23 and Table 24, the data in these files span a time interval of one day, the particular day being identified from both the file name and the name of the parent directory. The names also contain a

2-digit version. The initial version is V01. This directory exists in both CODMAC level 2 and 3 volumes.

Table 23: DATA/yyyy/yyyyddd/ION\_SPECIES directory contents for Level 2 data

Filename	Description
JAD_L20_CAL_ION_ANY_YYYYddd_Vnn.DAT	Calibration mode ion species count rate.
JAD_L20_HRS_ION_ANY_YYYYddd_Vnn.DAT	High rate science ion species counts.
JAD_L20_HVE_ION_ALL_YYYYddd_Vnn.DAT	High Voltage Engineering for all ion species counts.
JAD_L20_LRS_ION_ANY_YYYYddd_Vnn.DAT	Low Rate Science ion species count rate.

Table 24: DATA/yyyy/yyyyddd/ION\_SPECIES directory contents for Level 3 data

Filename	Description
JAD_L30_HRS_ION_ANY_CNT_YYYYddd_Vnn.DAT	High Rate Science ion species counts per second.
JAD_L30_LRS_ION_ANY_CNT_YYYYddd_Vnn.DAT	Low Rate Science ion species count per second.

#### 5.5.4.5 The ION\_TOF subdirectory

This directory contains JADE data files and their corresponding PDS labels. As shown in Table 25 and Table 26, the data in these files span a time interval of one day, the particular day being identified from both the file name and the name of the parent directory. The names also contain a 2-digit version. The initial version is V01. This directory exists in both CODMAC level 2 and 3 volumes.

Table 25: DATA/yyyy/yyyyddd/ION\_TOF directory contents for Level 2 data

Filename	Description
JAD_L20_HLC_ION_TOF_YYYYddd_Vnn.DAT	Ion time of flight counts, for high and low rate science plus calibration modes.
JAD_L20_HVE_ION_TOF_YYYYddd_Vnn.DAT	Ion time of flight counts, for the high voltage-engineering mode.

Table 26: DATA/yyyy/yyyyddd/ION\_TOF directory contents for Level 3 data

Filename	Description
JAD_L30_HLS_ION_TOF_CNT_YYYYddd_Vnn.DAT	Ion time of flight counts per second, for high and low rate modes.

## 5.6 DOCUMENT directory

The DOCUMENT directory contains a range of documentation considered either necessary or useful for users to understand the archive data set. Documents may be included in multiple forms, for example, ASCII, PDF, or HTML. PDS standards require that any documentation needed for use of the data be available in an ASCII format. “Clean” HTML is an acceptable ASCII format in addition to plain text. “Clean” HTML refers to HTML with minimal markup, and formatted in such a way as to facilitate reading in a text browser. Table 27 describes the contents of the DOCUMENT directory.

Table 27: DOCUMENT directory contents

Filename	Description	Responsibility
DOCINFO.TXT	A description of the contents of this directory	PPI
JADE_INST_PAPER.LBL	A PDS detached label for the JADE Instrument paper	JADE team
JADE_INST_PAPER.PDF	PDF version of the published paper (open access)	JADE team
JADE_INST_PAPER.HTM	The JADE instrument paper in HTML format (HTML Version 3.2)	JADE team
JADE_INST_PAPER_IMAGE_ <i>mmm</i> .JPG/PNG	Image files for JADE_INST_PAPER.HTM, some are JPG, others PNG, where <i>mmm</i> is a non-repeating incrementing number from 001 to 116.	JADE team
JADE_INST_PAPER_TABLE_ <i>mm</i> .PNG	Image files of the 18 tables from JADE_INST_PAPER.PDF, where <i>mm</i> is a non-repeating incrementing number from 01 to 18.	JADE team
JADE_FSW4_SIS_V <i>mm</i> .LBL	A PDS detached label for the SIS document, version <i>mm</i> .	JADE team
JADE_FSW4_SIS_V <i>mm</i> .DOCX	The SIS in Microsoft Word format; this was used to make the PDF – which is the file of record.	JADE team
JADE_FSW4_SIS_V01.HTM	The SIS in a simple HTML format. (Saved from Word, then hand edited. Only done for V01, future versions will use the PDF as the primary document of record, so no PNG files either.)	JADE team
JADE_FSW4_SIS_EQN_ <i>nn</i> .PNG (Only for JADE_FSW4_SIS_V01.HTM)	Image files of 6 equations (for the HTML file) from JADE_FSW4_SIS_V01.PDF, where <i>nn</i> is a non-repeating incrementing number from 01 to 06. (Note the SIS does not number equations.)	JADE team
JADE_FSW4_SIS_FIG_ <i>nn</i> .PNG (Only for JADE_FSW4_SIS_V01.HTM)	Image files of the 11 figures from JADE_FSW4_SIS_V01.PDF, where <i>nn</i> is a non-repeating incrementing number from 01 to 11. (Note that <i>nn</i> may not map to SIS figure <i>nn</i> .)	JADE team
JADE_FSW4_SIS_V <i>mm</i> .PDF	SIS in PDF format, the SIS version of record.	JADE team
JADE_FSW4_SIS_V <i>mm</i> _DIF_F_V <i>nn</i> .PDF	Tracked Changes PDF between SIS version <i>mm</i> and SIS version <i>nn</i> (usually $mm = nn + 1$ ).	JADE team

## 5.7 EXTRAS directory

The EXTRAS directory contains files which facilitate the use of the archive volume but which are not considered part of the archive itself. Table 28 contains a list of the important contents of the EXTRAS directory. [Helpful Software may be included here, rather than a SOFTWARE directory.]

Table 28: EXTRAS subdirectory contents

File	Description	Responsibility
EXTRINFO.TXT	A description of the contents of this directory	PPI
[TBD]		

## 5.8 INDEX directory

The INDEX.TAB file contains a listing of all data products on the archive volume. The index (INDEX.TAB) and index information (INDXINFO.TXT) files are required by the PDS volume standards. The format of these ASCII files is described in §6.2.5. An online and web-accessible index file will be available at the PPI Node while data volumes are being produced.

Table 29: INDEX directory contents

File	Description	Responsibility
INDXINFO.TXT	A description of the contents of this directory	PPI
INDEX.LBL	A PDS detached label that describes INDEX.TAB	JSOC
INDEX.TAB	A table listing all JADE data products on this volume	JSOC

## 6 Archive volume format

Data that comprise the JADE standard product archives will be formatted in accordance with PDS specifications [see *Planetary Science Data Dictionary*, *PDS Archiving Guide*, and *PDS Standards Reference* in §1.9].

### 6.1 Volume format

Although the JADE team does not control the volume format to be used by the PDS, it is necessary to define the format in which the data sets are to be transmitted via network from the SOC to the PPI node. This will be in the form of compressed *tar* archives, as created by the open source *gtar* program. Pathnames, in lower-case letters only, will be relative to the ROOT directory, e.g., *./data*, *./index*, etc.

### 6.2 File formats

The following section describes file formats for the kinds of files contained on archive volumes. For more information, see the *PDS Archive Preparation Guide* [see §1.9].

#### 6.2.1 Document files

Document files with a TXT extension exist in nearly all directories. They are ASCII files with embedded PDS labels. All TXT document files contain 80-byte fixed-length records; records are terminated with a carriage return (ASCII 13) and line feed character (ASCII 10) in the 79th and 80th byte, respectively. This format allows the files to be read by many operating systems, e.g., UNIX, Mac OSX, Windows, etc.

In general, documents are provided in ASCII text format. However, some documents in the DOCUMENT directory contain formatting and figures that cannot be rendered as ASCII text. Hence these documents are also given in additional formats such as hypertext, Microsoft Word, and Adobe Acrobat (PDF). Hypertext files contain ASCII text plus hypertext mark-up language (HTML) commands that enable them to be viewed in a web browser such as *Mozilla* or MS Internet Explorer. Hypertext documents may reference ancillary files, such as images, that are incorporated into the document by the web browser.

#### 6.2.2 Tabular files

Tabular files (TAB extension) exist in the DATA and INDEX directories. Tabular files are ASCII files formatted for direct reading into database management systems on various computers. Columns are fixed length, separated by commas or white space, and character fields are enclosed in double quotation marks ("). Character fields are padded with spaces to keep quotation marks in the same columns of successive records. Character fields are left justified, and numeric fields are right justified. The "start byte" and "bytes" values listed in the labels do not include the commas between fields or the quotation marks surrounding character fields. The records are of fixed length, and the last two bytes of each record contain the ASCII carriage return and line feed characters. This line format allows a table to be treated as a fixed length record file on computers



that support this file type and as a text file with embedded line delimiters on those that don't support it.

Detached PDS label files will describe all tabular files. A detached label file has the same name as the data file it describes, but with the extension LBL. For example, the file INDEX.TAB is accompanied by the detached label file INDEX.LBL in the same directory.

### 6.2.3 PDS labels

All data files in the JADE Standard Product Archive Collection have associated detached PDS labels [see the *Planetary Science Data Dictionary* and the *PDS Standards Reference* in §1.9]. These label files are named using the same prefix as the data file together with an LBL extension.

A PDS label provides descriptive information about the associated file. The PDS label is an object-oriented structure consisting of sets of “keyword = value” declarations. The object that the label refers to (*e.g.* IMAGE, TABLE, etc.) is denoted by a statement of the form:

```
^object = location
```

in which the carat character (^, also called a pointer in this context) indicates where to find the object. In a PDS label, the location denotes the name of the file containing the object, along with the starting record or byte number, if there is more than one object in the file. For example:

```
^HEADER = ("98118.TAB", 1)
^TABLE = ("98118.TAB", 1025 <BYTES>)
```

indicates that the HEADER object begins at record 1 and that the TABLE object begins at byte 1025 of the file 98118.TAB. The file 98118.TAB must be located in the same directory as the detached label file.

Below is a list of the possible formats for the ^object definition in labels in this product.

```
^object = n
^object = n <BYTES>
^object = "filename.ext"
^object = ("filename.ext", n)
^object = ("filename.ext", n <BYTES>)
```

where

- *n* is the starting record or byte number of the object, counting from the beginning of the file (record 1, byte 1),
- <BYTES> indicates that the number given is in units of bytes (the default is records),
- *filename* is the up-to-36-character, alphanumeric upper-case file name,
- *ext* is the up-to-3-character upper-case file extension,
- and all detached labels contain ASCII records that terminate with a carriage return followed by a line feed (ASCII 13<sub>10</sub>, 10<sub>10</sub>). This allows the files to be read by most computer operating systems, *e.g.*, UNIX, MacOS, MSWindows, etc.

Examples of PDS labels required for the JADE archive are shown in Appendix B.

### **6.2.4 Catalog files**

Catalog files (extension CAT) exist in the Root and CATALOG directories. They are plain text files formatted in an object-oriented structure consisting of sets of “keyword = value” declarations.

### **6.2.5 Index files**

The PDS team provides PDS index files. The format of these files is described in this SIS document for completeness.

A PDS index table contains a listing of all data products on an archive volume. For products described by a detached PDS label, the index file points to the label file, which in turn points to the data file. A PDS index is an ASCII table composed of required columns and optional columns (user defined). When values are constant across an entire volume, it is permissible to promote the value out of the table and into the PDS label for the index table.

To facilitate users’ searches of the JADE data submission, a few optional columns will be included in the index table. In particular, the file start and stop times will be included. Table 30 contains a description of the JADE archive volume index files. Index files are by definition fixed length ASCII files containing comma-delimited fields. Character strings are quoted using double quotes, and left justified in their field, followed where necessary by trailing blanks. The “Start Byte” column in Table 30 gives the location of the first byte (counting from 1) of the column within the file, skipping over delimiters and quotation marks.

### **6.2.6 Binary formats of files**

Most JADE data files are binary, where each object of each record of a file may be encoded in a different way. Each object has a DATA\_TYPE entry in the LBL (or FMT) file that describes the binary format of that object in standard PDS 3 terms. The four most common binary object types are DATE (ASCII character string of time), PC\_REAL (a float), LSB\_INTEGER (signed integer) and LSB\_UNSIGNED\_INTEGER (unsigned integer), the latter 3 being little endian.

For JADE Level 2 and 3 records, DATE objects will always be 21 characters long in ASCII, in the PDS UTC format CCYY-DDDTHH:MM:SS.sss. LSB\_INTEGER is a ‘least significant byte first’ (LSB, also known as little endian) signed integer and may be 1, 2 or 4 bytes long (the ITEM\_BYTES or if a scalar, BYTES, entry indicates which). LSB\_UNSIGNED\_INTEGER is similar, but for unsigned integers. PC\_REAL is an LSB float, and may be 4 or 8 bytes long (a single or double float respectively), which one is indicated by ITEM\_BYTES or BYTES.

There is also a bit level value indicated by BIT\_DATA\_TYPE = BOOLEAN entry, either 0 or 1.

### **6.2.7 Days without Data**

If a given day has no data of a given type, then there is simply no file present for that day. For instance, high rate science is generally only for 6 hours per orbit, and usually on the same day; therefore the vast majority of days will have no data files for high rate science data.

Table 30: Format of index files for Level 2

Column Name	Start Byte	Bytes	Description
VOLUME_ID	2	11	Contains the value JNOJAD_nnnn, where nnnn is a 4 digit number. (See Table 10)
STANDARD_DATA_PRODUCT_ID (SID)	16	19	The “type” of the data file. (See Table 7)
DATA_SET_ID	38	32	The PDS ID of the data set of which this file is a member. (See Table 10)
PRODUCT_ID	73	27	Identifier for the product [Typically filename without version number or extension]
START_TIME	102	21	Time (UTC) of the first record in the data file.
STOP_TIME	124	21	Time (UTC) of the last record in the data file.
FILE_SPECIFICATION_NAME	147	71	The full specification name of the PDS label file (including the file name and the path) that describes the product, relative to the root of the archive volume.
PRODUCT_CREATION_TIME (or CR_DATE)	220	17	Creation time of the PDS labeled data product.
PRODUCT_LABEL_MD5CHECKSUM	239	32	Labels contain product checksums, this field records the label’s checksum.

Table 31: Format of index files for Level 3

Column Name	Start Byte	Bytes	Description
VOLUME_ID	2	11	<i>Same description as from</i> Table 30
STANDARD_DATA_PRODUCT_ID (SID)	16	19	<i>Same description as from</i> Table 30
DATA_SET_ID	38	30	<i>Same description as from</i> Table 30
PRODUCT_ID	71	31	<i>Same description as from</i> Table 30
START_TIME	104	21	<i>Same description as from</i> Table 30
STOP_TIME	126	21	<i>Same description as from</i> Table 30
FILE_SPECIFICATION_NAME	149	70	<i>Same description as from</i> Table 30
PRODUCT_CREATION_TIME (or CR_DATE)	221	17	<i>Same description as from</i> Table 30
PRODUCT_LABEL_MD5CHECKSUM	240	32	<i>Same description as from</i> Table 30

## 6.2.8 Level 2 data files

The Level 2 data files are binary and have files ending in the extension .DAT. Accompanying them in the same directory are the label files with the same filename but the extension .LBL.

For example, the PDS file pairs will have the following paths in the Volume:

```
ROOT/DATA/yyyy/yyyyddd/subdir/JAD_L20_aaa_bbb_ccc_yyyyddd_Vnn.DAT
ROOT/DATA/yyyy/yyyyddd/subdir/JAD_L20_aaa_bbb_ccc_yyyyddd_Vnn.LBL
```

The format file (same filename minus the date part, but including the version number, with the extension .FMT) accompanying (and already listed within) the LBL files are usually found in the LABEL directory at the root of the volume – however it was decided to exclude this LABEL directory (and therefore exclude FMT files) as they are redundant and may be copy/pasted out of the LBL files. [FMT files are made locally for JADE file production, but do not get to the PDS.]

See section 3.1 for the explanation of JAD\_L20\_aaa\_bbb\_ccc\_yyyyddd\_Vnn, and *subdir* is the subdirectory name given in Table 16.

To save space in this document, Table 35 gives the 25-object header for the binary files for Level 2 products, which is then used throughout. This is the same for all but a few objects, e.g. PACKETID, that gives a slightly different description for each product, where text that may be different is shown in blue.

Other objects may have similar names in different product types, i.e. MIN\_SUBTRACTED\_VALUE, MCP\_NOT\_AT\_COMMAND, SWEEP\_TABLE, MCP\_COMMAND\_VALUE or DATA, but may have different sizes or be different types (i.e. float or unsigned integer, of either 2 or 4 bytes, or 1 or 3 elements) depending on which Level 2 product they are.

CODMAC Level 1 data (not in PDS, see section 3.3.1) collects counts in the DATA object, however has a MIN\_SUBTRACTED\_VALUE removed from it prior to onboard compression. For CODMAC Level 2 data here we re-add it to the DATA object, where:

$$\text{DATA}\{\text{Level 2}\} = \text{DATA}\{\text{Level 1}\} + \text{MIN\_SUBTRACTED\_VALUE}$$

Since MIN\_SUBTRACTED\_VALUE is always provided, you can work out the Level 1 DATA yourself if required.

Figure 5 shows all 43 different JADE \*\_SCI product IDs that will go in to the PDS, grouping them together in to Science and Operations. Product IDs are numerically represented in hex, and only those with PACKETIDs greater than 0x0A (16 decimal) and less than 0xA0 (160 decimal) will go in to the PDS.

Table 33 and Table 34 summarize the type of data the 43 different JADE \*\_SCI products provide over 14 file types, and how they are arranged and lossy compressed. For instance 16-8 bit means that the value onboard was collected as a two-byte unsigned integer, but lossy compressed to 1 byte for transmission to ground (lossless compression may also have occurred after this step). Although low rate science can send back electron data from any individual sensor, only one is returned due to bandwidth constraints.

Table 32 lists the 14 level 2 products and provides information on how many PDS Objects are in each record, and how many bytes are in a record. The number of records per day, however, is dependent on which products are commanded and what their ACCUMULATION\_TIME is (which may vary).

Note that the LBL/FMT files describe DATA as 2D containers (a container within a container that holds a scalar), but also show a 1D data array description that is commented out. The original telemetry stream is of 1D data blobs, but for convenience to the user we describe it in the 2D way in the FMT file, but you can use whichever description you find easier. The 1D ordering is based on c, in that the last dimension changes fastest, i.e. if a 1D array is  $x=[1, 2, 3, 4, 5, 6]$  and that should be a 3x2 array y, then:

$$y[0][0] = 1; \quad y[0][1] = 2; \quad y[1][0] = 3; \quad y[1][1] = 4; \quad y[2][0] = 5; \quad y[2][1] = 6;$$

*Table 32: Size of a record of each Level 2 product.*

<b>Product</b>	<b>Bytes per record</b>	<b>Objects per record</b>
JAD_L20_ALL_ION_DER_V01	4406	27
JAD_L20_ALL_ION_DES_V01	84	35
JAD_L20_CAL_ELC_ALL_V01	13154	30
JAD_L20_CAL_ION_ANY_V01	10054	25
JAD_L20_HLC_ION_LOG_V01	3270	25
JAD_L20_HLC_ION_TOF_V01	12358	25
JAD_L20_HRS_ELC_ALL_V01	6628	32
JAD_L20_HRS_ION_ANY_V01	838	25
JAD_L20_HVE_ELC_ALL_V01	282	25
JAD_L20_HVE_ION_ALL_V01	454	25
JAD_L20_HVE_ION_LOG_V01	170	25
JAD_L20_HVE_ION_TOF_V01	582	25
JAD_L20_LRS_ELC_ANY_V01	12384	32
JAD_L20_LRS_ION_ANY_V01	10054	25

HVENG_SCI		LOW_RATE_SCL_2 (FSW 4)		CAL_SCL_2 (FSW 4)		HIGH_RATE_SCL_2 (FSW 4)	
24	Counts	96	Rate	112	Rate	128	Counts
0x18 JAD_L20_HVE_ION_SPA_*		0x60	JAD_L20_LRS_ION_ANY_*	0x70	JAD_L20_CAL_ION_ANY_*	0x80	JAD_L20_HRS_ION_ANY_*
		LossLess	32>8	LossLess	32>8	16>8	LossLess
	97	Rate	113	Rate	129	Counts	
		0x61	JAD_L20_LRS_ION_ANY_*	0x71	JAD_L20_CAL_ION_ANY_*	0x81	JAD_L20_HRS_ION_ANY_*
		LossLess	32>8	LossLess	32>8	16>8	LossLess
	98	Rate	114	Rate	130	Counts	
		0x62	JAD_L20_LRS_ION_ANY_*	0x72	JAD_L20_CAL_ION_ANY_*	0x82	JAD_L20_HRS_ION_ANY_*
		LossLess	32>8	LossLess	32>8	16>8	LossLess
99	Rate	115	Rate	131	Counts		
	0x63	JAD_L20_LRS_ION_ANY_*	0x73	JAD_L20_CAL_ION_ANY_*	0x83	JAD_L20_HRS_ION_ANY_*	
	LossLess	32>8	LossLess	32>8	16>8	LossLess	
100	Rate	116	Rate	132	Counts		
	0x64	JAD_L20_LRS_ION_ANY_*	0x74	JAD_L20_CAL_ION_ANY_*	0x84	JAD_L20_HRS_ION_ANY_*	
	LossLess	32>8	LossLess	32>8	16>8	LossLess	
101	Rate	117	Rate	133	Counts		
	0x65	JAD_L20_LRS_ION_ANY_*	0x75	JAD_L20_CAL_ION_ANY_*	0x85	JAD_L20_HRS_ION_ANY_*	
	LossLess	32>8	LossLess	32>8	16>8	LossLess	
102	Rate	118	Rate	134	Counts		
	0x66	JAD_L20_LRS_ION_ANY_*	0x76	JAD_L20_CAL_ION_ANY_*	0x86	JAD_L20_HRS_ION_ANY_*	
	LossLess	32>8	LossLess	32>8	16>8	LossLess	
103	Rate	119	Rate	135	Counts		
	0x67	JAD_L20_LRS_ION_ANY_*	0x77	JAD_L20_CAL_ION_ANY_*	0x87	JAD_L20_HRS_ION_ANY_*	
	LossLess	32>8	LossLess	32>8	16>8	LossLess	
25	Counts	105	Counts	121	Counts	137	Counts
0x19	JAD_L20_HVE_ION_TOF_*	0x69	JAD_L20_HLC_ION_TOF_*	0x79	JAD_L20_HLC_ION_TOF_*	0x89	JAD_L20_HLC_ION_TOF_*
		LossLess	32>8	LossLess	32>8	16>8	LossLess
28	Counts	108	Counts	124	Counts	140	Counts
0x1C	JAD_L20_HVE_ION_LOG_*	0x6C	JAD_L20_HLC_ION_LOG_*	0x7C	JAD_L20_HLC_ION_LOG_*	0x8C	JAD_L20_HLC_ION_LOG_*
		LossLess	32>8	LossLess	32>8	16>8	LossLess

31	DE Word	111	DE Word	127	DE Word	143	DE Word
0x1F	JAD_L20_ALL_ION_DER_*	0x6F	JAD_L20_ALL_ION_DER_*	0x7F	JAD_L20_ALL_ION_DER_*	0x8F	JAD_L20_ALL_ION_DER_*
	JAD_L20_ALL_ION_DES_*		JAD_L20_ALL_ION_DES_*		JAD_L20_ALL_ION_DES_*		JAD_L20_ALL_ION_DES_*

30	Counts	104	Rate	126	Counts	142	Counts
0x1E JAD_L20_HVE_ELC_ALL_*		0x68	JAD_L20_LRS_ELC_ANY_*	0x7E JAD_L20_CAL_ELC_ALL_*	0x8E JAD_L20_HRS_ELC_ALL_*		
		LossLess	32>8				
	106	Rate	107			Rate	
	0x6A	JAD_L20_LRS_ELC_ANY_*					
	LossLess	32>8					
	0x6B	JAD_L20_LRS_ELC_ANY_*					
	LossLess	32>8					

**Key**

DPID in decimal      Data Units

**PACKETID/DPID (in Hex)**  
PDS file name

Bottom line lists data bit compression methods used (if any)

16>8    LossLess    32>8

Operations    Science

**\*.out / binary**

Note: LossLess compression is a commanding switch, and could be turned off to give 0% compression. However the 16>8 bit and 32>8 bit look up tables are always on.

Figure 5: 'Periodic' table comparing the different JADE products, giving their packet ID number in hex (DPID in figure key, see entry in Table 35), decimal, the PDS name fragment and information on what type of compression was used, and whether it records counts per accumulation or count rates.

PDS FMT Name	TLM Spreadsheet Name	# Bytes	Data Type	Packet ID				0x80-0x87			0x88-0x8F		0x90-0x9F		0xA0-0xAF		
				0x8E	0x68 0x6A 0x6B	0x7E	0x1E	0x1F 0x6F 0x7F 0x8F	0x1F 0x6F 0x7F 0x8F	0x82 0x63 0x64 0x65 0x66 0x67	0x61 0x62 0x63 0x64 0x65 0x66 0x67	0x18	0x79 0x89	0x19	0x6C 0x7C 0x8C	0x1C	
				JAD_L20_HRS_ELC_ALL	JAD_L20_HRS_ELC_ANY	JAD_L20_CAL_ELC_ALL	JAD_L20_HVE_ELC_ALL	JAD_L20_ALL_ION_DER	JAD_L20_ALL_ION_DES	JAD_L20_HRS_ION_ANY	JAD_L20_HRS_ION_ANY	JAD_L20_CAL_ION_ANY	JAD_L20_HVE_ION_ALL	JAD_L20_HLC_ION_TOF	JAD_L20_HVE_ION_TOF	JAD_L20_HLC_ION_LOG	JAD_L20_HVE_ION_LOG
SYNC	Sync Pattern	4	uint32[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DPID_COUNT	DPID Count (Source Sequence Count)	1	uint8[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
COMPRESSION	Lossless Compression Status	1	uint8[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
IDPLENGTH	IDP Length	2	uint16[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
PACKETID	Packet ID (DPID)	1	uint8[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
FLIGHT_OR_STL	Added on Ground (Placed to byte pack)	1	uint8[1]	^	^	^	^	^	^	^	^	^	^	^	^	^	^
PACKET_MODE	Added on Ground	1	int8[1]	^	^	^	^	^	^	^	^	^	^	^	^	^	^
PACKET_SPECIES	Added on Ground	1	int8[1]	^	^	^	^	^	^	^	^	^	^	^	^	^	^
TIMESTAMP_WHOLE	Timestamp (Whole Second)	4	uint32[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
TIMESTAMP_SUB	Timestamp (Subsecond)	2	uint16[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
ACCUMULATION_TIME	Accumulation Time	2	uint16[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
TABLES_VERSION	LUT Version (float version of Hex)	4	float[1]	✓	✓	✓	^	✓	✓	✓	✓	✓	^	✓	✓	✓	^
FSW_VERSION	FSW Version (float version of Hex)	4	float[1]	✓	✓	✓	^	✓	✓	✓	✓	✓	^	✓	✓	✓	^
ACCUM_TRUNCATION	Accum Truncation	1	uint8[1]	✓	✓	✓	^	✓	✓	✓	✓	✓	^	✓	✓	✓	^
DATA_UNITS	Added on Ground (Placed to byte pack)	1	uint8[1]	^	^	^	^	^	^	^	^	^	^	^	^	^	^
COMPRESSION_RATIO	Added on Ground	4	float[1]	^	^	^	^	^	^	^	^	^	^	^	^	^	^
UTC	Added on Ground	21	char[21]	^	^	^	^	^	^	^	^	^	^	^	^	^	^
LEAP_SECOND_VERSION	Added on Ground (Placed to byte pack)	1	uint8[1]	^	^	^	^	^	^	^	^	^	^	^	^	^	^
SCLKSCET_VERSION	Added on Ground	2	int16[1]	^	^	^	^	^	^	^	^	^	^	^	^	^	^
ISSUES (bit flags)	Added on Ground	4	uint32[1]	^	^	^	^	^	^	^	^	^	^	^	^	^	^
MIN_SUBTRACTED_VALUE	Min Subtracted Value	4	uint32[1]	✓	✓	✓	^	^	^	✓	✓	✓	^	^	^	✓	^
	Min Subtracted Value	4	float[1]	✓	✓	✓	^	^	^	✓	✓	✓	^	^	^	✓	^
MCP_NOT_AT_CMD	MCP not at Commanded	1	uint8[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SWEEP_TABLE	Sweep Table	1	uint8[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
MCP_CMDD_VAL	MCP Commanded, or, Ion MCP Commanded	2	uint16[1]	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
MCP_NOT_AT_CMD	E060, E180 and E300 MCPs not at Commanded	3	uint8[3]	✓	✓	✓	^										
SWEEP_TABLE	E060, E180 & E300 Sweep Tables	3	uint8[3]	✓	✓	✓	^										
MCP_CMDD_VAL	E060, E180 & E300 MCPs Commanded	6	uint16[3]	✓	✓	✓	^										
DATA	Array Data B[1]b	Depends	uint16	✓	✓	✓	✓			✓	✓	✓	✓	✓	✓	✓	✓
	Array Data B[k]b	Depends	uint32	✓	✓	✓	✓										
	Array Data B[k]b	Depends	float	✓	✓	✓	✓										
MAG_TIME_DIR	mag_time_direction	1	uint8[1]	✓	✓	✓	✓										
MAG_LOOK_DIR	mag_anode	1	uint8[1]	✓	✓	✓	✓										
MAG_FIRST_DFL	first_dfl	2	uint16[1]	✓	✓	✓	✓										
MAG_ELEVATION	elevation_sign + elevation_angle	1	int8[1]	✓	✓	✓	✓										
MAG_TIME_LATENCY	mag_time_latency	1	uint8[1]	✓	✓	✓	✓										
MAG_TIMESTAMP_WHOLE	mag_whole_seconds or Mag_time_whole	4	uint32[1]	✓	✓	✓	✓										
MAG_TIMESTAMP_SUB	Mag_time_sub	2	uint16[1]	✓	✓	✓	✓										
MAG_COUNT_VALID	Mag_count_valid	1	uint8[1]	✓	✓	✓	✓										
MAG_COUNT_INVALID	Mag_count_invalid	1	uint8[1]	✓	✓	✓	✓										
MAG_VECTOR	mag_x+mag_y+mag_z	12	int32[3]	✓	✓	✓	✓										
BACKGROUND_COUNTS	Background Counter	4	uint32[1]	Inc. in DATA	✓	Inc. in DATA	Inc. in DATA										
ESENSOR	Added on Ground	2	uint16[1]	✓	✓	✓	✓										
DE_COI_SUB_SEQ_COUNT	Collection sub-sequence count	2	uint16[1]	✓	✓	✓	✓										
DATA[]	DataBlob Padded to Fixed Size	4332	uint16[2166]	✓	✓	✓	✓										
DE_SIZE	Added on Ground	2	uint16[1]	✓	✓	✓	✓										
DE_BAD	Added on Ground	1	uint8[1]	✓	✓	✓	✓										
DE_EVENT0_BOUNDARY1_MARKER2	Added on Ground	1	uint8[1]	✓	✓	✓	✓										
DE_SWEEP_NUMBER	Added on Ground	2	uint16[1]	✓	✓	✓	✓										
DE_ESA_STEP	Added on Ground	1	uint8[1]	✓	✓	✓	✓										
DE_DFL_STEP	Added on Ground	1	uint8[1]	✓	✓	✓	✓										
DE_TOF	Added on Ground	2	uint16[1]	✓	✓	✓	✓										
DE_ANODE_ID	Added on Ground	1	uint8[1]	✓	✓	✓	✓										
DE_QUALITY_FLAG_2	Added on Ground	1	uint8[1]	✓	✓	✓	✓										
DE_QUALITY_FLAG_1	Added on Ground	1	uint8[1]	✓	✓	✓	✓										
DE_QUALITY_FLAG_0	Added on Ground	1	uint8[1]	✓	✓	✓	✓										

Figure 6: Breaking out the JADE Level 2 products in to the different Objects to allow similarities to be drawn.

There are a total of 14 products, compressed here for readability. A green shaded ^ mark values added on the ground, red shaded ones means MISSING\_CONSTANTS were added. Electron products include a background anode; only LRS data splits it out from the DATA object.

Table 33: Data Collection types by dimensions.

One spin is 48 E-Spin-Phase Sectors or 78 I-Spin-Phase Sectors.

Ion species may be commanded to return 1-8 species for HRS/LRS/CAL modes, but 3 is typical.

Electron background anodes have been ignored for this table.

A full ion energy sweep is of 64 steps, however each packet contains either the top 32 or bottom 32 only.

	HRS	LRS	MCP CAL	HVE
<b>Electrons</b>	3 Sensors 64 Energies 48 Anodes (Same as CAL)	1 Sensor 64 Energies 48 E-Spin-Phase	3 Sensors 64 Energies 48 Anodes (Same as HRS)	3 Sensors 1 Energy 48 Anodes
<b>Ion Species</b>	1-8 Species 32 Energies 12 Anodes	1-8 Species 32 Energies 78 I-Spin-Phase		8 Species 1 Energy 12 Anodes
<b>Ion TOF</b>	32 Energies 96 TOF			1 Energy 128 TOF
<b>Ion Logicals</b>	32 Energies 25 Logs			1 Energy 25 Logs
<b>Ion DE</b>	DE Words			

Table 34: Data Collection types by units (green), lossy bit compression (red) and number of Level 2 files (purple).

	HRS	LRS	MCP CAL	HVE
<b>Electrons</b>	1 File Counts 16>8 bit	3 Files Rate 32>8 bit	1 File Counts 32>8 bit	1 File Counts None
<b>Ion Species</b>	1 File Counts 16>8 bit	1 File Rate 32>8 bit	1 File Rate 32>8 bit	1 File Counts None
<b>Ion TOF</b>	1 File Counts 16>8 bit	1 File Counts 32>8 bit	1 File Counts 32>8 bit	1 File Counts None
<b>Ion Log</b>	1 File Counts 16>8 bit	1 File Counts 32>8 bit	1 File Counts 32>8 bit	1 File Counts None
<b>Ion DE</b>	1 File DE Word None	1 File DE Word None	1 File DE Word None	1 File DE Word None

Counts = Total Counts,

Rate = Count rates (normalized by number of views)



The following table (over 4 pages) describes the header that is identical for all the following data products. The names and word type (int/float/etc.) for all level 2 data is also summarized in Figure 6. Any text in *red italics* is a note that is not in the LBL nor FMT file, while any text in **blue boldface** may change depending on the product (usually just the product ID or species number). This color system will apply for format tables throughout the rest of section 6.2.

Table 35: Format of Level 2 data record header for all binary data files.

Byte	Bit	Length (bits)	Name	Description
1	0	32	SYNC	JADE Sync Pattern for IDP packets. Hex value = 0xFAF33403, Decimal = 4210242563
5	0	8	DPID_COUNT	DPID Count (Source Sequence Count) Count of the number of times this product has been generated since the startup (or reset) of the generating application (Boot Program or Science Program). This count resets to 0 upon entry to the modes of BOOT, LVENG, HVENG, LOW_RATE_SCI, MCP_CAL_SCI, HI_RATE_SCI, LOW_RATE_SCI2, MCP_CAL_SCI2, HI_RATE_SCI2. Note: starts with 0, increments by 1, eventually rolls over at 255.
6	0	8	COMPRESSION	Lossless Compression Status. Indicates whether the data (non-header) segment of the IDP packet (IDP Data) was lossless compressed. 0 = Not Compressed <b>1 = Compressed</b> <i>Last line only shown if the packet could be compressed.</i>
7	0	16	IDPLENGTH	IDP Length, Byte Length of the IDP packet. Uncompressed size for this product should be <b>416</b> .
9	0	8	PACKETID	Packet ID (DPID), Data Product Identifier <i>Followed by Name of Packet ID for each product, e.g.</i> <b>High Rate Science - Ion Species Histogram</b> <b>Each packet is one of the following ion species:</b> <b>SP0, species 0, PACKETID = 128 /* 0x80 */</b> <b>SP1, species 1, PACKETID = 129 /* 0x81 */</b> <b>SP2, species 2, PACKETID = 130 /* 0x82 */</b> <b>SP3, species 3, PACKETID = 131 /* 0x83 */</b> <b>SP4, species 4, PACKETID = 132 /* 0x84 */</b> <b>SP5, species 5, PACKETID = 133 /* 0x85 */</b> <b>SP6, species 6, PACKETID = 134 /* 0x86 */</b> <b>SP7, species 7, PACKETID = 135 /* 0x87 */</b>
10	0	8	FLIGHT_OR_STL	In Flight data, or STL (ground EM tests): 0 = In flight, from JADE on Juno (via FEI) 1 = On ground, from STL tests (via FEI) 2 = On ground, from SwRI tests (not FEI) 255 = Unknown

Byte	Bit	Length (bits)	Name	Description
11	0	8	PACKET_MODE	<p>Packet Mode, describes type of data telemetry.</p> <ul style="list-style-type: none"> <li>-2 = HSK / Housekeeping Engineering</li> <li>-1 = HVE / High Voltage Engineering</li> <li>0 = CAL / MCP Calibration Science</li> <li>1 = LRS / Low Rate Science</li> <li>2 = HRS / High Rate Science</li> <li>127 = Unknown</li> <li>254 = Wrong - but HSK, see below.</li> <li>255 = Wrong - but HVE, see below.</li> </ul> <p>(Note, this could also be calculated via PACKETID.) If you have 254 or 255 then your code is incorrect, check you read a signed byte, rather than unsigned.</p>
12	0	8	PACKET_SPECIES	<p>Packet Species, describes type of plasma data.</p> <ul style="list-style-type: none"> <li>-1 = electrons</li> <li>0 = ion species 0, SP0</li> <li>1 = ion species 1, SP1</li> <li>2 = ion species 2, SP2</li> <li>3 = ion species 3, SP3</li> <li>4 = ion species 4, SP4</li> <li>5 = ion species 5, SP5</li> <li>6 = ion species 6, SP6</li> <li>7 = ion species 7, SP7</li> <li>8 = Not Used</li> <li>9 = All ions</li> <li>127 = Unknown</li> <li>255 = Wrong - but electrons, see below.</li> </ul> <p>If you have 255 then your code is incorrect, check you read a signed byte, rather than unsigned.</p>
13	0	32	TIMESTAMP_WHOLE	<p>Timestamp (Whole Second).</p> <p>Timestamp (whole second) of the data for this packet when collection began.</p> <p>This is sometimes referred to as Mission Elapsed Time (MET) and is Referenced from 2000-001T12:00:00.000 UTC, but 1 tick is not exactly 1 S.I. second. See UTC object for corrected converted time. Note: Spacecraft Clock = TIMESTAMP_WHOLE:TIMESTAMP_SUB</p>
17	0	16	TIMESTAMP_SUB	<p>Timestamp (Subsecond).</p> <p>Timestamp subsecond of the data for this packet when collection began.</p> <p>Unit: Microseconds scaled to 16 bits. Note: Spacecraft Clock = TIMESTAMP_WHOLE:TIMESTAMP_SUB</p>

Byte	Bit	Length (bits)	Name	Description
19	0	16	ACCUMULATION_TIME	Accumulation Time. Number of seconds over which the data in this product was collected (Science Program). <i>NOTE: This is not the collection period of a given energy step at a given angle, etc., that would be used to convert to counts/second. It is the time it took to collect all the data measured within this record.</i>
21	0	32	TABLES_VERSION	Look Up Tables (LUT) version used onboard. All tables are combined (compression, sweeping, macros, etc.) onboard in to a large image. This is the image number, or table version. Number should be to 2 decimal places.
25	0	32	FSW_VERSION	Flight Software version used. Number should be to 2 decimal places.
29	0	8	ACCUM_TRUNCATION	Accumulation Truncation, Whether commanded accumulation time ended early. 0 = Nominal 1 = Early 255 = Unknown
30	0	8	DATA_UNITS	Science Data could be total counts (per accumulation) or a rate, normalized to counts per view. 0 = All counts in the accumulation period (int) 1 = All counts divided by number of views (float) 2 = Counts per second (float) 255 = Not appropriate for this dataset, or Unknown.
31	0	32	COMPRESSION_RATIO	Data compression ratio of data blob when it was transmitted to Earth: Ratio = {Uncompressed size}/{Compressed size} This is the compression due to the lossless scheme, and does not include any lossy compression which may have occurred prior to it, such as the 32-bit to 8-bit or 16-bit to 8-bit look up tables that are often used prior to the lossy compression. A value of 1 means there was no lossless data compression, i.e. it was turned off, and object COMPRESSION should equal 1.
35	0	168	UTC	UTC timestamp, of format yyyy-dddTHH:MM:SS.sss where yyyy = year, ddd = day of year, HH = hour, MM = minute, SS.sss = decimal seconds to millisecond resolution. Value calculated via SPICE from spacecraft clock time, {TIMESTAMP_WHOLE}:{TIMESTAMP_SUB}
56	0	8	LEAP_SECOND_VERSION	The NAIF SPICE kernel for lsk used to generate UTC. The lsk (leap second kernels) files are used in time conversions and have filenames naifnnnn.tls, where is the lsk version number (with leading zeros).

Byte	Bit	Length (bits)	Name	Description
57	0	16	SCLKSCET_VERSION	<p>The NAIF SPICE kernel for sclk used to generate UTC. The JUNO sclk files are used to convert the spacecraft clock timestamps to UTC time, and all have filenames JNO_SCLKSCET.nnnnn.tsc, where nnnnn is the SCLKSCET version number (with leading zeros and positive). Each kernel has a reconstructed and predicted part for it's values, typically any time after the last row of the SCLK01_COEFFICIENTS_61999 table is predicted. If TIMESTAMP_WHOLE:TIMESTAMP_SUB is in the predicted part then SCLKSCET_VERSION will be negative, the absolute value would be the version number. If a later SCLKSCET kernel version is used the UTC time will likely be different. If TIMESTAMP_WHOLE:TIMESTAMP_SUB is in the reconstructed region the number will be positive (equal to the version number) and will not vary with later kernels. e.g. If SCLKSCET_VERSION = -17 then kernel JNO_SCLKSCET.00017.tsc was used to convert to UTC, but it's a predicted UTC time. If SCLKSCET_VERSION = 18 then kernel JNO_SCLKSCET.00018.tsc was used to convert to UTC, and it's a reconstructed UTC time that will not change with later SCLKSCET kernel versions. Within the PDS archive this value should always be positive.</p>
59	0	32	ISSUES	<i>The ISSUES description is far too long to fit in this table, see Table 38 instead.</i>
63	0	32	MIN_SUBTRACTED_VALUE	<p>Minimum Subtracted Value. Minimum value subtracted from every element in the array data blob for transmission to Earth. (This has already been added back to the DATA.)  <i>If DATA_UNITS = 1, this is followed by:</i>  <b>Note: the units are rates (counts per views), are floats rather than integers, and are fractions of 1/512.</b></p>
67	0	8 or 24	MCP_NOT_AT_COMMAND	<p><i>See Table 36 and Table 37 for details of these final three header objects.</i>  Table 36 for ions and LRS electrons,  or Table 37 for other electron products.</p>
68 or 70	0	8 or 24	SWEEP_TABLE	
69 or 73	0	16 or 48	MCP_COMMAND_VALUE	

Table 36: Format of Level 2 data record sub-header for all binary data files of one sensor.

Byte	Bit	Length (bits)	Name	Description
67	0	8	MCP_NOT_AT_COMMANDDED	MCP not at Commanded flag. This denotes whether the MCP voltage was reduced during the data collection. 0 = Nominal 1 = Reduced 255 = Unknown
68	0	8	SWEEP_TABLE	Which sweep table does the <b>ion</b> sensor have, <b>0-3</b> .
69	0	16	MCP_COMMANDED_VALUE	<b>Ion</b> MCPs Commanded raw DAC value.

Table 37: Format of Level 2 data record sub-header for all binary data files of all electron sensors.

Byte	Bit	Length (bits)	Name	Description
67	0	24	MCP_NOT_AT_COMMANDDED	MCP not at Commanded flag. This denotes whether the MCP voltage was reduced during the data collection. (The three values are for the MCPs of E060, E180 and E300 respectively.) 0 = Nominal 1 = Reduced 255 = Unknown
70	0	24	SWEEP_TABLE	Which sweep table do the electron sensors have, 0-2. (The three values are for the MCPs of E060, E180 and E300 respectively.)
73	0	48	MCP_COMMANDED_VALUE	Electron MCPs Commanded raw DAC value. (The three values are for the MCPs of E060, E180 and E300 respectively.)

The ISSUES object description is far too large to fit in the tables above, so is given here in two column format and a reduced font size over two pages (with some line breaks from the FMT/LBL file contents altered/removed). Reading the FMT/LBL file itself may be clearer.

*Table 38: Full description of the ISSUE flag in the FMT/LBL files.*

Issues or potential issues in this data record.

These are issues that can be identified within the JADE packet of data itself without any external information. e.g. timing issues due to the MAG time stutter, or any voltage pulsing, would not be included as there are no indicators to them within this JADE packet.

[For a more comprehensive list of potential issues from internal and external sources please see the Level 3 data.]

Level 2 issues of this JADE packet are flagged by individual bits, and several may be hit. If no issues are flagged then this 4-byte unsigned integer is zero. A value of 4294967295 is the MISSING\_CONSTANT and means that the issue status is currently unknown.

All bits at 0 implies all is okay as seen by this packet. If a bit is set to 1 then that bit is flagged, otherwise it is set to zero and unflagged.

The bits are set as followed, grouped in to seriousness:

Not very serious issues for doing science:

Bit 0 = UTC time is predicted, yet to be finalized.

Bit 1 = Position/Orientation values predicted, yet to be finalized. Level 3 (and above) data only.

Bit 2 = TABLES\_VERSION object was altered on the ground to accurately reflect a 'commanded parameter update' outside the initial per-orbit commands JADE is returning.  
[If changed, the original downlinked TABLES\_VERSION value can be found by cross-referencing the PARAM\_TABLE\_VER object in the JAD\_L20\_HSK\_ALL\_SHK files. Note here the PARAM\_TABLE\_VER value is given as a unsigned integer of Hex Major-Middle-Minor, such that a value of 770 decimal is in hex 0x302, meaning Table Version 3.02 ]

Bit 3 = FSW\_VERSION 4.00 LRS/CAL Ion Species bug fixed on the ground by adjusting TIMESTAMP\_WHOLE, TIMESTAMP\_SUB, and ACCUMULATION\_TIME based on cross-referencing JADE commanding.

Bit 4 = LRS/CAL Ion Species record with unobserved look directions (views) populated using views from neighboring record. See Bit 12 for uncorrected/unpopulated description.  
(Only possible if ACCUMULATION\_TIME = 30.)

Bit 5 = TIMESTAMP\_WHOLE/SUB adjusted on the ground to mitigate any Juno time stutter affects.  
[Other TIMESTAMPS are susceptible to the onboard time stutter too, but only the JADE packet TIMESTAMP\_WHOLE/SUB is tracked here.]

Bit 6 = Currently unused.

Bit 7 = Warning, a leap second occurs during the accumulation period.

Data slightly different than expected, but can be used for science with a little extra coding:

Bit 8 = ACCUM\_TRUNCATION object flagged.

Bit 9 = Electron (HRS/LRS/CAL) MAG objects are not tracked, are either zeros or MISSING\_CONSTANT.  
[LRS and CAL did not have MAG objects prior to FSW\_VERSION 4.10, therefore those MAG objects here are set to MISSING\_CONSTANT when FSW\_VERSION < 4.10.]

Bit 10 = TIMESTAMP\_WHOLE/SUB affected by a Juno onboard time stutter, JADE reported timestamp is likely 1 whole tick too large.  
[Other TIMESTAMPS are susceptible to the onboard time stutter too, but only the JADE packet TIMESTAMP\_WHOLE/SUB is tracked here.]

Bit 11 = Currently unused.

Bit 12 = LRS/CAL Ion Species record potentially has unobserved look directions (spin phase sectors or views) present in the data, meaning the record may not contain data for a full 4pi steradians field-of-view.  
Unobserved look directions have zero counts per view (or counts per second) in the data, although an observed look direction may also have zero counts if no ions were measured. Therefore there is a potential confusion over zero measured counts or simply unmeasured. e.g. if the spin period is 30.7 seconds, then not all of the 78 spin phase sectors will be sampled in 30 seconds. (Unobserved views are only possible if ACCUMULATION\_TIME <= 30.)  
See the JADE SIS for more information.

Bit 13 = At least one anode is blanked.

See SIS document for further information.

Bit 14 = FSW\_VERSION 4.00 LRS/CAL Ion Species bug warning:  
Not fixed as yet - when fixed it will become bit 3 of ISSUES instead.

Level 2 data only when FSW\_VERSION = 4.00, ACCUMULTION\_TIME object is MISSING\_CONSTANT.

Also, TIMESTAMP\_WHOLE:TIMESTAMP\_SUB is the end of the packet rather than the usual start, see TIMESTAMP\_WHOLE object for more details.  
[Only affects data from 2015-089 to 2015-115.]

Bit 15 = Electron Anodes Reversed.

Level 2 data only when FSW\_VERSION < 4.10 and only electron packets. Electron anodes are reversed in order and need to be remapped, however electron Spin Phase data (LRS data) cannot be remapped. See the SIS document for more information about this.  
[Affects all electron data 2011 to 2015-115.]

Data very different than expected, may not be suitable for science - use with extreme caution.

Bit 16 = Data is not from flight instrument on Juno, see FLIGHT\_OR\_STL object.

Bit 17 = MCP\_NOT\_AT\_COMMANDED object flagged. Electron HRS/CAL/HVE packets use all three electron sensors and therefore have three MCP\_NOT\_AT\_COMMANDED values per packet. Setting this flag means at least one of those three mcps is not at its commanded value.

Bit 18 = Data includes some JADE-E300 sensor data. (Only flagged for HRS, LRS, CAL and HVE data.) E300 has a high voltage power supply issue and reported energy steps may be incorrect. If E300 is off but still reported in the data product, it may be zeros of fill values.

Bit 19 = Ion packet abruptly truncated. This packet should not be used. It had an ACCUMULATION\_TIME = 1, ACCUM\_TRUNCATION = 1 and the DATA object is all zeros, with a timestamp that matches an earlier valid packet that was not truncated and has non-zero DATA. e.g. TOF and LOG example in level 2 data at TIMESTAMP\_WHOLE of 495879710 (UTC 2015-261).

Bit 20 = MCP Dipping Triggered, in one or more sensors. If the sensor measures excessive counts, it temporarily lowers the MCP voltage to reduce the number of counts and protect the sensor. The MCP\_NOT\_AT\_COMMANDED object is also flagged (Bit 17 in ISSUES) since the MCP is no longer at the commanded voltage.

For HRS/CAL/HVE electrons (datasets where multiple sensors are on) it is possible that one sensor has been dipped, but the others are not and still providing good data. (First MCP dip was HRS electrons, 2017-350.)

Bit 21 = MCP Dipped sensor's DATA set to fill values. If MCP dipping has triggered (Bit 20 of ISSUES) then: DATA and BACKGROUND objects (and their \*\_SIGMAS) have been replaced with MISSING\_CONSTANT values. (Never used for Level 2 data, which has the counts as measured in the dipped state.)

In addition, Bit 17 of the ISSUES object (i.e. MCP\_NOT\_AT\_COMMANDED object = 1) is set to zero, and, if it exists, the MCP\_NOT\_AT\_COMMANDED object itself is changed (from 1) to be 0 for the offending sensor(s). If the DATA object contains data from multiple sensors (HRS/CAL/HVE electrons) then only the elements of the DATA object for the dipped sensor are set to MISSING\_CONSTANT (as identified by the MCP\_NOT\_AT\_COMMANDED value for each sensor (prior to setting them to 0)).

[See Bit 22 for a similar flag.]

Bit 22 = 1 or more ELC sensor DATA set to fill values. Affects only electron HRS/CAL/HVE products (i.e. products that use multiple sensors), and generally only when starting that mode.

When switching to HRS/CAL/HVE from LRS, one JADE-E sensor is already on, and the other(s) have to turn on, then it takes some time for that sensor to reach the commanded voltage. For a given record, MCP\_NOT\_AT\_COMMANDED = 0 for one sensor but is still = 1 for others. That is one sensor is taking valid science but the other(s) are not there yet and for those sensors: DATA and BACKGROUND objects (and their \*\_SIGMAS) have been replaced with MISSING\_CONSTANT values. (Never used for Level 2 data, which has the counts as measured in the dipped state.)

In addition, Bit 17 of the ISSUES object (i.e. MCP\_NOT\_AT\_COMMANDED object = 1) is set to zero, and, if it exists, the MCP\_NOT\_AT\_COMMANDED object itself is changed (from 1) to be 0 for the offending sensor(s). Only the elements of the DATA object for the original MCP\_NOT\_AT\_COMMANDED = 1 sensor(s) (prior to setting them to 0) are set to MISSING\_CONSTANT. [Bits 21 and 22 are essentially the same feature caused by an mcp voltage not being at the commanded value, but the reason why this is the case is different. The treatment is identical for both Bit 21 and Bit 22.]

Bit 23 = Currently unused.

Bit 24 = Currently unused.

Bit 25 = Currently unused.

Bit 26 = Currently unused.

Bit 27 = Currently unused.

Bit 28 = Currently unused.

Bit 29 = Currently unused.

Bit 30 = Currently unused.

Bit 31 = Reserved for MISSING\_CONSTANT use.

Each bit has a decimal value of  $2^{\{\text{bit number}\}}$ , and the Issues flag is the sum of  $2^{\{\text{flagged bit numbers}\}}$ . For instance, if this ISSUES flag = 131329, then in binary that value is 0000000000001000000010000001 showing bits 17, 8 and 0 are flagged.

[If a currently unused bit is set, please check the latest LBL file for this product that you can find to see if it now has a definition.]

### 6.2.8.1 Electron Data

JADE-E consists of three electron sensors. For high rate science, calibration and high voltage engineering; data from all three sensors are returned in each record. For low rate science, only one sensor of the three is on at any given time, therefore just that one sensor's data is returned per record. Each electron sensor has 16 anodes and 1 background anode. The following figure provides the look directions and numbering of the different anodes (excluding background ones) from 0 to 47.




Figure 7: JADE-E Anodes vs. Look Directions (see Table 39 for the values).

For FSW4.00 only (or any FSW3) with anodes reversed (see ISSUES flag), you need to reorder the data packets of 51 bins to get sequential azimuth coverage, using this anode order:

```
{15, 14, 13, 12, 11, 10, 9, 8, 7, 6, 5, 4, 3, 2, 1, 0, /* E060 */
 31, 30, 29, 28, 27, 26, 25, 24, 23, 22, 21, 20, 19, 18, 17, 16, /* E180 */
 47, 46, 45, 44, 43, 42, 41, 40, 39, 38, 37, 36, 35, 34, 33, 32, /* E300 */
 48, 49, 50 /* Background anodes remain at end*/ };
```

Table 39 maps bins to the sensor anodes and look directions for CAL, HRS, HVE and LRS, and should be used as the guide to convert to field of view directions for level 3 data. LRS data arrays are returned in electron spin phase sectors, calculated from *look\_direction\_id* as shown in section 6.2.8.1.4.



Table 39: Electron anode mapping to bins and look directions. (Note: Electron spin phase sectors are over many anodes and require an equation, see section 6.2.8.1.4.)

Sensor	Hardware Anode ( <i>anode_id</i> or <i>a_id</i> )	JADE SC Look Direction	JSIB Data Index	HRS/CAL/HVE Bin	LRS Sensor Loop Index ( <i>look_direction_id</i> )
E060	15	0	15	0	0
E060	14	1	14	1	1
E060	13	2	13	2	2
E060	12	3	12	3	3
E060	11	4	11	4	4
E060	10	5	10	5	5
E060	9	6	9	6	6
E060	8	7	8	7	7
E060	7	8	7	8	8
E060	6	9	6	9	9
E060	5	10	5	10	10
E060	4	11	4	11	11
E060	3	12	3	12	12
E060	2	13	2	13	13
E060	1	14	1	14	14
E060	0	15	0	15	15
E180	15	16	31	16	0
E180	14	17	30	17	1
E180	13	18	29	18	2
E180	12	19	28	19	3
E180	11	20	27	20	4
E180	10	21	26	21	5
E180	9	22	25	22	6
E180	8	23	24	23	7
E180	7	24	23	24	8
E180	6	25	22	25	9
E180	5	26	21	26	10
E180	4	27	20	27	11
E180	3	28	19	28	12
E180	2	29	18	29	13
E180	1	30	17	30	14
E180	0	31	16	31	15
E300	15	32	47	32	0
E300	14	33	46	33	1
E300	13	34	45	34	2
E300	12	35	44	35	3
E300	11	36	43	36	4
E300	10	37	42	37	5
E300	9	38	41	38	6
E300	8	39	40	39	7
E300	7	40	39	40	8
E300	6	41	38	41	9
E300	5	42	37	42	10
E300	4	43	36	43	11
E300	3	44	35	44	12
E300	2	45	34	45	13
E300	1	46	33	46	14
E300	0	47	32	47	15
E060	<i>Background</i>	<i>N/A</i>	48	48	<i>N/A</i>
E180	<i>Background</i>	<i>N/A</i>	49	49	<i>N/A</i>
E300	<i>Background</i>	<i>N/A</i>	50	50	<i>N/A</i>

The electron products may all contain the onboard MAG vector, depending if the magnetic field magnitude is above a threshold value, set in the uploaded Look-Up Tables (LUT, also known as the TABLES\_VERSION object in Level 2 files). From LUT 3.00 (2015, start of this archive) the threshold magnitude was set to 200 nT, meaning that a valid MAG\_VECTOR object was only returned near perijove (and never in the solar wind) when the magnetic field magnitude was stronger than 200 nT. This changed in LUT 3.11 (starting 2017-074) to 25 nT. Future LUT versions may change this threshold again, generally there is a usable MAG\_VECTOR (when the threshold is met) or MAG\_VECTOR = [0,0,0], indicating that the threshold was not met, and the true mag vector is unknown to the JADE instrument. (Earlier LUTs (pre 2015) had also set the threshold to zero for operational testing.)

This MAG\_VECTOR object (when the threshold is met and not returning zeroes) is only a guide. The user should cross reference the JADE timestamp with the Level 3 MAG (also known as FGM) team's calibrated magnetic field vectors for any publications involving magnetometer data.

JADE-E has three electron sensors, but publications may refer to only two electron sensors. This is because E300 was turned off in 2016 (prior to arrival at Jupiter) and remains off. As such, any data product still including E300 data (such as JAD\_L20\_HRS\_ELC\_ALL\_\*) will have elements relating to E300 populated with the MISSING\_CONSTANT value (see Table 41).

### 6.2.8.1.1 JAD\_L20\_CAL\_ELC\_ALL\_\*

The electron product for calibration mode is PACKETID 0x7E and includes data from all three electron sensors.

The DATA object is 2-D, 64 energies x 51 anodes, and is described in Table 40.

From 2016 onwards E300 will remain off, but the downlinked product still contains values from all three sensors. For bins that are from E300 (32 to 47 and 50), their values will be replaced with the DATA object's MISSING\_CONSTANT value, so should be obvious.

Table 40: Format of Level 2 data records for JAD L20 CAL ELC ALL \*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 37 for bytes 1 to 78.</i>				
79	0	104448	DATA	DATA: Electron Counts 64 Energies x 51 Bins The 51 Bins are: 0 - 15 : E060 Look Directions 0-15 16 - 31 : E180 Look Directions 0-15 32 - 47 : E300 Look Directions 0-15 48 : E060 Background Anode 49 : E180 Background Anode 50 : E300 Background Anode (See SIS document for a figure.)
13135	0	32	MAG_TIMESTAMP_WHOLE	MAG_TIMESTAMP_WHOLE Whole-second timestamp of last received MAG vector *before* data collection start. Referenced from 12:00UTC 2000/01/01. [May be affected by a Juno Time Stutter.]
13139	0	16	MAG_TIMESTAMP_SUB	MAG_TIMESTAMP_SUB Sub-second timestamp of last received MAG vector *before* data collection start. A value of 65535 could be real or a MISSING_CONSTANT, however it is MISSING_CONSTANT only if MAG_TIMESTAMP_WHOLE = 0, e.g. WHOLE and SUB must both be real or both be MISSING_CONSTANT. Unit: Microseconds scaled to 16 bits. [May be affected by a Juno Time Stutter.]
13141	0	8	MAG_COUNT_VALID	MAG_COUNT_VALID Count of valid (above threshold and not saturated) MAG vectors between start of *previous* packet and start of this packet. Note: This saturates at 255. e.g if there is a 600s accumulation period, and the MAG vector is given every 2-seconds, then that's 300 counts. If all are valid then that 300 will be expressed as 255, however MAG_COUNT_INVALID would still be zero.

Byte	Bit	Length (bits)	Name	Description
13142	0	8	MAG_COUNT_INVALID	<p>MAG_COUNT_INVALID Count of invalid (below threshold or saturated) MAG vectors between start of *previous* packet and start of this packet. Note: This saturates at 255. e.g if there is a 600s accumulation period, and the MAG vector is given every 2-seconds, then that's 300 counts. If all are invalid then that 300 will be expressed as 255, however MAG_COUNT_VALID would still be zero.</p>
13143	0	96	MAG_VECTOR	<p>Last received MAG vector in nT before data collection start: 3 components [X, Y, Z]</p> <p>MAG range is +/- 16 G, hence limits. The coordinate system is spacecraft based, with: +X is between E060 and E300, along the 0 degree mark where E060 anode 0 starts +Y is 90 degrees, between E060 anodes 11 and 12, +Z is the spin axis. Note: these are signed integers.</p> <p>A Mag vector of [0 0 0] has four meanings: [Meanings 1 and 2 require MAG_TIMESTAMP_WHOLE = 0. The MAG_COUNT_VALID and MAG_COUNT_INVALID objects can help distinguish meaning 1 from 2.] 1) JADE never received a mag vector at all. (So initialized to 0s.) e.g. MAG_COUNT_VALID = 0 for this record. 2) A 25s timeout has expired without JADE receiving a MAG vector over a threshold magnitude. [Meanings 3 and 4 require MAG_TIMESTAMP_WHOLE &gt; 0] 3) The threshold parameter was set to 0 nT. (Some early HVCO1 check-out data may have this.) 4) The broadcast message was corrupted and the magnitude and components mismatched.</p>

### 6.2.8.1.2 JAD\_L20\_HRS\_ELC\_ALL\_\*

The electron product for high rate science is PACKETID 0x8E and includes data from all three electron sensors.

The DATA object is 2-D, 64 energies x 51 anodes, and is described in Table 41.

From 2016 onwards E300 will remain off, but the downlinked product still contains values from all three sensors. For bins that are from E300 (32 to 47 and 50), their values will be replaced with the DATA object's MISSING\_CONSTANT value, so should be obvious.

Table 41: Format of Level 2 data records for JAD\_L20\_HRS\_ELC\_ALL\_\*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 37 for bytes 1 to 78.</i>				
79	0	52224	DATA	DATA: Electron Counts 64 Energies x 51 Bins The 51 Bins are: 0 - 15 : E060 Look Directions 0-15 16 - 31 : E180 Look Directions 0-15 32 - 47 : E300 Look Directions 0-15 48 : E060 Background Anode 49 : E180 Background Anode 50 : E300 Background Anode (See SIS document for a figure.) <i>[Note: E300 was turned off in 2016, so look directions 32-47 and 50 are usually populated with the MISSING_CONSTANT value of 65535.]</i>
6607	0	8	MAG_TIME_DIRECTION	MAG Time Direction. Indicates whether the MAG_TIME_LATENCY object indicates a past or future latency. 0: (time_received - time_in_packet) 1: (time_in_packet - time_received)
6608	0	8	MAG_LOOK_DIRECTION <i>[In earlier drafts was known as MAG_ANODE.]</i>	MAG Look direction (0 to 47), e.g. which electron bin the MAG vector fell on. E060 has bins 0 to 15 E180 has bins 16 to 31 E300 has bins 32 to 47 (See DATA object for description of bins and look directions, and see the SIS document for a figure.) Note: Background anodes (per sensor) are not included for this mapping.
6609	0	16	MAG_FIRST_DEFLECTION	MAG First Deflection. First Deflection value written to the electron sweep table for the sensor the mag vector landed on. (1-bit range/gain (MSb) + 12-bit DAC value).
6611	0	8	MAG_ELEVATION	MAG elevation. Elevation angle of the mag vector, rounded to the nearest degree.

Byte	Bit	Length (bits)	Name	Description
6612	0	8	MAG_TIME_LATENCY	<p>MAG Time Latency. Time difference (in 250 ms blocks) between the timestamp of the MAG vector and the time it was received by JADE. Values map to:</p> <p>0 = 0.000 - 0.249 s 1 = 0.250 - 0.499 s 2 = 0.500 - 0.749 s 3 = 0.750 - 0.999 s etc. 14 = 3.500 - 3.749 s 15 = 3.750 - infinity s</p>
6613	0	32	MAG_TIMESTAMP_WHOLE	<p>MAG_TIMESTAMP_WHOLE</p> <p>Timestamp (whole second) for MAG vector. MAG timestamp subsecond is not returned in JADE high rate science electron packets. Referenced from 12:00UTC 2000/01/01. [May be affected by a Juno Time Stutter.]</p>
6617	0	96	MAG_VECTOR	<p>MAG vector in nT, 3 components [X, Y, Z] MAG range is +/- 16 G, hence limits. The coordinate system is spacecraft based, with: +X is between E060 and E300, along the 0 degree mark where E060 anode 0 starts +Y is 90 degrees, between E060 anodes 11 and 12, +Z is the spin axis. Note: these are signed integers.</p> <p>A Mag vector of [0 0 0] has four meanings: [Meanings 1 and 2 require MAG_TIMESTAMP_WHOLE = 0] 1) JADE never received a mag vector at all. (So initialized to 0s.) 2) A 25s timeout has expired without JADE receiving a MAG vector over a threshold magnitude. [Meanings 3 and 4 require MAG_TIMESTAMP_WHOLE &gt; 0] 3) The threshold parameter was set to 0 nT. (Some early HVCO1 check-out data may have this.) 4) The broadcast message was corrupted and the magnitude and components mismatched.</p>

6.2.8.1.3 JAD\_L20\_HVE\_ELC\_ALL\_\*

The electron product for high voltage engineering is PACKETID 0x1E and includes data from all three electron sensors.

The DATA object is 1-D, 51 anodes (over 1 energy), and is described in Table 42.

[The one energy is really 64 energy steps where all 64-steps are at the same fixed energy.]

Table 42: Format of Level 2 data records for JAD L20 HVE ELC ALL \*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 37 for bytes 1 to 78.</i>				
79	0	1632	DATA	DATA: Electron Counts 1 Energy x 51 Bins The 51 Bins are: 0 - 15 : E060 Look Direction 0-15 16 - 31 : E180 Look Directions0-15 32 - 47 : E300 Look Directions0-15 48 : E060 Background Anode 49 : E180 Background Anode 50 : E300 Background Anode (See SIS document for a figure.) 16-bit counter at 1 energy step over ACCUMULATION_TIME. Theoretical range (with max Accumulation of 1800s) is 0 to 7549632000, greater than a 4-byte unsigned int. It is extremely unlikely to fill 4- bytes, but if it does it will simply roll over to zero and keep going.

#### 6.2.8.1.4 JAD\_L20\_LRS\_ELC\_ANY\_\*

The electron products for low rate science (PACKETID 0x68, 0x6A and 0x6B) cover all three electron sensors in the same file but one record contains data from one electron sensor only. At any time only one sensor will have a record.

This product is not about anodes, but electron Spin Phase sectors (different to ion Spin Phase sectors). For electron spin sectoring, there is a many-many relationship between anodes and spin sectors; an anode will travel through many sectors, and many anodes will contribute to each sector.

The formula for mapping sensor look directions into electron spin-phase sectors is:

$$spin\_sector = ((spin\_phase + sensor\_id + 7.5 * look\_direction\_id) / 7.5 - 8) \text{ MOD } 48$$

where:

*spin\_sector* (electron) is 0 to 47 (rounded down to an integer).

*spin\_phase* is in the range 0 to 360 degrees (angle from last crossing)  
(S/C reports in SHK files the angle to next crossing, a decreasing number, hence this spin-phase is 360 degrees minus that.)

*sensor\_id* is either 60, 180, or 300, depending on which sensor it is for.

*look\_direction\_id* is 0 to 15 (also known as *sensor\_loop\_index* in operations documents)  
and is the look direction of anode *anode\_id*, where  $look\_direction\_id = 15 - anode\_id$ .

*anode\_id* (or *a\_id*) is one of the 16 anodes of the given sensor, 0-15.

7.5 degrees is the width of one anode.

$(15 - anode\_id)$  is to correct for the look directions of the anodes.

Simplifying the equation (the last one is the one listed in the PDS file description):

$$\Rightarrow spin\_sector = ((spin\_phase + sensor\_id + 7.5 * (15 - anode\_id)) / 7.5 - 8) \text{ MOD } 48$$

$$\Rightarrow spin\_sector = ((spin\_phase + sensor\_id) / 7.5 + (15 - anode\_id) - 8) \text{ MOD } 48$$

$$\Rightarrow spin\_sector = ((spin\_phase + sensor\_id) / 7.5 + 7 - anode\_id) \text{ MOD } 48$$

Note that during FSW4.0 (April 2015 data only) the flight software had reversed anode mapping which messed up this calculation (see ISSUES object) (this reverse mapping affected all earlier FSW versions too, which are not covered in this PDS volume). If using FSW4.00/April 2015 data for this product (cruise solar wind only, no Jupiter science use) do not trust the spin sector calculation (in Level 3 data *DIM2\_AZIMUTH\_DESPUN* is replaced with fill values for FSW4.00). The only science use is to sum over spin phase sector to reduce the array to energy by time only. This was fixed in FSW4.10 (uploaded prior to the August 2015 data), from when this calculation was done correctly.

The DATA object is 2-D, 64 energies x 48 Electron Spin Phase sectors (from one electron sensor), and is described in



Table 43: Format of Level 2 data records for JAD L20 LRS ELC ANY \*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 36 for bytes 1 to 70.</i>				
71	0	98304	DATA	<p>DATA: Counts 64 Energies x 48 Electron Spin Phase Sectors. The formula for mapping anodes into spin-phase sectors is described in full in the PDS JADE SIS and simplifies to:</p> $SP\_sector = ((s\_phase + s\_id)/7.5 + 7 - a\_id) \text{ MOD } 48$ <p>where:            SP_sector (electron spin phase sector) is 0 to 47 (rounded down to an integer).            s_phase is spin phase, 0 to 360 degrees.            s_id is the sensor in question, either 60, 180, or 300.            a_id is one of the 16 anodes of the given sensor, 0-15. (This is anode, not the look direction.)            7.5 degrees is the width of one anode.</p> <p>Note the data units are rates (counts per views), are floats rather than integers, and are fractions of 1/512.            Note 2: Rate is independent of accumulation time.            Note 3: If the data is from FSW 4.00 (April 2015 only, when anodes were reversed - see ISSUES object) then the SP_sector calculation was done incorrectly. If you must use this FSW4.00 data, sum over electron spin phase sector to reduce the data to energy by time and use that.</p>
12359	0	32	MAG_TIMESTAMP_WHOLE	<p>MAG_TIMESTAMP_WHOLE Whole-second timestamp of last received MAG vector *before* data collection start. Referenced from 12:00UTC 2000/01/01.</p>
12363	0	16	MAG_TIMESTAMP_SUB	<p>MAG_TIMESTAMP_SUB Sub-second timestamp of last received MAG vector *before* data collection start. A value of 65535 could be real or a MISSING_CONSTANT, however it is MISSING_CONSTANT only if MAG_TIMESTAMP_WHOLE = 0, e.g. WHOLE and SUB must both be real or both be MISSING_CONSTANT. Unit: Microseconds scaled to 16 bits.</p>

Byte	Bit	Length (bits)	Name	Description
12365	0	8	MAG_COUNT_VALID	<p>MAG_COUNT_VALID Count of valid (above threshold and not saturated) MAG vectors between start of *previous* packet and start of this packet. Note: This saturates at 255. e.g if there is a 600s accumulation period, and the MAG vector is given every 2-seconds, then that's 300 counts. If all are valid then that 300 will be expressed as 255, however MAG_COUNT_INVALID would still be zero.</p>
12366	0	8	MAG_COUNT_INVALID	<p>MAG_COUNT_INVALID Count of invalid (below threshold or saturated) MAG vectors between start of *previous* packet and start of this packet. Note: This saturates at 255. e.g if there is a 600s accumulation period, and the MAG vector is given every 2-seconds, then that's 300 counts. If all are invalid then that 300 will be expressed as 255, however MAG_COUNT_VALID would still be zero.</p>
12367	0	96	MAG_VECTOR	<p>Last received MAG vector in nT before data collection start: 3 components [X, Y, Z]</p> <p>MAG range is +/- 16 G, hence limits. The coordinate system is spacecraft based, with: +X is between E060 and E300, along the 0 degree mark where E060 anode 0 starts +Y is 90 degrees, between E060 anodes 11 and 12, +Z is the spin axis. Note: these are signed integers.</p> <p>A Mag vector of [0 0 0] has four meanings: [Meanings 1 and 2 require MAG_TIMESTAMP_WHOLE = 0. The MAG_COUNT_VALID and MAG_COUNT_INVALID objects can help distinguish meaning 1 from 2.] 1) JADE never received a mag vector at all. (So initialized to 0s.) e.g. MAG_COUNT_VALID = 0 for this record. 2) A 25s timeout has expired without JADE receiving a MAG vector over a threshold magnitude. [Meanings 3 and 4 require MAG_TIMESTAMP_WHOLE &gt; 0 3) The threshold parameter was set to 0 nT. (Some early HVCO1 check-out data may have this.) 4) The broadcast message was corrupted and the magnitude and components mismatched.</p>

Byte	Bit	Length (bits)	Name	Description
12379	0	32	BACKGROUND_COUNTS	<p>Background counts (NOT a background rate). The background counter for this record's electron sensor (see ESENSOR object to know which sensor).</p> <p>This is a total count, not a rate.</p> <p>This is a 16-bit counter over 64 energies over the accumulation time (up to 1800 seconds), which means it could roll over the 4-byte word. i.e. 4294967296 = 0. However this is unlikely, and even if so, should be obvious from the visible background in object DATA.</p>
12383	0	16	ESENSOR	<p>ESENSOR - which one of the three electron sensors is this record for. Values can only be 60, 180 or 300 for electron sensor E060, E180 or E300 respectively. Note: each sensor also has a different PACKETID.</p>

### 6.2.8.2 Ion Species Data

The JADE ion sensor has 12 anodes, as shown in the following figure.




Figure 8: JADE-I Anodes.

#### 6.2.8.2.1 JAD\_L20\_HRS\_ION\_ANY\_\*

The ion species products for high rate science cover PACKETIDs 0x80-0x87. Each ion species has its own packet; therefore several packets of different species may have the same time stamp. The DATA object is 2-D, 32 energies x 12 anodes, and is described in Table 44.

Table 44: Format of Level 2 data records for JAD L20 HRS ION ANY \*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 36 for bytes 1 to 70.</i>				
71	0	6144	DATA	DATA: Counts 32 Energies x 12 Anodes

### 6.2.8.2.2 JAD\_L20\_HVE\_ION\_ALL\_\*

The ion species product for high voltage engineering is PACKETID 0x18.

The DATA object is 2-D, 8 ion species x 12 anodes (over 1 energy), and is described in Table 45. [The one energy is really 32 energy steps where all 32-steps are at the same fixed energy.]

Table 45: Format of Level 2 data records for JAD L20 HVE ION ALL \*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 36 for bytes 1 to 70.</i>				
71	0	3072	DATA	DATA: Counts 8 Species x 12 anodes (x1 Energy) Species is 0-7, ion anodes 0-11. (16-bit counter, summed over 32 identical energy steps over accumulation period.)

### 6.2.8.2.3 JAD\_L20\_LRS\_ION\_ANY\_\* and JAD\_L20\_CAL\_ION\_ANY\_\*

The ion species products for low rate science (PACKETID 0x60-0x67) and calibration modes (PACKETID 0x70-0x77) are identical. Each ion species has its own packet; therefore several packets of different species may have the same time stamp.

The DATA object is 2-D, 32 energies x 78 ion spin phase sectors (note that ion spin phase sectors in FSW4 are different to those described in the original JADE instrument paper that was for FSW3). Ion spin phase sectors [0-77] are a factor of ion anode and the spin phase at the start of the record. The ion spin phase sector mapping is shown in Figure 9 and also within Table 46 in the description of the DATA object (where a range of 0-12 means  $0 \leq \text{range} < 12$ ); it is different to the electron spin phase sectors.

Spin phase of Juno's +x axis is the angle **from** the last ECLIPJ2000 +z ('north') crossing, which increases over time and is shown in light red on the bottom of Figure 9. Juno reports in JADE operations SHK files the angle to next crossing, a decreasing number; hence this spin phase is 360 degrees minus that. The actual spin phase of JADE-I is shown in the dark red on the top of Figure 9, and is always 195 degrees greater than the equivalent spin phase of Juno's +x axis.

		Spin phase of JADE-I instrument (Degrees)																																		
		195	207	219	231	243	255	267	279	291	303	315	327	339	351	3	15	27	39	51	63	75	87	99	111	123	135	147	159	171	183					
Anode 0	Anodes 0-3 not reported as part of LRS Species map																																			
Anode 1																																				
Anode 2																																				
Anode 3																																				
Anode 4	0							1							2																					
Anode 5	3			4			5			6			7			8																				
Anode 6	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23																					
Anode 7	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38																					
Anode 8	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53																					
Anode 9	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68																					
Anode 10	69			70			71			72			73			74																				
Anode 11	75					76					77																									
		0	12	24	36	48	60	72	84	96	108	120	132	144	156	168	180	192	204	216	228	240	252	264	276	288	300	312	324	336	348					
		Spin phase of Juno +X axis (Degrees)																																		

Figure 9: The Ion Spin Phase Sector mapping to ion anode and spin phase (start angles).

Be careful with this product when ACCUMULATION\_TIME = 30 for a record. There are the 78 ion spin phase sectors, however for a 30 second accumulation it is possible that not all 78 spin phase sectors will be observed. This is because Juno's spin period may be 29.2 to 30.8 seconds,

and at time of writing has always been over 30 seconds. If the spin period was exactly 30.0 seconds, then all spin-phase sectors for anodes 6 to 9 would be observed once in a 30 second accumulation. If the spin period is less than 30 seconds, it's possible for 4 or 8 sectors to be skipped. E.g. if spin phase sector 9 is skipped, then so is spin phase sector 24, 39 and 54 as they are all at the same spin phase. Or if the spin period is greater than 30 seconds and the spin started on exactly zero spin-phase, then the accumulation period may simply end before spin phase sector 23 (and 38, 53, 68 as all the same spin phase) is reached. Identifying which spin phase sectors may be missed or unobserved is tricky as it depends on both the spin period and exact spin-phase at the start of the accumulation period, neither of which is known for a level 2 product.

This means that 4 or 8 spin-phase sectors may not be observed in a record with an ACCUMULATION\_TIME of 30 seconds, and is usually just 4. The assumption is that LRS or CAL ion species data covers the full sky of  $4\pi$  steradians, however this is not true when some spin-phase sectors are missing. If the accumulation time is greater than 30 (that is 60, 120, 150, 300 or 600) seconds then all spin phase sectors are viewed at least once during the accumulation, therefore none are unobserved.

If a spin phase sector is unobserved then a value of zero counts/view is returned. Unfortunately, this is indistinguishable from an observed spin-phase sector that simply did not measure any ions. Hence there is potential confusion when presented with zero counts/view (or counts per second for Level 3 files), was this spin phase sector measured but counted no ions, or was it not measured at all.

If it is known that some spin phase sectors are missing, one could use the values from the equivalent spin phase sectors on the next record. However, the LRS and CAL ion species data has many measured zero counts/view, making it impossible to identify which are unobserved when in the solar wind or in a low count region. In high count regions where there are naturally some counts (even if they are background counts) in most spin phase sectors then it is easy to pick out the 4 or 8 elements of a record that are zero because there are no other zeros. In such case, if 4 zeros, they should be in spin phase sector numbers that are 15 apart, e.g. the same spin phase like spin phase sectors 14, 29, 44 and 59. If 8 zeros, then there should be two sets of numbers 15 apart. Also, for a given time stamp there will be multiple records with different ion species numbers, e.g. PACKET\_SPECIES of 3, 4 and 5. For the same time stamp, all species should be missing the same spin phase sector numbers.

Table 46: Format of Level 2 data records for JAD\_L20\_LRS\_ION\_ANY\_\* and JAD L20 CAL ION ANY \*

Byte	Bit	Length (bits)	Name	Description																																																																																																																																																																																																																																																																																																
<i>See Level 2 binary header from Table 35 and Table 36 for bytes 1 to 70.</i>																																																																																																																																																																																																																																																																																																				
71	0	79872	DATA	<p>DATA: Counts per view            32 Energies x 78 Ion Spin Phase Sectors            The formula for mapping anodes into spin-phase sectors is described in the PDS JADE SIS and as follows:</p> <p>Each Spin Phase Sector has contributions from multiple spin phases, but always the same anode.            The spin phase is calculated from the start of the record.            Only anodes 4-11 are used, 0-3 are not reported.            There are 78 Spin Phase sectors [0-77] over the eight anodes and thirty 12-degree wide sectors, with spin phase sectors given in the following table of anode by start spin phase:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: left;">Ion Start Spin Phase (Degrees)</th> <th colspan="8" style="text-align: center;">Ion Anode</th> </tr> <tr> <th style="text-align: left;">(Degrees)</th> <th>4</th> <th>5</th> <th>6</th> <th>7</th> <th>8</th> <th>9</th> <th>10</th> <th>11</th> </tr> </thead> <tbody> <tr><td>195-207</td><td>0</td><td>3</td><td>9</td><td>24</td><td>39</td><td>54</td><td>69</td><td>75</td></tr> <tr><td>207-219</td><td>0</td><td>3</td><td>9</td><td>24</td><td>39</td><td>54</td><td>69</td><td>75</td></tr> <tr><td>219-231</td><td>0</td><td>3</td><td>10</td><td>25</td><td>40</td><td>55</td><td>69</td><td>75</td></tr> <tr><td>231-243</td><td>0</td><td>3</td><td>10</td><td>25</td><td>40</td><td>55</td><td>69</td><td>75</td></tr> <tr><td>243-255</td><td>0</td><td>3</td><td>11</td><td>26</td><td>41</td><td>56</td><td>70</td><td>75</td></tr> <tr><td>255-267</td><td>0</td><td>3</td><td>11</td><td>26</td><td>41</td><td>56</td><td>70</td><td>75</td></tr> <tr><td>267-279</td><td>0</td><td>4</td><td>12</td><td>27</td><td>42</td><td>57</td><td>70</td><td>75</td></tr> <tr><td>279-291</td><td>0</td><td>4</td><td>12</td><td>27</td><td>42</td><td>57</td><td>70</td><td>75</td></tr> <tr><td>291-303</td><td>0</td><td>4</td><td>13</td><td>28</td><td>43</td><td>58</td><td>70</td><td>75</td></tr> <tr><td>303-315</td><td>0</td><td>4</td><td>13</td><td>28</td><td>43</td><td>58</td><td>70</td><td>75</td></tr> <tr><td>315-327</td><td>1</td><td>5</td><td>14</td><td>29</td><td>44</td><td>59</td><td>71</td><td>76</td></tr> <tr><td>327-339</td><td>1</td><td>5</td><td>14</td><td>29</td><td>44</td><td>59</td><td>71</td><td>76</td></tr> <tr><td>339-351</td><td>1</td><td>5</td><td>15</td><td>30</td><td>45</td><td>60</td><td>71</td><td>76</td></tr> <tr><td>351-003</td><td>1</td><td>5</td><td>15</td><td>30</td><td>45</td><td>60</td><td>71</td><td>76</td></tr> <tr><td>003-015</td><td>1</td><td>5</td><td>16</td><td>31</td><td>46</td><td>61</td><td>72</td><td>76</td></tr> <tr><td>015-027</td><td>1</td><td>5</td><td>16</td><td>31</td><td>46</td><td>61</td><td>72</td><td>76</td></tr> <tr><td>027-039</td><td>1</td><td>6</td><td>17</td><td>32</td><td>47</td><td>62</td><td>72</td><td>76</td></tr> <tr><td>039-051</td><td>1</td><td>6</td><td>17</td><td>32</td><td>47</td><td>62</td><td>72</td><td>76</td></tr> <tr><td>051-063</td><td>1</td><td>6</td><td>18</td><td>33</td><td>48</td><td>63</td><td>72</td><td>76</td></tr> <tr><td>063-075</td><td>1</td><td>6</td><td>18</td><td>33</td><td>48</td><td>63</td><td>72</td><td>76</td></tr> <tr><td>075-087</td><td>2</td><td>7</td><td>19</td><td>34</td><td>49</td><td>64</td><td>73</td><td>77</td></tr> <tr><td>087-099</td><td>2</td><td>7</td><td>19</td><td>34</td><td>49</td><td>64</td><td>73</td><td>77</td></tr> <tr><td>099-111</td><td>2</td><td>7</td><td>20</td><td>35</td><td>50</td><td>65</td><td>73</td><td>77</td></tr> <tr><td>111-123</td><td>2</td><td>7</td><td>20</td><td>35</td><td>50</td><td>65</td><td>73</td><td>77</td></tr> <tr><td>123-135</td><td>2</td><td>7</td><td>21</td><td>36</td><td>51</td><td>66</td><td>74</td><td>77</td></tr> <tr><td>135-147</td><td>2</td><td>7</td><td>21</td><td>36</td><td>51</td><td>66</td><td>74</td><td>77</td></tr> <tr><td>147-159</td><td>2</td><td>8</td><td>22</td><td>37</td><td>52</td><td>67</td><td>74</td><td>77</td></tr> <tr><td>159-171</td><td>2</td><td>8</td><td>22</td><td>37</td><td>52</td><td>67</td><td>74</td><td>77</td></tr> <tr><td>171-183</td><td>2</td><td>8</td><td>23</td><td>38</td><td>53</td><td>68</td><td>74</td><td>77</td></tr> <tr><td>183-195</td><td>2</td><td>8</td><td>23</td><td>38</td><td>53</td><td>68</td><td>74</td><td>77</td></tr> </tbody> </table> <p>[The onboard software triggers on the spin phase of the s/c +X axis, but JADE-I is 195 degrees further around, so the Ion Start Spin Phase starts at 195.]</p> <p>The meaning of each species is described in the JADE instrument paper.            Note the data units are rates (counts per views), are floats rather than integers, and are fractions of 1/512.            Note 2: Rate is independent of accumulation time.</p>	Ion Start Spin Phase (Degrees)	Ion Anode								(Degrees)	4	5	6	7	8	9	10	11	195-207	0	3	9	24	39	54	69	75	207-219	0	3	9	24	39	54	69	75	219-231	0	3	10	25	40	55	69	75	231-243	0	3	10	25	40	55	69	75	243-255	0	3	11	26	41	56	70	75	255-267	0	3	11	26	41	56	70	75	267-279	0	4	12	27	42	57	70	75	279-291	0	4	12	27	42	57	70	75	291-303	0	4	13	28	43	58	70	75	303-315	0	4	13	28	43	58	70	75	315-327	1	5	14	29	44	59	71	76	327-339	1	5	14	29	44	59	71	76	339-351	1	5	15	30	45	60	71	76	351-003	1	5	15	30	45	60	71	76	003-015	1	5	16	31	46	61	72	76	015-027	1	5	16	31	46	61	72	76	027-039	1	6	17	32	47	62	72	76	039-051	1	6	17	32	47	62	72	76	051-063	1	6	18	33	48	63	72	76	063-075	1	6	18	33	48	63	72	76	075-087	2	7	19	34	49	64	73	77	087-099	2	7	19	34	49	64	73	77	099-111	2	7	20	35	50	65	73	77	111-123	2	7	20	35	50	65	73	77	123-135	2	7	21	36	51	66	74	77	135-147	2	7	21	36	51	66	74	77	147-159	2	8	22	37	52	67	74	77	159-171	2	8	22	37	52	67	74	77	171-183	2	8	23	38	53	68	74	77	183-195	2	8	23	38	53	68	74	77
Ion Start Spin Phase (Degrees)	Ion Anode																																																																																																																																																																																																																																																																																																			
(Degrees)	4	5	6	7	8	9	10	11																																																																																																																																																																																																																																																																																												
195-207	0	3	9	24	39	54	69	75																																																																																																																																																																																																																																																																																												
207-219	0	3	9	24	39	54	69	75																																																																																																																																																																																																																																																																																												
219-231	0	3	10	25	40	55	69	75																																																																																																																																																																																																																																																																																												
231-243	0	3	10	25	40	55	69	75																																																																																																																																																																																																																																																																																												
243-255	0	3	11	26	41	56	70	75																																																																																																																																																																																																																																																																																												
255-267	0	3	11	26	41	56	70	75																																																																																																																																																																																																																																																																																												
267-279	0	4	12	27	42	57	70	75																																																																																																																																																																																																																																																																																												
279-291	0	4	12	27	42	57	70	75																																																																																																																																																																																																																																																																																												
291-303	0	4	13	28	43	58	70	75																																																																																																																																																																																																																																																																																												
303-315	0	4	13	28	43	58	70	75																																																																																																																																																																																																																																																																																												
315-327	1	5	14	29	44	59	71	76																																																																																																																																																																																																																																																																																												
327-339	1	5	14	29	44	59	71	76																																																																																																																																																																																																																																																																																												
339-351	1	5	15	30	45	60	71	76																																																																																																																																																																																																																																																																																												
351-003	1	5	15	30	45	60	71	76																																																																																																																																																																																																																																																																																												
003-015	1	5	16	31	46	61	72	76																																																																																																																																																																																																																																																																																												
015-027	1	5	16	31	46	61	72	76																																																																																																																																																																																																																																																																																												
027-039	1	6	17	32	47	62	72	76																																																																																																																																																																																																																																																																																												
039-051	1	6	17	32	47	62	72	76																																																																																																																																																																																																																																																																																												
051-063	1	6	18	33	48	63	72	76																																																																																																																																																																																																																																																																																												
063-075	1	6	18	33	48	63	72	76																																																																																																																																																																																																																																																																																												
075-087	2	7	19	34	49	64	73	77																																																																																																																																																																																																																																																																																												
087-099	2	7	19	34	49	64	73	77																																																																																																																																																																																																																																																																																												
099-111	2	7	20	35	50	65	73	77																																																																																																																																																																																																																																																																																												
111-123	2	7	20	35	50	65	73	77																																																																																																																																																																																																																																																																																												
123-135	2	7	21	36	51	66	74	77																																																																																																																																																																																																																																																																																												
135-147	2	7	21	36	51	66	74	77																																																																																																																																																																																																																																																																																												
147-159	2	8	22	37	52	67	74	77																																																																																																																																																																																																																																																																																												
159-171	2	8	22	37	52	67	74	77																																																																																																																																																																																																																																																																																												
171-183	2	8	23	38	53	68	74	77																																																																																																																																																																																																																																																																																												
183-195	2	8	23	38	53	68	74	77																																																																																																																																																																																																																																																																																												

### 6.2.8.3 Ion Time of Flight Data

#### 6.2.8.3.1 JAD\_L20\_HLC\_ION\_TOF\_\*

The ion time of flight products for high rate science, low rate science and calibration mode are all of the same format and in the same file; covering PACKETID 0x69, 0x79 and 0x89.

[Technically, the high rate science data product is of 2-byte values, whereas low rate/calibration data are 4-byte values, however the high rate data is up-cast to 4-bytes to make them identical.]

The DATA object is 2-D, 32 energies x 96 TOF channels, and is described in Table 47.

Table 47: Format of Level 2 data records for JAD\_L20\_HLC\_ION\_TOF\_\*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 36 for bytes 1 to 70.</i>				



Byte	Bit	Length (bits)	Name	Description
71	0	98304	DATA	<p>DATA: Time of Flight Counts 32 Energies x 96 TOF channels. The last 3 channels have special meanings. The <del>42896</del> TOF channels are <del>counters are:</del><a href="#">created from the Medium</a> <a href="#">Resolution set of 128 channels, binned as follows:</a></p> <p>[ 0]: <a href="#">Medium Resolution</a> TOF channels 0 - 1 [ 1]: <a href="#">Medium Resolution</a> TOF channel 2 [ 2]: <a href="#">Medium Resolution</a> TOF channel 3 [ 3]: <a href="#">Medium Resolution</a> TOF channel 4 ... [59]: <a href="#">Medium Resolution</a> TOF channel 60 [60]: <a href="#">Medium Resolution</a> TOF channel 61 [61]: <a href="#">Medium Resolution</a> TOF channels 62 - 63 [62]: <a href="#">Medium Resolution</a> TOF channels 64 - 65 ... [70]: <a href="#">Medium Resolution</a> TOF channels 80 - 81 [71]: <a href="#">Medium Resolution</a> TOF channels 82 - 83 [72]: <a href="#">Medium Resolution</a> TOF channel 84 [73]: <a href="#">Medium Resolution</a> TOF channel 85 [74]: <a href="#">Medium Resolution</a> TOF channel 86 [75]: <a href="#">Medium Resolution</a> TOF channel 87 [76]: <a href="#">Medium Resolution</a> TOF channel 88 [77]: <a href="#">Medium Resolution</a> TOF channels 89 - 90 [78]: <a href="#">Medium Resolution</a> TOF channels 91 - 92 ... [89]: <a href="#">Medium Resolution</a> TOF channels 113 - 114 [90]: <a href="#">Medium Resolution</a> TOF channels 115 - 116 [91]: <a href="#">Medium Resolution</a> TOF channels 117 - 118 [92]: <a href="#">Medium Resolution</a> TOF channels 119 - 124 [93]: TOF with Start overload. <a href="#">(Medium Resolution TOF channel 125)</a> [94]: TOF value below minimum resolution. <a href="#">(Medium Resolution TOF channel 126)</a> [95]: TOF too long. <a href="#">(Medium Resolution TOF channel 127)</a></p>

### 6.2.8.3.2 JAD\_L20\_HVE\_ION\_TOF\_\*

The ion time of flight product for high voltage engineering is PACKETID 0x19.  
The DATA object is 1-D, 128 TOF channels (over 1 energy), and is described in Table 48.  
[The one energy is really 32 energy steps where all 32-steps are at the same fixed energy.]

Table 48: Format of Level 2 data records for JAD L20 HVE ION TOF \*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 36 for bytes 1 to 70.</i>				

Byte	Bit	Length (bits)	Name	Description
71	0	4096	DATA	<p>DATA: Time of Flight Counts  128 TOF channels (x 1 Energy)  The last 3 channels have special meanings.  The 128 TOF channels are counters are:  [ 0]: <a href="#">Medium Resolution TOF channel 0</a>  [ 1]: <a href="#">Medium Resolution TOF channel 1</a>  ...  [123]: <a href="#">Medium Resolution TOF channel 123</a>  [124]: <a href="#">Medium Resolution TOF channel 124</a>  [125]: TOF with Start overload.  <a href="#">(Medium Resolution TOF channel 125)</a>  [126]: TOF value below minimum resolution.  <a href="#">(Medium Resolution TOF channel 126)</a>  [127]: TOF too long.  <a href="#">(Medium Resolution TOF channel 127)</a>  (16-bit counter, summed over 32 identical energy steps over accumulation period.)</p>

## 6.2.8.4 Ion Logicals Data

### 6.2.8.4.1 JAD\_L20\_HLC\_ION\_LOG\_\*

The ion logicals products for high rate science, low rate science and calibration mode are all of the same format and in the same file; covering PACKETID 0x6C, 0x7C and 0x8C.

[Technically, the high rate science data product is of 2-byte values, whereas low rate/calibration data are 4-byte values, however the high rate data is upcast to 4-bytes to make them identical.]

The DATA object is 2-D, 32 energies x 25 logicals, and is described in Table 49, which runs over 2 pages despite only being for the DATA object.

The 25 logical counters here are the same for JAD\_L20\_HVE\_ION\_LOG\_\*.

Table 49: Format of Level 2 data records for JAD\_L20\_HLC\_ION\_LOG\_\*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 36 for bytes 1 to 70.</i>				
71	0	25600	DATA	<p>DATA: Counts 32 Energies x 25 Logical counters. The 25 Logical counters are:</p> <ul style="list-style-type: none"> <li>[ 0]: Anode 0 Events</li> <li>[ 1]: Anode 1 Events</li> <li>[ 2]: Anode 2 Events</li> <li>...</li> <li>[10]: Anode 10 Events</li> <li>[11]: Anode 11 Events</li> <li>[12]: Background Events</li> </ul> <p>The above 13 logicals are raw count hits, independent of whether a TOF Event has begun. Adjacent and Non-Adjacent hits will be counted in both anodes. As such, anode counts can exceed All Stops [15] counts.</p> <p>The Background anode [12] is not included in Adjacent and Non-Adjacent calculations.</p> <ul style="list-style-type: none"> <li>[13]: Start Overload Start signal exceeds threshold level.</li> <li>[14]: All Starts Independent of whether a TOF Event has begun, usually starts a TOF Event.</li> <li>[15]: All Stops Independent of whether a TOF Event has begun, usually ends a TOF Event.</li> </ul> <p>If an event is seen on multiple anodes this counter is still only incremented once, therefore this is usually less than the sum of anodes 0 to 11.</p> <p>The Background anode is not included in All Stops, just anodes 0 to 11.</p> <ul style="list-style-type: none"> <li>[16]: Non-Adjacent Anodes This is either two non-neighbor anodes (anodes 0-11 only), or more than 2 anodes.</li> </ul> <p><i>Continues on next page.</i></p>

Byte	Bit	Length (bits)	Name	Description
				<p><i>Continues from previous page.</i></p> <p>[17]: Adjacent Anodes A count hit was measured in neighboring anodes; other products (e.g. Ion Species) will assign this to just the lower anode.</p> <p>[18]: Stop without Start A stop signal was received before a TOF Event was initiated by a start.</p> <p>[19]: Dual Start A TOF Event had started but one or more other start signals were received before a stop signal or the TOF Event overflowed.</p> <p>[20]: Start in Process Time The number of TOF Events started, can be less than All Starts [14].</p> <p>[21]: TOF Underflow Received a stop event before 1 tap, that is 1.6ns, the base unit of TOF times.</p> <p>[22]: TOF Overflow No stop signal arrived within timeout of 330ns.</p> <p>[23]: Invalid TOF Event If the TOF Event is measured in 1 anode (anodes 0-11 only) or two neighboring anodes (anodes 0-11 only) it is valid. Otherwise it is invalid, unless it was an underflow in which case the Underflow [21] counter is increased instead of this counter (i.e. an Underflow event is considered valid). Therefore, if the event is not an Underflow event, it will be invalid if one of these three situations is met:  <ul style="list-style-type: none"> <li>- hit in more than two anodes, or</li> <li>- hit in two non-neighbor anodes, or</li> <li>- no anodes hit at all.</li> </ul> The latter is different to overflow events [22] which are considered valid. The Background anode is not considered in any of these calculations.</p> <p>[24]: Event Strobe The number of TOF Events completed, by a stop signal or over/underflow, usually the same as Start in Process Time [20].</p> <p>For the above, a TOF Event is a start signal followed by either a stop signal or timeout.</p> <p>Note: This file can contain data from Low Rate Science, MCP Calibration or High Rate Science modes. High Rate Science have a maximum counts of 65535 per accumulation unlike the others with a maximum of 117963000.</p>

#### 6.2.8.4.2 JAD\_L20\_HVE\_ION\_LOG\_\*

The ion logicals product for high voltage engineering is PACKETID 0x1C.

The DATA object is 1-D, 25 logicals (over 1 energy), and is described in Table 50.

[The one energy is really 32 energy steps where all 32-steps are at the same fixed energy.]

The 25 logical counters here are the same for JAD\_L20\_HLC\_ION\_LOG\_\*

Table 50: Format of Level 2 data records for JAD\_L20\_HVE\_ION\_LOG\_\*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 36 for bytes 1 to 70.</i>				
71	0	800	DATA	DATA: Counts 1 Energy x 25 Logical counters. The 25 Logical counters are: [ 0]: Anode 0 [ 1]: Anode 1 [ 2]: Anode 2 [ 3]: Anode 3 [ 4]: Anode 4 [ 5]: Anode 5 [ 6]: Anode 6 [ 7]: Anode 7 [ 8]: Anode 8 [ 9]: Anode 9 [10]: Anode 10 [11]: Anode 11 [12]: Background [13]: Start Overload [14]: All Starts [15]: All Stops [16]: Non-Adjacent Anodes [17]: Adjacent Anodes [18]: Stop without Start [19]: Dual Start [20]: Start in Process Time [21]: TOF Underflow [22]: TOF Overflow [23]: Invalid TOF Event [24]: Event Strobe (16-bit counter, summed over 32 identical energy steps over accumulation period.) See the DESCRIPTION of DATA in JAD_L20_HLC_ION_LOG files for a better description of the 25 logicals.

### 6.2.8.5 Ion Direct Events Data

The ion direct events products for high rate science, low rate science, calibration mode and high voltage engineering are all of the same format and in the same file; covering PACKETID 0x1F, 0x6F, 0x7F and 0x8F.

Direct Event (DE) data records the full resolution data on an event-by-event basis, as opposed to the other data products which are collapsed based on product type over an accumulation period. Whereas JAD\_L20\_HLC\_ION\_TOF\_\* data will collect the number of incident ions at each energy step falling within each TOF bin over an accumulation period, Direct Event data record the anode, TOF bin, and ESA step on an event by event basis. Because of this the data volume of Direct Events is too large to provide a continuous record and only a subset is returned. Direct Events will be of most use in performing spot validation of the other data products.

#### 6.2.8.5.1 JAD\_L20\_ALL\_ION\_DER\_\*

The DE-Words contained in the JAD\_L20\_ALL\_ION\_DER\_\* data require decoding, and have been decoded in the JAD\_L20\_ALL\_ION\_DES\_\* file, see Table 53, which we expect science users to use in preference.

Table 51: Format of Level 2 data records for JAD\_L20\_ALL\_ION\_DER\_\*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 36 for bytes 1 to 70.</i>				
71	0	16	DE_COL_SUB_SEQ_COUNT	Direct Events Collection sub-sequence count. Resets to 0 at the start of the playback of a new collection cycle. Increments for each produced packet, before data policing, thus acting as an indicator for data policing loss. Maximum value is 19,999 unless the data is taken from High Rate Science (HRS), when the maximum is 3599. See PACKET_MODE or PACKETID objects to see if in HRS.
73	0	34656	DATA	DATA: Direct Event Two-Byte Words Array of 16-bit raw direct events. A Direct Event is information about each specific particle that hit the Ion sensor. [See PDS JADE SIS document for JAD_L20_ALL_ION_DES for a table on how to decode this 2-byte word.] Note, not all 2166 bytes are used, see DE_SIZE Object, and this object has to be padded to size.
4405	0	16	DE_SIZE	Array size of Direct Events to use. The above data array can vary in size, but PDS records must be a fixed size, so the end is padded with fill values. This value tells you how many values should be used (starting from the beginning).

### 6.2.8.5.2 JAD\_L20\_ALL\_ION\_DER\_\*

This is the same data as for the JAD\_L20\_ALL\_ION\_DER\_\* products (from the same JADE packet IDs), except the DATA object's data is split out in to its many meanings. Table 52 describes how the two-byte word can either be an *event* word, a *boundary* word, a *sweep marker* word or a *fill value* (occasionally required for padding the DER DATA to a fixed size), and then how to split up the bit pattern for each. Each JAD\_L20\_ALL\_ION\_DER\_\* DATA word then becomes an entire JAD\_L20\_ALL\_ION\_DER\_\* record. As such, one JAD\_L20\_ALL\_ION\_DER\_\* record can become (up to) 2,166 JAD\_L20\_ALL\_ION\_DER\_\* records. If the DER DATA word was fill then no JAD\_L20\_ALL\_ION\_DER\_\* record is written. Technically the Sweep Number is a 14-bit long value, however it has a limit of 1800, which results in bits 13 to 11 always being zero. Direct Events will be of most use in performing spot validation of the other data products.

Since FSW 4.00 the ion deflectors are turned off during HRS, such that 'DFL Step' is always zero, hence the 'Boundary Word' is now essentially identical format for all telemetry modes. This following table is still valid, and is also true for earlier FSW versions (e.g. FSW 3).

*Table 52: Description of DATA two-byte words for JAD\_L20\_ALL\_ION\_DER\_\* files to show how it is split out for the JAD\_L20\_ALL\_ION\_DER\_\* files.*

Bit number	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Event Word	0	TOF								Anode ID				QF2	0	QF0
Boundary Word LRS/CAL/HVE	1	0	0	0	0	0	0	0	0	ESA Step				0	0	0
Boundary Word HRS	1	0	0	0	0	0	0	0	0	ESA Step				DFL Step		
Sweep Marker Word	1	1	Sweep Number (max 1800)													
			0	0	0	Sweep Number										
Fill Value	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1

The format of the JAD\_L20\_ALL\_ION\_DER\_\* data records is given on the next page, Table 53, and extends over 2 pages.

Table 53: Format of Level 2 data records for JAD L20 ALL ION DES \*

Byte	Bit	Length (bits)	Name	Description
<i>See Level 2 binary header from Table 35 and Table 36 for bytes 1 to 70.</i>				
71	0	16	DE_COL_SUB_SEQ_COUNT	Direct Events Collection sub-sequence count. Resets to 0 at the start of the playback of a new collection cycle. Increments for each produced packet, before data policing, thus acting as an indicator for data policing loss. Maximum value is 19,999 unless the data is taken from High Rate Science (HRS), when the maximum is 3599. See PACKET_MODE or PACKETID objects to see if in HRS.
73	0	8	DE_BAD	Bad Direct Event Two-Byte Word = 0 is good, Direct Event word is valid. = 1 is bad, Direct Event word is invalid. The two-byte DE Words found in JAD_L20_ALL_ION_DER_* files are split out bit by bit in JAD_L20_ALL_ION_DES_* files, however only certain combinations are valid. If a non-valid bit combination is found, all objects for that record in this file are set to their MISSING_CONSTANT value. [Possible reason for invalid words are SEUs (single event upsets) where a bit is altered in memory. While very rare, we believe such a SEU occurred in Direct Event data at SCLK 494493538 (2015-245). SEUs may occur in other JADE products too, but the bit structure of direct events make their identification easier.]
74	0	8	DE_EVENT0_BOUNDARY1_MARKER2	Direct Event, or Boundary, or Sweep Marker, Word. 0 = Direct Event Word 1 = Boundary Word 2 = Sweep Marker Word 255 = Fill Value - all other DE_* objects should also be their MISSING_CONSTANT VALUE To decode the original bit pattern of a DE_WORD: 0 if bit 15 = 0 1 if bit 15 = 1 and bit 14 = 0 2 if bit 15 = 1 and bit 14 = 1
75	0	16	DE_SWEEP_NUMBER	Direct Event Sweep Number. (bits 13-0) Value is only given when DE_EVENT0_BOUNDARY1_MARKER2 is 2, otherwise equals MISSING_CONSTANT.
77	0	8	DE_ESA_STEP	Direct Event ESA Step. (bits 7-3) Value is only given when DE_EVENT0_BOUNDARY1_MARKER2 is 1, otherwise equals MISSING_CONSTANT.
78	0	8	DE_DFL_STEP	Direct Event DFL Step. (bits 2-0) Value is only given when DE_EVENT0_BOUNDARY1_MARKER2 is 1, otherwise equals MISSING_CONSTANT.



Byte	Bit	Length (bits)	Name	Description
79	0	16	DE_TOF	<p>Direct Event TOF value. (bits 14-7)</p> <p>0-252: Valid TOF measurement (min_TOF to 330ns).</p> <p>253 : TOF with Start overload.</p> <p>254 : TOF value below minimum resolution.</p> <p>255 : TOF too long.</p> <p>65535: Fill value = MISSING_CONSTANT (Value in telemetry is 1 byte (0-255) only, but upcast to 2 bytes here to allow a MISSING_CONSTANT value to be added.)</p> <p>Value is only given when DE_EVENT0_BOUNDARY1_MARKER2 is 0, otherwise equals MISSING_CONSTANT.</p>
81	0	8	DE_ANODE_ID	<p>Direct Event Anode ID. (bits 6-3)</p> <p>0-11: Valid Anode ID, 0-11.</p> <p>12-13: Reserved (should never be seen).</p> <p>14 : No Anode ID between Start and Stop.</p> <p>15 : Two non-adjacent Anodes IDs between Start and Stop.</p> <p>Value is only given when DE_EVENT0_BOUNDARY1_MARKER2 is 0, otherwise equals MISSING_CONSTANT.</p>
82	0	8	DE_QUALITY_FLAG_2	<p>Direct Event Quality Flag 2: (bit 2)</p> <p>Two Adjacent Anode IDs between Start and Stop.</p> <p>0 = Flag not triggered,</p> <p>1 = Flag triggered.</p> <p>Value is only given when DE_EVENT0_BOUNDARY1_MARKER2 is 0, otherwise equals MISSING_CONSTANT.</p>
83	0	8	DE_QUALITY_FLAG_1	<p>Direct Event Quality Flag 1: (bit 1)</p> <p>Reserved - should be 0.</p> <p>Value is only given when DE_EVENT0_BOUNDARY1_MARKER2 is 0, otherwise equals MISSING_CONSTANT.</p>
84	0	8	DE_QUALITY_FLAG_0	<p>Direct Event Quality Flag 0: (bit 0)</p> <p>Additional Start(s) between Start and Stop.</p> <p>0 = Flag not triggered,</p> <p>1 = Flag triggered.</p> <p>Value is only given when DE_EVENT0_BOUNDARY1_MARKER2 is 0, otherwise equals MISSING_CONSTANT.</p>

## 6.2.9 Level 3 data files [for file versions 01, 02 and 03](#)

[This section \(6.2.9\) and sub-sections are only for Level 3 file versions 01, 02 and 03. If you are after Level 3 file version 04, go to section 6.2.10.](#)

The Level 3 data files are binary and have files ending in the extension .DAT. Accompanying them in the same directory are the label files with the same filename but the extension .LBL.

For example, the PDS file pairs will have the following paths in the Volume:

```
ROOT/DATA/yyyy/yyyyddd/subdir/JAD_L30_aaa_bbb_ccc_uuu_YYYYddd_Vnn.DAT
ROOT/DATA/yyyy/yyyyddd/subdir/JAD_L30_aaa_bbb_ccc_uuu_YYYYddd_Vnn.LBL
```

The format file (same filename minus the date part, but including the version number, with the extension .FMT) accompanying (and already listed within) the LBL files are usually found in the LABEL directory at the root of the volume – however it was decided to exclude this LABEL directory (and therefore exclude FMT files) as they are redundant and may be copy/pasted out of the LBL files. [FMT files are made locally for JADE file production, but do not get to the PDS.]

See section 3.1 for the explanation of JAD\_L30\_aaa\_bbb\_ccc\_uuu\_YYYYddd\_Vnn, and *subdir* is the subdirectory name given in Table 17.

There are currently [67](#) different Level 3 product types, [see Table 54 for their sizes](#), but they are similar and they all have the same [16-objects \(per version\)](#) as a header. [File versions 01, 02 and 03 are all the same format. File version 04 \(and future versions\) are a different format, and are discussed later in section 6.2.10.](#)

*Table 54: Size of a record of each Level 3 product, by version number<sup>a,b</sup>*

<a href="#">Version (nn)</a>	<a href="#">Product</a>	<a href="#">Bytes per record</a>	<a href="#">Objects per record</a>
<a href="#">01, 02, 03</a>	<a href="#">JAD L30 HLS ION LOG CNT Vnn</a>	<a href="#">83488</a>	<a href="#">47</a>
<a href="#">01, 02, 03</a>	<a href="#">JAD L30 HLS ION TOF CNT Vnn</a>	<a href="#">100476</a>	<a href="#">56</a>
<a href="#">01, 02, 03</a>	<a href="#">JAD L30 HRS ELC ALL CNT Vnn</a>	<a href="#">160042</a>	<a href="#">48</a>
<a href="#">01, 02, 03</a>	<a href="#">JAD L30 HRS ELC TWO CNT Vnn</a>	<a href="#">106790</a>	<a href="#">48</a>
<a href="#">01, 02, 03</a>	<a href="#">JAD L30 HRS ION ANY CNT Vnn</a>	<a href="#">40224</a>	<a href="#">47</a>
<a href="#">01, 02, 03</a>	<a href="#">JAD L30 LRS ELC ANY CNT Vnn</a>	<a href="#">160036</a>	<a href="#">49</a>
<a href="#">01, 02, 03</a>	<a href="#">JAD L30 LRS ION ANY CNT Vnn</a>	<a href="#">259872</a>	<a href="#">47</a>
<a href="#">Version (nn)</a>	<a href="#">Product</a>	<a href="#">Bytes per record</a>	<a href="#">Objects per record</a>
<a href="#">04</a>	<a href="#">JAD L30 HLS ION LOG CNT Vnn</a>	<a href="#">45120</a>	<a href="#">51</a>
<a href="#">04</a>	<a href="#">JAD L30 HLS ION TOF CNT Vnn</a>	<a href="#">98228</a>	<a href="#">58</a>
<a href="#">04</a>	<a href="#">JAD L30 HRS ELC ALL CNT Vnn</a>	<a href="#">86346</a>	<a href="#">52</a>
<a href="#">04</a>	<a href="#">JAD L30 HRS ELC TWO CNT Vnn</a>	<a href="#">57670</a>	<a href="#">52</a>
<a href="#">04</a>	<a href="#">JAD L30 HRS ION ANY CNT Vnn</a>	<a href="#">21824</a>	<a href="#">51</a>
<a href="#">04</a>	<a href="#">JAD L30 LRS ELC ANY CNT Vnn</a>	<a href="#">86340</a>	<a href="#">53</a>
<a href="#">04</a>	<a href="#">JAD L30 LRS ION ANY CNT Vnn</a>	<a href="#">140096</a>	<a href="#">51</a>

[\(a\) Level 3 versions 01 to 03 are an identical format.](#)

[\(b\) Versions not listed are expected to have the version 04 format.](#)

To save space in this document, Table 56 gives the 34-object header for the binary files for Level 3 products [versions 01, 02 and 03](#), which is then used throughout. This is the same for all, except the PACKETID (which can change within a product type for Level 3 data) that gives a different description for each packet, shown in [blue](#), and the last 4 objects that have the same names but different sizes. The rest of the data product is the same format (floats) but may have different sizes. The UTC entries are not side by side due to PDS rules requiring multi-byte words to start on even byte boundaries, so are spaced by 1-byte words.

Efforts were made to keep the objects as similar as possible (both in name and dimensions), as shown in Figure 10. Some may consider this redundant but this is deliberately done so that the same code may be used on different datasets. For example a 64 by 48 object may only contain 64 unique values that change with the 1<sup>st</sup> dimension during low rate science files, however during high rate science files both the 1<sup>st</sup> and 2<sup>nd</sup> dimension values change – since these objects are the same dimension the same code may then be used to analyze both high and low rate science files.

In order to have fewer products than level 2 had, like ones were grouped together to give just [67](#) products per unit, with the unit of counts per second being the base file, that files with other units are to be created from. Data from high voltage engineering and calibration modes are excluded from level 3 data, as they are not designed for science use (possibly with highly variable MCPs voltages for MCP tests).

Level 3 data should be scientifically useful data, however there is still an object called ISSUES. This is for occasions where the data is scientifically valid, but may not be similar to its neighbors. For instance, the data may be accumulating records over 30 second accumulation times, but the last record was during a mode change so there's only 13 seconds. The data for those 13 seconds are valid, but for consistency the end user may wish to disregard and only use the full 30 second data that's available. This ISSUES object allows such occurrences to be flagged easily.

If a level 2 high rate or low rates science record is unsuitable for science work, a level 3 record [will/may](#) still be created, however the DATA object will be replaced with MISSING\_CONSTANT fill values. This is to allow a user to know that high or low rate data was deliberately excluded, but does exist in level 2 data. However when calibration mode data is excluded (as not for science), no equivalent record of fill values will exist in the level 3 data.

[The MISSING\\_CONSTANT for the objects DATA, DATA SIGMA, BACKGROUND and BACKGROUND SIGMA is -1 \(not -999999\) in Level 3 versions 01, 02 and 03 data \(but not version 04\). See section 6.2.11.19 for more details.](#)

[Table 55](#) lists the Level 3 products and which Level 2 products were used to get them. There are no high voltage engineering data in level 3 (no JAD\_L20\_HVE\*), nor ion direct events (no JAD\_aaa\_ION\_DER nor JAD\_aaa\_ION\_DES).

*Table 55: Mapping Level 2 data files to Level 3 data files*

<u>Level 2 Data Product</u>	<u>Path</u>	<u>Level 3 Data Product</u>
<u>JAD_L20_HRS_ELC_ALL</u>	----->	<u>JAD_L30_HRS_ELC_ALL_CNT</u>
<u>JAD_L20_LRS_ELC_ANY</u>	----->	<u>JAD_L30_HRS_ELC_TWO_CNT</u>
<u>JAD_L20_HLC_ION_LOG</u>	Remove CAL data	<u>JAD_L30_LRS_ELC_ANY_CNT</u>
<u>JAD_L20_HRS_ION_ANY</u>	----->	<u>JAD_L30_HLS_ION_LOG_CNT</u>
<u>JAD_L20_LRS_ION_ANY</u>	----->	<u>JAD_L30_HRS_ION_ANY_CNT</u>
<u>JAD_L20_HLC_ION_TOF</u>	Remove CAL data	<u>JAD_L30_LRS_ION_ANY_CNT</u>
		<u>JAD_L30_HLS_ION_TOF_CNT</u>

As ion species [2-filesrecords](#) go in the same level 3 products, it is possible to have consecutive records with the same time stamp. The difference will be in the PACKETID that tells you which particular ion species that record is for. Likewise JAD\_L30\_LRS\_ELC\_ANY\_CNT may contain records from any of the 3 electron sensors, however a given time will only ever have a record from one sensor record.

Note that the LBL/FMT files describe DATA, DATA\_SIGMA, BACKGROUND, BACKGROUND\_SIGMA, DIM1\_\*, DIM2\_\* and transformation matrices DESPUN\_SC\_TO\_J2000 and J2000\_TO\_RTP as 2D or 3D containers (containers in containers than hold a scalar). If you read the object in as a 1D vector then it should be reformed by the user to a 2D or 3D array. The 1D ordering is based on c, in that the last dimension changes fastest, i.e. if a 1D array is x=[1, 2, 3, 4, 5, 6] and that should be a 3x2 array y, then:

$$y[0][0] = 1; \quad y[0][1] = 2; \quad y[1][0] = 3; \quad y[1][1] = 4; \quad y[2][0] = 5; \quad y[2][1] = 6;$$

*Table 54: Size of a record of each Level 3 product.*

Product	Bytes per record	Objects per record
JAD_L30_HLS_ION_LOG_CNT_V01	83488	47
JAD_L30_HLS_ION_TOF_CNT_V01	100476	56
JAD_L30_HRS_ELC_ALL_CNT_V01	160042	48
JAD_L30_HRS_ELC_TWO_CNT_V01	106790	48
JAD_L30_HRS_ION_ANY_CNT_V01	40224	47
JAD_L30_LRS_ELC_ANY_CNT_V01	160036	49
JAD_L30_LRS_ION_ANY_CNT_V01	259872	47

*Table 55: Mapping Level 2 data files to Level 3 data files*

Level 2 Data Product	Path	Level 3 Data Product
<del>JAD_L20_HRS_ELC_ALL</del>	<del>-----&gt;</del>	<del>JAD_L30_HRS_ELC_ALL_CNT</del>
<del>JAD_L20_LRS_ELC_ANY</del>	<del>-----&gt;</del>	<del>JAD_L30_HRS_ELC_TWO_CNT</del>
<del>JAD_L20_LRS_ELC_ANY</del>	<del>-----&gt;</del>	<del>JAD_L30_LRS_ELC_ANY_CNT</del>
<del>JAD_L20_HLC_ION_LOG</del>	<del>Remove CAL data</del>	<del>JAD_L30_HLS_ION_LOG_CNT</del>
<del>JAD_L20_HRS_ION_ANY</del>	<del>-----&gt;</del>	<del>JAD_L30_HRS_ION_ANY_CNT</del>
<del>JAD_L20_LRS_ION_ANY</del>	<del>-----&gt;</del>	<del>JAD_L30_LRS_ION_ANY_CNT</del>
<del>JAD_L20_HLC_ION_TOF</del>	<del>Remove CAL data</del>	<del>JAD_L30_HLS_ION_TOF_CNT</del>

Object	Data Type	Total Number of Bytes	JAD_L30_HRS_ELC_ALL	JAD_L30_HRS_ELC_TWO	JAD_L30_IRS_ELC_ANY	JAD_L30_CAL_ELC_ALL	JAD_L30_HRS_ION_ANY	JAD_L30_IRS_ION_ANY	JAD_L30_CAL_ION_ANY	JAD_L30_HIS_ION_TOF	JAD_L30_CAL_ION_TOF	JAD_L30_HIS_ION_LOG	JAD_L30_CAL_ION_LOG
DIMO_UTC	char[21]	21	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
PACKETID	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIMO_UTC_UPPER	char[21]	21	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
PACKET_MODE	int8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIMO_UTC_LOWER	char[21]	21	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
PACKET_SPECIES	int8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
ACCUMULATION_TIME	uint16[1]	2	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DATA_UNITS	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_BACKGROUND	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_DEAD_TIME	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_MAG	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_JADE_METAKERNEL	int16[1]	2	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_JADE_CALIB	int16[1]	2	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
FSW_VERSION	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_R	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_R_UPPER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_R_LOWER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LAT	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LAT_UPPER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LAT_LOWER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LOCAL_TIME	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LOCAL_TIME_UPPER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LOCAL_TIME_LOWER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_JUPITER_J2000XYZ	float[3]	12	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_VEL_JUPITER_J2000XYZ	float[3]	12	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_VEL_ANGULAR_J2000XYZ	float[3]	12	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_SPIN_PERIOD	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DESPUN_SC_TO_J2000	float[3,3]	36	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
J2000_TO_JSSXYZ	float[3,3]	36	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
J2000_TO_JSSRTP	float[3,3]	36	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
MCP_VOLTAGE	float	4, 8 or 12	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
ISSUES	uint32	4 or 8	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
TIMESTAMP_WHOLE	uint32	4 or 8	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
TIMESTAMP_SUB	uint16	2 or 4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DATA	float[64,n]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DATA_SIGMA	float[64,n]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
BACKGROUND	float[64,n]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
BACKGROUND_SIGMA	float[64,n]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM1_E	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM1_E_UPPER	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM1_E_LOWER	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM2_ELEVATION	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM2_ELEVATION_UPPER	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM2_ELEVATION_LOWER	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM2_AZIMUTH_DESPUN	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM2_AZIMUTH_DESPUN_UPPER	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM2_AZIMUTH_DESPUN_LOWER	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM3_TOF	float[n=93]	372								✓	✓		
DIM3_TOF_UPPER	float[n=93]	372								✓	✓		
DIM3_TOF_LOWER	float[n=93]	372								✓	✓		
TOF_WITH_START_OVERLOAD	float[64]	256								✓	✓		
TOF_WITH_START_OVERLOAD_SIGMA	float[64]	256								✓	✓		
TOF_TOO_SHORT	float[64]	256								✓	✓		
TOF_TOO_SHORT_SIGMA	float[64]	256								✓	✓		
TOF_TOO_LONG	float[64]	256								✓	✓		
TOF_TOO_LONG_SIGMA	float[64]	256								✓	✓		
MAG_VECTOR	float[3]	12	✓	✓	✓	✓							
ESENSOR	uint16[1]	2			✓								
Number of Objects			48	48	49	48	47	47	47	56	56	47	47

Figure 10: Breaking out the JADE Level 3 [Version 01](#), [02](#) and [03](#) products in to the different PDS Objects to allow similarities to be drawn.

Grey columns represent calibration files for JADE operations use that will not go to the PDS. Blue text values do not need to be in level 3 files, but aids cross comparison with level 2 data, and red text are extra values that may be useful.  $m = n$  for all but TOF products, where  $m = 1$  because of the 3<sup>rd</sup> TOF dimension.

The following table (over 7 pages) describes the header that is identical for all the following data [version 01, 02 and 03](#) products (and is based on Level 3 Version 01 FMT files). The names and word type (int/float/etc.) for all level [23 version 01, 02 and 03](#) data is also summarized in Figure 10. Any text in *red italics* is a note that is not in the FMT file, while any text in **blue boldface** may change depending on the product (usually just the product ID or species number). This color system will apply for format tables throughout the rest of section 6.2.

Table 56: Format of Level 3 data record header [for Versions 01, 02 and 03](#)

Byte	Length (bytes)	Name	Fmt*	Units	Description
1	21	DIM0.UTC	UTC string	Time	UTC timestamp at center (not start) of record. Format is yyyy-dddTHH:MM:SS.sss where yyyy = year, ddd = day of year, HH = hour, MM = minute, SS.sss = decimal seconds to millisecond resolution. Note: Duration of record can be found in S.I. seconds by DIM0.UTC_UPPER - DIM0.UTC_LOWER. Do not confuse this with the ACCUMULATION_TIME object, which is the number of spacecraft clock ticks for accumulation. While 1 tick is approximately 1 second, it is not identical.
22	1	PACKETID	uint8	None	Packet ID (DPID), Data Product Identifier <b>Low Rate Science – Electron</b> <b>One electron sensor per record:</b> <b>Sensor E060 is PACKETID = 104 (0x68)</b> <b>Sensor E180 is PACKETID = 106 (0x6A)</b> <b>Sensor E300 is PACKETID = 107 (0x6B)</b> <b>[There is no PACKETID = 105]</b> <i>Note: A value of 255 indicates Unknown, which can be used for higher order products that use a mix of packets.</i>
23	21	DIM0.UTC_UPPER	UTC string	Time	0th Dimension of DATA: Time - upper limit. See DIM0.UTC for description.

Byte	Length (bytes)	Name	Fmt*	Units	Description
44	1	PACKET_MODE	int8	None	<p>Packet Mode, describes type of data telemetry.</p> <ul style="list-style-type: none"> <li>-2 = HSK / Housekeeping Engineering (Level 2 only)</li> <li>-1 = HVE / High Voltage Engineering (Level 2 only)</li> <li>0 = CAL / MCP Calibration Science (Level 2 only)</li> <li>1 = LRS / Low Rate Science</li> <li>2 = HRS / High Rate Science</li> <li>3 = DRS / DeRived Science from LRS and/or HRS</li> <li>127 = Unknown</li> <li>254 = Wrong - but HSK, see below. (Level 2 only)</li> <li>255 = Wrong - but HVE, see below. (Level 2 only)</li> </ul> <p>(Note, this could also be calculated via PACKETID.)</p> <p>If you have 254 or 255 then your code is incorrect, check you read a signed byte, rather than unsigned.</p>
45	21	DIM0.UTC_LOWER	UTC string	Time	<p>0th Dimension of DATA: Time - lower limit. See DIM0.UTC for description.</p>
66	1	PACKET_SPECIES	int8	None	<p>Packet Species, describes type of plasma data.</p> <ul style="list-style-type: none"> <li>-1 = electrons</li> <li>0 = ion species 0, SP0</li> <li>1 = ion species 1, SP1</li> <li>2 = ion species 2, SP2</li> <li>3 = ion species 3, SP3</li> <li>4 = ion species 4, SP4</li> <li>5 = ion species 5, SP5</li> <li>6 = ion species 6, SP6</li> <li>7 = ion species 7, SP7</li> <li>8 = Sum of SP3, SP4 and SP5</li> <li>9 = All ions /* or any ion, e.g. TOF and LOG */</li> <li>10 = Single ion species derived from TOF data</li> <li>127 = Unknown</li> <li>255 = Wrong - but electrons, see below.</li> </ul> <p>If you have 255 then your code is incorrect, check you read a signed byte, rather than unsigned.</p>



Byte	Length (bytes)	Name	Fmt*	Units	Description
67	2	ACCUMULATION_TIME	uint16	SCLK ticks	<p>Accumulation Time.  Number of seconds over which the data in this product was collected (Science Program).</p> <p><i>Note: Duration of record can be found in S.I. seconds by DIM0.UTC_UPPER - DIM0.UTC_LOWER. Do not confuse this with the ACCUMULATION_TIME object, which is the number of spacecraft clock ticks for accumulation.</i></p> <p><i>While 1 tick is approximately 1 second, it is not identical.</i></p> <p><i>ACCUMULATION_TIME is left in spacecraft clock ticks to both aid matching with the level 2 data and to help filtering for data taken in a particular mode.</i></p>
69	1	DATA_UNITS	uint8	None	<p>Data units correspond to:</p> <ul style="list-style-type: none"> <li>0 = All counts in the accumulation period</li> <li>1 = All counts divided by number of views</li> </ul> <p><b>/* 0 and 1 are for Level 2 data only – but keeping the numbering convention */</b></p> <ul style="list-style-type: none"> <li>2 = Counts per second</li> <li>/* S.I. science units: */</li> <li>3 = Differential Energy Flux [1/( m<sup>2</sup> sr s)]</li> <li>4 = Differential Number Flux [1/( m<sup>2</sup> sr s J)]</li> <li>5 = Phase Space Density [ m<sup>-6</sup> s<sup>3</sup> ]</li> <li>/* Convenient (non-S.I.) science units: */</li> <li>6 = Differential Energy Flux [1/(cm<sup>2</sup> sr s)]</li> <li>7 = Differential Number Flux [1/(cm<sup>2</sup> sr s keV)]</li> <li>8 = Phase Space Density [ cm<sup>-6</sup> s<sup>3</sup> ]</li> </ul> <p>/* As new products are developed this list will increase */</p> <p>/* If a number is not listed, */</p> <p>/* try a LBL/FMT file from a recent date. */</p> <p>255 = Unknown.</p>
70	1	SOURCE_BACKGROUND	uint8	None	<p>Source of Background values (see BACKGROUND object) that have been removed from the DATA object.</p> <ul style="list-style-type: none"> <li>0 = None: No background has been removed</li> <li>1 = Background anode (electron sensors only)</li> </ul> <p><b>/* As new background removal methods are developed this list will increase */</b></p> <p>255 = Unknown.</p>

Byte	Length (bytes)	Name	Fmt*	Units	Description
71	1	SOURCE_DEAD_TIME	uint8	None	Source of Dead Time Correction Method 0 = None: Data has not been Dead Time corrected. 255 = Unknown.
72	1	SOURCE_MAG	uint8	None	Source of MAG data Except case 0 and 1, PAYLOAD (pl) co-ordinate MAG files were used at 1s (or 2s if no 1s) resolution. 0 = None: No MAG data in this product. 1 = From Juno JADE's Level 2 files. (From spacecraft and therefore uncalibrated.) This is independent to JADE Level 2 version number as it does not change with versions. [Note MAG data in JADE files may be affected by the Juno time stutter.] 3n = Juno's MAG's Level 3 version n calibrated files, e.g. 34 means version 4, so: 30 = From Juno MAG's Level 3 version 00 quicklook payload files. (These are temporary files not in PDS.) 31 = From Juno MAG's Level 3 version 01 calibrated payload files. 32 = From Juno MAG's Level 3 version 02 calibrated payload files. Likewise 33 to 39 being Level 3 version 3 to 9. 255 = Unknown.  If you see a number not listed above, there may be later versions of MAG data - find the latest available LBL file for this product and see what that has listed.

Byte	Length (bytes)	Name	Fmt*	Units	Description
73	2	SOURCE_JADE_METAKERNEL	int16	None	<p>The JADE SPICE metakernel used to get the time, position, velocity, orientation and transformation objects in this file. The metakernel lists the many individual spice kernels used, which are archived by NAIF and not in this PDS volume. The JADE SPICE metakernel may be found in the CALIB directory of this PDS volume, with filenames of:  JAD_L30_SPICE_METAKERNEL_#####.TXT where ##### is the SOURCE_JADE_METAKERNEL object number (with leading zeros and positive). If any of the kernels within the metakernel are not reconstructed (but reference or predicted) for the time in question, this value will be negative. Within the JADE PDS archive this value should always be positive.</p>
75	2	SOURCE_JADE_CALIB	int16	None	<p>The JADE calibration files list used to convert the engineering units of Level 2 data to the scientific units in this file. Similar to the SPICE metakernel list, this lists the many individual calibration files used, each of which may be found in the CALIB directory on this PDS volume.</p> <p>This list may be found in the CALIB directory of this PDS volume, with filenames of:  JAD_L30_CALIB_LIST_#####.TXT where ##### is the SOURCE_JADE_CALIB object number (with leading zeros and positive). If any of the calibration files listed are not final at the time in question, this value will be negative. (Newer calibration files will have a higher version and simply be listed in a newer SOURCE_JADE_CALIB file.) Within the JADE PDS archive this value should always be positive. However a version 00 file (for team use or uploaded to JSOC, not PDS) may have negative values with predicted positions/orientations/transformations.</p>
77	4	FSW_VERSION	f	None	<p>Flight Software version used. Number should be to 2 decimal places, with rounding. e.g. 4.00, 4.10, 4.20.</p>

Byte	Length (bytes)	Name	Fmt*	Units	Description
81	4	SC_POS_R	f	R <sub>J</sub>	Juno radial distance from Jupiter. (1 R <sub>J</sub> = 71492.0 km) [Values may be greater than VALID_MAXIMUM during cruise to Jupiter before primary mission.]
85	4	SC_POS_R_UPPER	f	R <sub>J</sub>	Juno radial distance from Jupiter - upper limit. See SC_POS_R for description.
89	4	SC_POS_R_LOWER	f	R <sub>J</sub>	Juno radial distance from Jupiter - lower limit. See SC_POS_R for description.
93	4	SC_POS_LAT	f	Degrees	Juno Latitude above Jupiter. (0 = Equatorial)
97	4	SC_POS_LAT_UPPER	f	Degrees	Juno Latitude above Jupiter - upper limit. See SC_POS_LAT for description.
101	4	SC_POS_LAT_LOWER	f	Degrees	Juno Latitude above Jupiter - lower limit. See SC_POS_LAT for description.
105	4	SC_POS_LOCAL_TIME	f	Hours	Juno Local Time from Jupiter. 00 = Midnight 06 = Dawn 12 = Noon 18 = Dusk
109	4	SC_POS_LOCAL_TIME_UPPER	f	Hours	Juno Local Time from Jupiter - upper limit. See SC_POS_LOCAL_TIME for description.
113	4	SC_POS_LOCAL_TIME_LOWER	f	Hours	Juno Local Time from Jupiter - lower limit. See SC_POS_LOCAL_TIME for description.
117	12	SC_POS_JUPITER_J2000XYZ	f	km	Juno position from Jupiter in J2000 cartesian co-ordinates [x,y,z] (units km). [Values may be outside of VALID_MIN/MAX range (~140R <sub>J</sub> ) during cruise to Jupiter before primary mission.]
129	12	SC_VEL_JUPITER_J2000XYZ	f	km/s	Juno Velocity with respect to Jupiter in J2000 Cartesian co-ordinates [V <sub>x</sub> ,V <sub>y</sub> ,V <sub>z</sub> ] (units km/s).
141	12	SC_VEL_ANGULAR_J2000XYZ	f	rads/s	Juno Angular Velocity in cartesian co-ordinates [AV <sub>x</sub> ,AV <sub>y</sub> ,AV <sub>z</sub> ] (units radians/s). (This is calculated with the SPICE ckgpav command where ref=J2000. SPICE defines it as 'This is the axis about which the reference frame tied to the instrument is rotating in the right-handed sense.')
153	4	SC_SPIN_PERIOD	f	Seconds	Juno spin period (seconds). This is not useful during spacecraft maneuvers.

Byte	Length (bytes)	Name	Fmt*	Units	Description
157	36	DESPUN_SC_T O_J2000	f	None	Rotation matrix from despun spacecraft co-ordinates to J2000. This is a 3x3 matrix, but if read in as a 1x9 stream then the 1D stream is [a,b,c, d,e,f, g,h,i] and the 2D matrix would be [a,b,c d,e,f g,h,i]
193	36	J2000_TO_JSS XYZ	f	None	Rotation matrix from J2000 co-ordinates to JSS xyz (JSS = Jupiter-De-Spun-Sun, see SIS for details). This is a 3x3 matrix, but if read in as a 1x9 stream then the 1D stream is [a,b,c, d,e,f, g,h,i] and the 2D matrix would be [a,b,c d,e,f g,h,i]
229	36	J2000_TO_JSS RTP	f	None	Rotation matrix from J2000 co-ordinates to JSS RTP, where RTP is Jupiter centered right handed R-Theta-Phi. (JSS = Jupiter-De-Spun-Sun, see SIS for details.) This is a 3x3 matrix, but if read in as a 1x9 stream then the 1D stream is [a,b,c, d,e,f, g,h,i] and the 2D matrix would be [a,b,c d,e,f g,h,i]
265		MCP_VOLTAGE			The last 4 objects of this header all start at byte 265 and have the same names, but three different sizes depending on the JADE product. For the ion products go to Table 57. For the HRS electrons (all) go to Table 58, or Table 59 for HRS electrons (two). For the LRS electrons go to Table 60.
		ISSUES			
		TIMESTAMP_ WHOLE			
		TIMESTAMP_ SUB			

Fmt\* is shortened for the table and is decoded in PDS format as: f = PC\_REAL (float), uint8/uint16/uint32 are = one/two/four-byte LSB\_UNSIGNED\_INTEGER and int8/int16/int32 = one/two/four byte LSB\_INTEGER.

Table 57: Format of Level 3 data record subheader for Level 3 ion products. [for V01, V02 and V03](#)

Byte	Length (bytes)	Name	Fmt*	Units	Description
265	4	MCP_VOLTAGE	f	Volts	MCP Voltage on sensor.
269	8	ISSUES	uint32	None	Issues or potential issues in this data record. [Two values for ions as this is the ISSUES object from both the ping and pong level 2 packets used to create this record.]... <b>The rest is a direct copy of the Level 2 ISSUES object, see Table 38 for description.</b>
277	8	TIMESTAMP_WHOLE	uint32	Ticks	Timestamps (Whole Second) of JADE Level 2 packets used to make this Level 3 record. (Both the ping and pong level 2 packets.)
285	4	TIMESTAMP_SUB	uint16	Subticks	Timestamps (Subsecond) of JADE Level 2 packets used to make this Level 3 record. (Both the ping and pong level 2 packets.)

Table 58: Format of Level 3 data record subheader for JAD\_L30\_HRS\_ELC\_ALL\_\* [for V01, V02 and V03](#)

Byte	Length (bytes)	Name	Fmt*	Units	Description
265	12	MCP_VOLTAGE	f	Volts	MCP Voltages on the three electron sensors, E060, E180 and E300 respectively.
277	4	ISSUES	uint32	None	Issues or potential issues in this data record. ... <b>The rest is a direct copy of the Level 2 ISSUES object, see Table 38 for description.</b>
281	4	TIMESTAMP_WHOLE	uint32	Ticks	Timestamp (Whole Second) of JADE Level 2 packet used to make this Level 3 record.
285	2	TIMESTAMP_SUB	uint16	Subticks	Timestamp (Subsecond) of JADE Level 2 packet used to make this Level 3 record.

Table 59: Format of Level 3 data record subheader for JAD\_L30\_HRS\_ELC\_TWO\_\* [for V01, V02 and V03](#)

Byte	Length (bytes)	Name	Fmt*	Units	Description
265	8	MCP_VOLTAGE	f	Volts	MCP Voltages on the two electron sensors in this product, E060 and E180 respectively.
273	4	ISSUES	uint32	None	Issues or potential issues in this data record. ... <b>The rest is a direct copy of the Level 2 ISSUES object, see Table 38 for description.</b>
277	4	TIMESTAMP_WHOLE	uint32	Ticks	Timestamp (Whole Second) of JADE Level 2 packet used to make this Level 3 record.
281	2	TIMESTAMP_SUB	uint16	Subticks	Timestamp (Subsecond) of JADE Level 2 packet used to make this Level 3 record.

Table 60: Format of Level 3 data record subheader for JAD\_L30\_LRS\_ELC\_ANY\_\* [for V01, V02 and V03](#)

Byte	Length (bytes)	Name	Fmt*	Units	Description
265	4	MCP_VOLTAGE	f	Volts	MCP Voltage on sensor.
269	4	ISSUES	uint32	None	Issues or potential issues in this data record. ... <b>The rest is a direct copy of the Level 2 ISSUES object, see Table 38 for description.</b>
273	4	TIMESTAMP_WHOLE	uint32	Ticks	Timestamp (Whole Second) of JADE Level 2 packet used to make this Level 3 record.
277	2	TIMESTAMP_SUB	uint16	Subticks	Timestamp (Subsecond) of JADE Level 2 packet used to make this Level 3 record.

In general, the rest of the format for the different products have the same object names (see Figure 10), however their size (byte length) and start bytes will differ. The descriptions are also much the same when they have the same object name, with only DATA really changing (text that may alter between products is shown in **blue boldface**).

### 6.2.9.1 Electron Data [for V01, V02 and V03](#)

#### 6.2.9.1.1 JAD\_L30\_HRS\_ELC\_ALL\_CNT\_\* [for V01, V02 and V03](#)

The electron product for high rate science is PACKETID 0x8E and includes data from all three electron sensors.

The DATA object is 2-D, 64 energies x 48 look directions, and is described in Table 61, and continues over the next 4 pages.

This product is a combination of look directions from all 3 JADE-E sensors, but E300 was turned off in 2016, hence those anodes that would have been from E300 are populated with the MISSING\_CONSTANT (-1) value.

Table 61: Format of Level 3 data records for JAD\_L30\_HRS\_ELC\_ALL\_CNT [for V01, V02 and V03](#)

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 56 and Table 58 for bytes 1 to 286.</i>					
287	12288	DATA	f	Counts/s	DATA: Counts/Second 64 Energy x 48 Look Directions. <i>[Note: E300 was turned off in 2016, so the last 16 look directions (32-47) are usually populated with the MISSING_CONSTANT value of -1.]</i>
12575	12288	DATA_SIGMA A	f	Counts/s	DATA_SIGMA 1-sigma uncertainties on values in object DATA, such that true value = DATA +/- DATA_SIGMA. See DATA entry above for size information.
24863	12288	BACKGROUND D	f	Counts/s	Background value removed from DATA. No further background removal is required. If you wish to do your own background removal, add this object to DATA then you can remove a background via your own method. The background values here were found from either a background anode or JADE's own ground method.
37151	12288	BACKGROUND D_SIGMA	f	Counts/s	BACKGROUND_SIGMA 1-sigma uncertainties on values in object BACKGROUND, such that true value = BACKGROUND +/- BACKGROUND_SIGMA. See BACKGROUND entry above for size information.



Byte	Length (bytes)	Name	Fmt*	Units	Description
49439	12288	DIM1_E	f	eV/q	1st Dimension of DATA: Energy - center eV/q value. Upper and lower limits are given by the objects DIM1_E_UPPER and DIM1_E_LOWER.
61727	12288	DIM1_E_UPPER	f	eV/q	1st Dimension of DATA: Energy - upper eV/q limit. See DIM1_E for description.
74015	12288	DIM1_E_LOWER	f	eV/q	1st Dimension of DATA: Energy - lower eV/q limit. See DIM1_E for description.
86303	12288	DIM2_ELEVATION	f	Degrees	2nd Dimension of DATA: Spacecraft elevation - center value. Spacecraft elevation (degs) is analogous to latitude on a sphere. In spacecraft xyz co-ords: +z is equivalent to elevation = +90 degs -z is equivalent to elevation = -90 degs (The communication dish is directed along +z) xy-plane at z = 0 is equivalent to elevation = 0.  Note, 2nd dimension is really look direction which has an elevation and azimuth; hence two objects describe this: DIM2_ELEVATION and DIM2_AZIMUTH_DESPUN.
98591	12288	DIM2_ELEVATION_UPPER	f	Degrees	2nd Dimension of DATA: S/C elevation - upper limit. See DIM2_ELEVATION for description.
110879	12288	DIM2_ELEVATION_LOWER	f	Degrees	2nd Dimension of DATA: S/C elevation - lower limit. See DIM2_ELEVATION for description.

Byte	Length (bytes)	Name	Fmt*	Units	Description
123167	12288	DIM2_AZIMUTH_DESPUN	f	Degrees	<p>2nd Dimension of DATA: Despun S/C azimuth - center value. Spacecraft azimuth (degs) is analogous to longitude on a sphere. In spacecraft xyz co-ords:  +x is equivalent to azimuth = 0 degs  +y is equivalent to azimuth = 90 degs  -x is equivalent to azimuth = 180 degs  -y is equivalent to azimuth = 270 degs  +x is equivalent to azimuth = 360 degs  +y is equivalent to azimuth = 450 degs  The 'Despun' azimuth angle varies because Juno spins, where azimuth = 0 is defined as +x when spin phase equals zero (e.g. despun x-z plane contains the ECLIPJ2000 north).</p> <p>The relationship between despun azimuth and spin phase (which decreases during a spin) is simply:  Despun Azimuth = 360 degrees - Spin Phase</p> <p>Because a lower to upper limit could occur over a 360 degree boundary, the VALID_MINIMUM and VALID_MAXIMUM go from 0 to +720 degrees:  e.g. [lower, center, upper] = [-10, 5, 20] would be given instead as = [350, 365, 380]</p> <p>Note, 2nd dimension is really look direction which has an elevation and azimuth; hence two objects describe this:  DIM2_ELEVATION and DIM2_AZIMUTH_DESPUN.</p>
135455	12288	DIM2_AZIMUTH_DESPUN_UPPER	f	Degrees	2nd Dimension of DATA: Despun S/C azimuth - upper limit. See DIM2_AZIMUTH_DESPUN for description.
147743	12288	DIM2_AZIMUTH_DESPUN_LOWER	f	Degrees	2nd Dimension of DATA: Despun S/C azimuth - lower limit. See DIM2_AZIMUTH_DESPUN for description.

Byte	Length (bytes)	Name	Fmt*	Units	Description
160031	12	MAG_VECTO R	f	nT	MAG vector in nT, 3 components [X, Y, Z] MAG range is +/- 16 G, hence limits. This xyz coordinate system is despun spacecraft; see the definitions of DIM2_ELEVATION and DIM2_AZIMUTH: +X is when [azimuth, elevation] = [ 0, 0] degrees, +Y is when [azimuth, elevation] = [ 90, 0] degrees, +Z is when elevation = 90 degrees.

6.2.9.1.2 JAD\_L30\_HRS\_ELC\_TWO\_CNT\_\* [for V01, V02 and V03](#)

This is a repeat of the JAD\_L30\_HRS\_ELC\_ALL\_CNT\_\* file, but with E300 data removed to provide a smaller (but still large) file, thus only contains E060 and E180 data. This product was introduced when it was decided not to use sensor E300 in flight operations, however the HRS electron data packet would still return zeros for E300.

The DATA object is 2-D, 64 energies x 32 look directions (rather than 48 look directions), and is described in Table 62.

Table 62: Format of Level 3 data records for JAD\_L30\_HRS\_ELC\_TWO\_CNT [for V01, V02 and V03](#)

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 56 and Table 58 for bytes 1 to 286.</i>					
283	8192	DATA	f	Counts/s	DATA: Counts/Second 64 Energy x 32 Look Directions.
8475	8192	DATA_SIGMA	f	Counts/s	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
16667	8192	BACKGROUND	f	Counts/s	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
24859	8192	BACKGROUND_SIGMA	f	Counts/s	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
33051	8192	DIM1_E	f	eV/q	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
41243	8192	DIM1_E_UPPER	f	eV/q	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
49435	8192	DIM1_E_LOWER	f	eV/q	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
57627	8192	DIM2_ELEVATION	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
65819	8192	DIM2_ELEVATION_UPPER	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
74011	8192	DIM2_ELEVATION_LOWER	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
82203	8192	DIM2_AZIMUTH_DESPUN	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
90395	8192	DIM2_AZIMUTH_DESPUN_UPPER	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
98587	8192	DIM2_AZIMUTH_DESPUN_LOWER	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
106779	12	MAG_VECTOR	f	nT	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>

### 6.2.9.1.3 JAD\_L30\_LRS\_ELC\_ANY\_CNT\_\* [for V01, V02 and V03](#)

The electron products for low rate science are PACKETIDs 0x68, 0x6A and 0x6B, and includes data from one electron sensor per record (only one sensor is on at any given time).

The DATA object is 2-D, 64 energies x 48 look directions, and is described in Table 63.

Practically there are only two differences between this and the

JAD\_L30\_HRS\_ELC\_ALL\_CNT\_\* file:

- 1) The MCP\_VOLTAGE object is a singular value here (for the one sensor) as opposed to 3 values for the HRS case (one for each of the sensors). This in turn makes the start byte of all following objects 8 bytes earlier in the LRS product compared to the HRS product. The description of MCP\_VOLTAGE in the FMT file is slightly different to reflect this.
- 2) This product has an extra object at the end; called ESENSOR that states which of the three sensors is in use (60, 180 or 300). This does not exist in the HRS product as the data array always includes all three sensors.

So the only difference between tables Table 61 and Table 63 are the first column byte values are offset by 8 (as indicated in the first red row), and Table 63 has the ESENSOR product at the end.

If using FSW4.00 (April 2015 only) data for this product (cruise solar wind only, no Jupiter science use) all *DIM2\_AZIMUTH\_DESPUN* values are replaced with the fill value 65535 due to the reverse anode mapping bug (see section 6.2.8.1.4).

Table 63: Format of Level 3 data records for JAD\_L30\_LRS\_ELC\_ANY\_CNT for V01, V02 and V03

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 56 and Table 60 for bytes 1 to 278.</i>					
279	12288	DATA	f	Counts/s	DATA: Counts/Second 64 Energy x 48 Look Directions. <i>This is the same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
12567	12288	DATA_SIGMA	f	Counts/s	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
24855	12288	BACKGROUND	f	Counts/s	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
37143	12288	BACKGROUND_SIGMA	f	Counts/s	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
49431	12288	DIM1_E	f	eV/q	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
61719	12288	DIM1_E_UPPER	f	eV/q	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
74007	12288	DIM1_E_LOWER	f	eV/q	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
86295	12288	DIM2_ELEVATION	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
98583	12288	DIM2_ELEVATION_UPPER	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
110871	12288	DIM2_ELEVATION_LOWER	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
123159	12288	DIM2_AZIMUTH_DESPUN	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
135447	12288	DIM2_AZIMUTH_DESPUN_UPPER	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
147735	12288	DIM2_AZIMUTH_DESPUN_LOWER	f	Degrees	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
160023	12	MAG_VECTOR	f	nT	<i>Same description as from Table 61 for JAD_L30_HRS_ELC_ALL_CNT.</i>
160035	2	ESENSOR	uint16	None	ESENSOR - which one of the three electron sensors is this record for. Values can only be 60, 180 or 300 for electron sensor E060, E180 or E300 respectively. Note: each sensor also has a different PACKETID. <i>This object is NOT in the product for JAD_L30_HRS_ELC_ALL_CNT.</i>

## 6.2.9.2 Ion Species Data [for V01, V02 and V03](#)

### 6.2.9.2.1 JAD\_L30\_HRS\_ION\_ANY\_CNT\_\* [for V01, V02 and V03](#)

The ion species products for high rate science cover PACKETIDs 0x80-0x87. Each ion species has its own packet; therefore several packets of different species may have the same time stamp. The DATA object is 2-D, 64 energies x 12 look directions, and is described in Table 64, and continues over the next 3 pages.

Table 64: Format of Level 3 data records for JAD\_L30\_HRS\_ION\_ANY\_CNT\* [for V01, V02 and V03](#)

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 56 and Table 57 for bytes 1 to 288.</i>					
289	3072	DATA	f	Counts/s	DATA: Counts/Second 64 Energy x 12 Look Directions.
3361	3072	DATA_SIGMA A	f	Counts/s	DATA_SIGMA 1-sigma uncertainties on values in object DATA, such that true value = DATA +/- DATA_SIGMA. See DATA entry above for size information.
6433	3072	BACKGROUN D	f	Counts/s	Background value removed from DATA. No further background removal is required. If you wish to do your own background removal, add this object to DATA then you can remove a background via your own method. The background values here were found from either a background anode or JADE's own ground method.
9505	3072	BACKGROUN D_SIGMA	f	Counts/s	BACKGROUND_SIGMA 1-sigma uncertainties on values in object BACKGROUND, such that true value = BACKGROUND +/- BACKGROUND_SIGMA. See BACKGROUND entry above for size information.
12577	3072	DIM1_E	f	eV/q	1st Dimension of DATA: Energy - center eV/q value. Upper and lower limits are given by the objects DIM1_E_UPPER and DIM1_E_LOWER.
15649	3072	DIM1_E_UPP ER	f	eV/q	1st Dimension of DATA: Energy - upper eV/q limit. See DIM1_E for description.
18721	3072	DIM1_E_LOW ER	f	eV/q	1st Dimension of DATA: Energy - lower eV/q limit. See DIM1_E for description.

Byte	Length (bytes)	Name	Fmt*	Units	Description
21793	3072	DIM2_ELEVATION	f	Degrees	<p>2nd Dimension of DATA: Spacecraft elevation - center value. Spacecraft elevation (degs) is analogous to latitude on a sphere. In spacecraft xyz co-ords:</p> <ul style="list-style-type: none"> <li>+z is equivalent to elevation = +90 degs</li> <li>-z is equivalent to elevation = -90 degs (The communication dish is directed along +z)</li> <li>xy-plane at z = 0 is equivalent to elevation = 0.</li> </ul> <p>Note, 2nd dimension is really look direction which has an elevation and azimuth; hence two objects describe this: DIM2_ELEVATION and DIM2_AZIMUTH_DESPUN.</p>
24865	3072	DIM2_ELEVATION_UPPER	f	Degrees	<p>2nd Dimension of DATA: S/C elevation - upper limit. See DIM2_ELEVATION for description.</p>
27937	3072	DIM2_ELEVATION_LOWER	f	Degrees	<p>2nd Dimension of DATA: S/C elevation - lower limit. See DIM2_ELEVATION for description.</p>



Byte	Length (bytes)	Name	Fmt*	Units	Description
31009	3072	DIM2_AZIMUTH_DESPUN	f	Degrees	<p>2nd Dimension of DATA: Despun S/C azimuth - center value. Spacecraft azimuth (degs) is analogous to longitude on a sphere. In spacecraft xyz co-ords:</p> <ul style="list-style-type: none"> <li>+x is equivalent to azimuth = 0 degs</li> <li>+y is equivalent to azimuth = 90 degs</li> <li>-x is equivalent to azimuth = 180 degs</li> <li>-y is equivalent to azimuth = 270 degs</li> <li>+x is equivalent to azimuth = 360 degs</li> <li>+y is equivalent to azimuth = 450 degs</li> </ul> <p>The 'Despun' azimuth angle varies because Juno spins, where azimuth = 0 is defined as +x when spin phase equals zero (e.g. despun x-z plane contains the ECLIPJ2000 north).</p> <p>The relationship between despun azimuth and spin phase (which decreases during a spin) is simply: Despun Azimuth = 360 degrees - Spin Phase</p> <p>Because a lower to upper limit could occur over a 360 degree boundary, the VALID_MINIMUM and VALID_MAXIMUM go from 0 to +720 degrees: e.g. [lower, center, upper] = [-10, 5, 20] would be given instead as = [350, 365, 380]</p> <p>Note, 2nd dimension is really look direction which has an elevation and azimuth; hence two objects describe this: DIM2_ELEVATION and DIM2_AZIMUTH_DESPUN.</p>
34081	3072	DIM2_AZIMUTH_DESPUN_UPPER	f	Degrees	2nd Dimension of DATA: Despun S/C azimuth – upper limit. See DIM2_AZIMUTH_DESPUN for description.
37153	3072	DIM2_AZIMUTH_DESPUN_LOWER	f	Degrees	2nd Dimension of DATA: Despun S/C azimuth – lower limit. See DIM2_AZIMUTH_DESPUN for description.

6.2.9.2.2 JAD\_L30\_LRS\_ION\_ANY\_CNT\_\* [for V01, V02 and V03](#)

The ion species products for low rate science (PACKETID 0x60-0x67). Each ion species has its own packet; therefore several packets of different species may have the same time stamp. The DATA object is 2-D, 64 energies x 78 look directions, and is described in Table 65. The basic format of this file is identical to the HRS counterpart, except there are 78 look directions here instead of 12. As such the start byte and lengths change, but the object names and descriptions are the same (except for the description of the DATA object).

Table 65: Format of Level 3 data records for JAD\_L30\_LRS\_ION\_ANY\_CNT [for V01, V02 and V03](#)

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 56 and Table 57 for bytes 1 to 288.</i>					
289	19968	DATA	f	Counts/s	DATA: Counts/Second 64 Energy x 78 Look Directions.
20257	19968	DATA_SIGMA	f	Counts/s	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
40225	19968	BACKGROUND	f	Counts/s	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
60193	19968	BACKGROUND_SIGMA	f	Counts/s	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
80161	19968	DIM1_E	f	eV/q	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
100129	19968	DIM1_E_UPPER	f	eV/q	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
120097	19968	DIM1_E_LOWER	f	eV/q	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
140065	19968	DIM2_ELEVATION	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
160033	19968	DIM2_ELEVATION_UPPER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
180001	19968	DIM2_ELEVATION_LOWER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
199969	19968	DIM2_AZIMUTH_DESPUN	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
219937	19968	DIM2_AZIMUTH_DESPUN_UPPER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
239905	19968	DIM2_AZIMUTH_DESPUN_LOWER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>

### 6.2.9.3 Ion Time of Flight Data [for V01, V02 and V03](#)

#### 6.2.9.3.1 JAD\_L30\_HLS\_ION\_TOF\_CNT\_\* [for V01, V02 and V03](#)

The ion time of flight products for high and low rate science, covering PACKETIDs 0x69 and 0x89.

The DATA object is 3-D, 64 energies x 1 look direction x 93 TOF channels, and is described in Table 66 (over [32](#) pages). This product usually has 96 TOF channels with the last 3 having special meanings, but for level 3 data the last 3 channels have been removed and given their own objects within this file.

This product is usually considered to be a 2 dimensional array of energy by TOF channel. However all other JADE data is Energy by look direction, so to keep things similar, this product is a 3 dimensional array of 64 energies by 1 look direction by 93 TOF channels. There is only 1 look direction, but given the ion instrument covers 270 degrees field of view in elevation over the 12 anodes, and this product sums all 12 anodes, this leads to some interesting azimuth and elevation numbers. The DIM2\_AZIMUTH objects will use the respective azimuth of anodes 4-11 (anodes 0-3 azimuths would normally be 180 degrees from those). However DIM2\_ELEVATION will range from -90 to +180 degrees (spanning 270 degrees) with a center value of +45 degrees. As such, elevation of +90 to +180 is being used to describe the contribution of anodes 3, 2, 1 and 0 that are technically covering elevations of +90 down to 0 degrees but with an azimuth 180 degrees different.

The object names (and descriptions, DATA description excepted) are identical to the other level 3 ion products, but with 6 TOF only objects on the end. [\(Text that may alter between products is shown in blue boldface, e.g. version number of files should match the version number of the DAT files.\)](#)

Table 66: Format of Level 3 data records for JAD\_L30\_HLS\_ION\_TOF\_CNT for V01, V02 and V03

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 56 and Table 57 for bytes 1 to 288.</i>					
289	23808	DATA	f	Counts/s	<p>DATA: Counts/Second 64 Energy x 1 Look Direction x 93 Channels. <del>The 93 elements collapse the original 128 TOF channels as:</del>  <del>[ 0]: TOF channels 0—1</del>  <del>[ 1]: TOF channel 2</del>  <del>[ 2]: TOF channel 3</del>  <del>[ 3]: TOF channel 4</del>  <del>...</del>  <del>[59]: TOF channel 60</del>  <del>[60]: TOF channel 61</del>  <del>[61]: TOF channels 62—63</del>  <del>[62]: TOF channels 64—65</del>  <del>...</del>  <del>[70]: TOF channels 80—81</del>  <del>[71]: TOF channels 82—83</del>  <del>[72]: TOF channel 84</del>  <del>[73]: TOF channel 85</del>  <del>[74]: TOF channel 86</del>  <del>[75]: TOF channel 87</del>  <del>[76]: TOF channel 88</del>  <del>[77]: TOF channels 89—90</del>  <del>[78]: TOF channels 91—92</del>  <del>...</del>  <del>[89]: TOF channels 113—114</del>  <del>[90]: TOF channels 115—116</del>  <del>[91]: TOF channels 117—118</del>  <del>[92]: TOF channels 119—124</del></p> <p>These channels are expressed as a duration in seconds in object DIM3_TOF- <del>Original TOF channels 125, 126, and 127</del>for more details see the <a href="#">TOF_CHANNEL_TO_SECONDS_HLC_V03.CSV</a> file in the CALIB directory of this PDS archive. <del>The Level 2 data had 96 channels, those last 3</del> are now objects TOF_WITH_START_OVERLOAD, TOF_TOO_SHORT and TOF_TOO_LONG respectively.</p>
24097	23808	DATA_SIGMA	f	Counts/s	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
47905	23808	BACKGROUND	f	Counts/s	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>

Byte	Length (bytes)	Name	Fmt*	Units	Description
71713	23808	BACKGROUND_SIGMA	f	Counts/s	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
95521	256	DIM1_E	f	eV/q	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
95777	256	DIM1_E_UPPER	f	eV/q	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
96033	256	DIM1_E_LOWER	f	eV/q	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
96289	256	DIM2_ELEVATION	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
96545	256	DIM2_ELEVATION_UPPER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
96801	256	DIM2_ELEVATION_LOWER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
97057	256	DIM2_AZIMUTH_DESPUN	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
97313	256	DIM2_AZIMUTH_DESPUN_UPPER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
97569	256	DIM2_AZIMUTH_DESPUN_LOWER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
97825	372	DIM3_TOF	f	Seconds	3rd Dimension of DATA: Time Of Flight - center value. (Seconds)
98197	372	DIM3_TOF_UPPER	f	Seconds	3rd Dimension of DATA: Time Of Flight - upper limit. See DIM3_TOF for description.
98569	372	DIM3_TOF_LOWER	f	Seconds	3rd Dimension of DATA: Time Of Flight - lower limit. See DIM3_TOF for description.
98941	256	TOF_WITH_START_OVERLOAD	f	Counts/s	TOF with start overload: Counts/Second A signal pulse that is too strong (above a threshold) in the electronics. Multiple start-overloads that occur within a 330ns event window are counted each time in the Logicals Start Overload, but only once here.

Byte	Length (bytes)	Name	Fmt*	Units	Description
99197	256	TOF_WITH_START_OVERLOAD_SIGMA	f	Counts/s	TOF with start overload uncertainty: Counts/Second 1-sigma uncertainties on values in object TOF_WITH_START_OVERLOAD such that true value = TOF_WITH_START_OVERLOAD +/- TOF_WITH_START_OVERLOAD_SIGMA. See TOF_WITH_START_OVERLOAD entry above for size information.
99453	256	TOF_TOO_SHORT	f	Counts/s	TOF too short: Counts/Second TOF underflow: Count of TOF measurements that did not timeout, but resulted in a measurement smaller than the sensor could measure.
99709	256	TOF_TOO_SHORT_SIGMA	f	Counts/s	TOF too short uncertainty: Counts/Second 1-sigma uncertainties on values in object TOF_TOO_SHORT such that true value = TOF_TOO_SHORT +/- TOF_TOO_SHORT_SIGMA. See TOF_TOO_SHORT entry above for size information.
99965	256	TOF_TOO_LONG	f	Counts/s	TOF too long: Counts/Second <a href="#">TOF overflow: Count of TOF measurements that resulted in no stop signal arriving within 330ns of the start signal.</a>
100221	256	TOF_TOO_LONG_SIGMA	f	Counts/s	TOF too long uncertainty: Counts/Second 1-sigma uncertainties on values in object TOF_TOO_LONG such that true value = TOF_TOO_LONG +/- TOF_TOO_LONG_SIGMA. See TOF_TOO_LONG entry above for size information.

#### 6.2.9.4 Ion Logicals Data [for V01, V02 and V03](#)

##### 6.2.9.4.1 JAD\_L30\_HLS\_ION\_LOG\_CNT\_\* [for V01, V02 and V03](#)

The ion logicals products for high and low rate science, covering PACKETID 0x6C and 0x8C. The DATA object is 2-D, 64 energies x 25 logicals (each with variable look directions), and is described in Table 67 (over 3 pages).

Given the ion instrument covers 270 degrees field of view in elevation, this leads to some interesting azimuth and elevation numbers, as elevation can range from -90 to +180 degrees; see the descriptions below. e.g. if Azimuth is 200 degrees and elevation is 100 degrees, that's equivalent to an azimuth of 20 (200-180) degrees and an elevation of 80 (180-100) degrees. That is anode 0 will have an azimuth 180 degrees from anode's 7, which is described in the DIM2 objects, however the logicals that combine all individual anodes the DIM2 values will use the azimuth from anodes 4-11 for all, but the elevations range will be -90 to +180 degrees.

The 25 logical counters here are the same as for level 2 data.

Table 67: Format of Level 3 data records for JAD\_L30\_HLS\_ION\_LOG\_CNT [for V01, V02 and V03](#)

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 56 and Table 57 for bytes 1 to 288.</i>					
289	6400	DATA	f	Counts/s	<p>DATA: Counts/Second            64 Energy x 25 Logicals.            The 25 Logical counters are:            [ 0]: Anode 0 Events            [ 1]: Anode 1 Events            [ 2]: Anode 2 Events            ...            [10]: Anode 10 Events            [11]: Anode 11 Events            [12]: Background Events            The above 13 logicals are raw count hits, independent of whether a TOF Event has begun. Adjacent and Non-Adjacent hits will be counted in both anodes. As such, anode counts can exceed All Stops [15] counts.            The Background anode [12] is not included in Adjacent and Non-Adjacent calculations.            [13]: Start Overload            Start signal exceeds threshold level.            [14]: All Starts            Independent of whether a TOF Event has begun, usually starts a TOF Event.            [15]: All Stops            Independent of whether a TOF Event has begun, usually ends a TOF Event.            If an event is seen on multiple anodes this counter is still only incremented once, therefore this is usually less than the sum of anodes 0 to 11.            The Background anode is not included in All Stops, just anodes 0 to 11.            [16]: Non-Adjacent Anodes            This is either two non-neighbor anodes (anodes 0-11 only), or more than 2 anodes.            [17]: Adjacent Anodes            A count hit was measured in neighboring anodes; other products (e.g. Ion Species) will assign this to just the lower anode.            [18]: Stop without Start            A stop signal was received before a TOF Event was initiated by a start.</p> <p><i>Continues on next page.</i></p>



Byte	Length (bytes)	Name	Fmt*	Units	Description
					<p><i>Continues from previous page.</i></p> <p>[19]: Dual Start A TOF Event had started but one or more other start signals were received before a stop signal or the TOF Event overflowed.</p> <p>[20]: Start in Process Time The number of TOF Events started, can be less than All Starts [14].</p> <p>[21]: TOF Underflow Received a stop event before 1 tap, that is 1.6ns, the base unit of TOF times.</p> <p>[22]: TOF Overflow No stop signal arrived within timeout of 330ns.</p> <p>[23]: Invalid TOF Event If the TOF Event is measured in 1 anode (anodes 0-11 only) or two neighboring anodes (anodes 0-11 only) it is valid. Otherwise it is invalid, unless it was an underflow in which case the Underflow [21] counter is increased instead of this counter (i.e. an Underflow event is considered valid). Therefore, if the event is not an Underflow event, it will be invalid if one of these three situations is met:</p> <ul style="list-style-type: none"> <li>- hit in more than two anodes, or</li> <li>- hit in two non-neighbor anodes, or</li> <li>- no anodes hit at all.</li> </ul> <p>The latter is different to overflow events [22] which are considered valid.</p> <p>The Background anode is not considered in any of these calculations.</p> <p>[24]: Event Strobe The number of TOF Events completed, by a stop signal or over/underflow, usually the same as Start in Process Time [20].</p> <p>Note that the look directions of logicals 12-24 cover the combined look directions of logicals 0-11. Anodes 0-3 will have an azimuth 180 degrees greater than anodes 4-11. For logicals 12-24 that cover all 12 anodes, the azimuth of anodes 4-11 will be used, but elevation will be -90 to +180 degrees, centered at +45 degrees (between anodes 5 and 6).</p>
6689	6400	DATA_SIGMA	f	Counts/s	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>

Byte	Length (bytes)	Name	Fmt*	Units	Description
13089	6400	BACKGROUND	f	Counts/s	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
19489	6400	BACKGROUND_SIGMA	f	Counts/s	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
25889	6400	DIM1_E	f	eV/q	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
32289	6400	DIM1_E_UPPER	f	eV/q	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
38689	6400	DIM1_E_LOWER	f	eV/q	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
45089	6400	DIM2_ELEVATION	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
51489	6400	DIM2_ELEVATION_UPPER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
57889	6400	DIM2_ELEVATION_LOWER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
64289	6400	DIM2_AZIMUTH_DESPUN	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
70689	6400	DIM2_AZIMUTH_DESPUN_UPPER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>
77089	6400	DIM2_AZIMUTH_DESPUN_LOWER	f	Degrees	<i>Same description as from Table 64 for JAD_L30_HRS_ION_ANY_CNT.</i>

### 6.2.9.5 Level 3 conversion of data for V01, V02 and V03

Moved to section 6.2.11 (as it's independent of version number).

## 6.2.10 Level 3 data files for file version 04+

*This section (6.2.10) and sub-sections are only for Level 3 file version 04. If you are after Level 3 file versions 01, 02 and 03, go to section 6.2.9.*

The Level 3 data files are binary and have files ending in the extension .DAT. Accompanying them in the same directory are the label files with the same filename but the extension .LBL.

For example, the PDS file pairs will have the following paths in the Volume:

ROOT/DATA/yyyy/yyyyddd/subdir/JAD\_L30\_aaa\_bbb\_ccc\_uuu\_YYYYddd\_Vnn.DAT  
ROOT/DATA/yyyy/yyyyddd/subdir/JAD\_L30\_aaa\_bbb\_ccc\_uuu\_YYYYddd\_Vnn.LBL

The format file (same filename minus the date part, but including the version number, with the extension .FMT) accompanying (and already listed within) the LBL files are usually found in the LABEL directory at the root of the volume – however it was decided to exclude this LABEL directory (and therefore exclude FMT files) as they are redundant and may be copy/pasted out of the LBL files. [FMT files are made locally for JADE file production, but do not get to the PDS.]

See section 3.1 for the explanation of JAD\_L30\_aaa\_bbb\_ccc\_uuu\_YYYYddd\_Vnn, and subdir is the subdirectory name given in Table 17.

There are currently 7 different Level 3 product types, see Table 54 for their sizes, but they are similar and they all have the same objects (per version) as a header. To save space in this document, Table 68 gives the 44-object header for the binary files for Level 3 products version 04(+), which is then used throughout. This is the same for all (with one object name exception), except the PACKETID (which can change within a product type for Level 3 data) that gives a different description for each packet, shown in blue, and the last 4 objects that have the same names but different sizes. The rest of the data product is the same format (floats) but may have different sizes. The UTC entries are not side by side due to PDS rules requiring multi-byte words to start on even byte boundaries, so are spaced by 1-byte words. The exception to the same object names in the header is that ion TOF and ion species have a SOURCE\_SPECIES\_REMAPPED object (= 0 if no remapping), whereas the ion logicals and electron products (that never have remapping) have an object called SPARE\_ZEROS (=0). Since both these objects are one-byte unsigned integers, one may simply use SOURCE\_SPECIES\_REMAPPED for all 7 data products, as the value of zero (no remapping) is still appropriate for ion logicals or electrons.

Efforts were made to keep the objects as similar as possible (both in name and dimensions), as shown in Figure 11. Some may consider this redundant but this is deliberately done so that the same code may be used on different datasets. For example a 64 by 48 object may only contain 64 unique values that change with the 1<sup>st</sup> dimension during low rate science files, however during high rate science files both the 1<sup>st</sup> and 2<sup>nd</sup> dimension values change – since these objects are the same dimension the same code may then be used to analyze both high and low rate science files.

In order to have fewer products than level 2 had, like ones were grouped together to give just 7 products per unit, with the unit of counts per second being the base file, that files with other units

are to be created from. Data from high voltage engineering and calibration modes are excluded from level 3 data, as they are not designed for science use (possibly with highly variable MCPs voltages for MCP tests).

Level 3 data should be scientifically useful data, however there is still an object called ISSUES. This is for occasions where the data is scientifically valid, but may not be similar to its neighbors. For instance, the data may be accumulating records over 30 second accumulation times, but the last record was during a mode change so there's only 13 seconds. The data for those 13 seconds are valid, but for consistency the end user may wish to disregard and only use the full 30 second data that's available. This ISSUES object allows such occurrences to be flagged easily.

If a level 2 high rate or low rates science record is unsuitable for science work, a level 3 record may still be created, however the DATA object will be replaced with MISSING\_CONSTANT fill values. This is to allow a user to know that high or low rate data was deliberately excluded, but does exist in level 2 data. However when calibration mode data is excluded (as not for science), no equivalent record of fill values will exist in the level 3 data.

The MISSING\_CONSTANT for the objects DATA, DATA\_SIGMA, BACKGROUND and BACKGROUND\_SIGMA is -999999 (not -1) in Level 3 version 04+ data (but not versions 01, 02 and 03). See section 6.2.11.19 for more details.

Table 55 lists the Level 3 products and which Level 2 products were used to get them. There are no high voltage engineering data in level 3 (no JAD\_L20\_HVE\*), nor ion direct events (no JAD\_aaa\_ION\_DER nor JAD\_aaa\_ION\_DES).

As ion species records go in the same level 3 products, it is possible to have consecutive records with the same time stamp. The difference will be in the PACKETID that tells you which particular ion species that record is for. Likewise JAD\_L30\_LRS\_ELC\_ANY\_CNT may contain records from any of the 3 electron sensors, however a given time will only ever have a record from one sensor record.

Note that the LBL/FMT files describe DATA, DATA\_SIGMA, BACKGROUND, BACKGROUND\_SIGMA, DIM1 \*, DIM2 \* and transformation matrices DESPUN\_SC\_TO\_J2000 and J2000\_TO\_RTP as 2D or 3D containers (containers in containers than hold a scalar). If you read the object in as a 1D vector then it should be reformed by the user to a 2D or 3D array. The 1D ordering is based on c, in that the last dimension changes fastest, i.e. if a 1D array is  $x=[1, 2, 3, 4, 5, 6]$  and that should be a 3x2 array  $y$ , then:

$$\underline{y[0][0] = 1; \quad y[0][1] = 2; \quad y[1][0] = 3; \quad y[1][1] = 4; \quad y[2][0] = 5; \quad y[2][1] = 6;}$$

Object	Data Type	Total Number of Bytes	Calibration Files												
			JAD_L30_HRS_ELC_ALL	JAD_L30_HRS_ELC_TWC	JAD_L30_LRS_ELC_ANY	JAD_L30_HRS_ION_ANY	JAD_L30_LRS_ION_ANY	JAD_L30_CAL_ION_ANY	JAD_L30_HIS_ION_TOF	JAD_L30_CAL_ION_TOF	JAD_L30_HRS_ION_TOF	JAD_L30_CAL_ION_TOF			
DIM0_UTC	char[21]	21	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
	PACKETID	uint8[1]													
DIM0_UTC_UPPER	char[21]	21	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
	PACKET_MODE	int8[1]													
DIM0_UTC_LOWER	char[21]	21	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
	PACKET_SPECIES	int8[1]													
ACCUMULATION_TIME	uint16[1]	2	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DATA_UNITS	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_BACKGROUND	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_DEAD_TIME	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SPARE_ZEROS	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_SPECIES_REMAPPED	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_MAG	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_JADE_METAKERNEL	int16[1]	2	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SOURCE_JADE_CALIB	int16[1]	2	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
FSW_VERSION	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
LUT_VERSION	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
LUT_VERSION_SUB_LETTER	char[2]	2	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
LUT_SWEEP_TABLE	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
FILE_VERSION	uint8[1]	1	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_R	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_R_UPPER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_R_LOWER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LAT	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LAT_UPPER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LAT_LOWER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LOCAL_TIME	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LOCAL_TIME_UPPER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_LOCAL_TIME_LOWER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_SYSIII_ELONG	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_SYSIII_ELONG_UPPER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_SYSIII_ELONG_LOWER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_POS_JUPITER_J2000XYZ	float[3]	12	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_VEL_JUPITER_J2000XYZ	float[3]	12	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_VEL_ANGULAR_J2000XYZ	float[3]	12	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_SPIN_PERIOD	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_SPIN_PHASE	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_SPIN_PHASE_UPPER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
SC_SPIN_PHASE_LOWER	float[1]	4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DESPUN_SC_TO_J2000	float[3,3]	36	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
J2000_TO_JSSXYZ	float[3,3]	36	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
J2000_TO_JSSRTP	float[3,3]	36	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
MCP_VOLTAGE	float	4, 8 or 12	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
ISSUES	uint32	4 or 8	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
TIMESTAMP_WHOLE	uint32	4 or 8	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
TIMESTAMP_SUB	uint16	2 or 4	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DATA	float[64,n]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DATA_SIGMA	float[64,n]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
BACKGROUND	float[64,n]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
BACKGROUND_SIGMA	float[64,n]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM1_E	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM1_E_UPPER	float[64,m]	Depends													
DIM1_E_LOWER	float[64,m]	Depends													
DIM2_ELEVATION	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM2_ELEVATION_UPPER	float[64,m]	Depends													
DIM2_ELEVATION_LOWER	float[64,m]	Depends													
DIM2_AZIMUTH_DESPUN	float[64,m]	Depends	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
DIM2_AZIMUTH_DESPUN_UPPER	float[64,m]	Depends													
DIM2_AZIMUTH_DESPUN_LOWER	float[64,m]	Depends													
DIM3_TOF	float[n=93]	372								✓	✓				
DIM3_TOF_UPPER	float[n=93]	372													
DIM3_TOF_LOWER	float[n=93]	372													
TOF_WITH_START_OVERLOAD	float[64]	256								✓	✓				
TOF_WITH_START_OVERLOAD_SIGMA	float[64]	256								✓	✓				
TOF_TOO_SHORT	float[64]	256								✓	✓				
TOF_TOO_SHORT_SIGMA	float[64]	256								✓	✓				
TOF_TOO_LONG	float[64]	256								✓	✓				
TOF_TOO_LONG_SIGMA	float[64]	256								✓	✓				
MAG_VECTOR	float[3]	12	✓	✓	✓	✓									
ESENSOR	uint16[1]	2			✓										
<b>Number of Objects</b>			52	52	53	52	51	51	51	58	58	51	51		

Figure 11: Breaking out the JADE Level 3 Version 04+ products in to the different PDS Objects to allow similarities to be drawn. Grey columns represent calibration files for JADE operations use that will not go to the PDS.

Blue text values do not need to be in level 3 files, but aids cross comparison with level 2 data, and red text are extra values that may be useful.  $m = n$  for all but TOF products, where  $m = 1$  because of the 3<sup>rd</sup> TOF dimension.

The following table (over 10 pages) describes the header that is identical for all the following data version 04 (and is based on Level 3 Version 04 FMT files). The names and word type (int/float/etc.) for all level 3 version 04 data is also summarized in Figure 11. Any text in *red italics* is a note that is not in the FMT file, while any text in **blue boldface** may change depending on the product (usually just the product ID or species number). This color system will apply for format tables throughout the rest of section 6.2.

Table 68: Format of Level 3 data record header for Version 04+

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>1</u>	<u>21</u>	<u>DIM0.UTC</u>	<u>UTC string</u>	<u>Time</u>	<p><u>UTC timestamp at center (not start) of record.</u>  <u>Format is yyyy-dddTHH:MM:SS.sss</u>  <u>where yyyy = year, ddd = day of year,</u>  <u>HH = hour, MM = minute,</u>  <u>SS.sss = decimal seconds to millisecond resolution.</u>  <u>Note: Duration of record can be found in S.I. seconds by DIM0.UTC_UPPER - DIM0.UTC_LOWER. Do not confuse this with the ACCUMULATION_TIME object, which is the number of spacecraft clock ticks for accumulation.</u>  <u>While 1 tick is approximately 1 second, it is not identical.</u></p>
<u>22</u>	<u>1</u>	<u>PACKETID</u>	<u>uint8</u>	<u>None</u>	<p><u>Packet ID (DPID), Data Product Identifier</u>  <u><b>High Rate Science – Electron</b></u>  <u><b>Two Electron sensors per record: E060 and E180.</b></u>  <u>(This is the same data as for</u>  <u><b>JAD L30 HRS ELC ALL but with E300</b></u>  <u><b>data removed for a smaller file.)</b></u>  <u><b>PACKETID = 142 (0x8E)</b></u></p>
<u>23</u>	<u>21</u>	<u>DIM0.UTC_UPPER</u>	<u>UTC string</u>	<u>Time</u>	<p><u>0th Dimension of DATA: Time - upper limit.</u>  <u>See DIM0.UTC for description.</u></p>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>44</u>	<u>1</u>	<u>PACKET_MOD</u> <u>E</u>	<u>int8</u>	<u>None</u>	<u>Packet Mode, describes type of data telemetry.</u> <u>-2 = HSK / Housekeeping Engineering (Level 2 only)</u> <u>-1 = HVE / High Voltage Engineering (Level 2 only)</u> <u>0 = CAL / MCP Calibration Science (Level 2 only)</u> <u>1 = LRS / Low Rate Science</u> <u>2 = HRS / High Rate Science</u> <u>3 = DRS / DeRived Science from LRS and/or HRS</u> <u>127 = Unknown</u> <u>254 = Wrong - but HSK, see below. (Level 2 only)</u> <u>255 = Wrong - but HVE, see below. (Level 2 only)</u> <u>(Note, this could also be calculated via PACKETID.)</u> <u>If you have 254 or 255 then your code is incorrect, check you read a signed byte, rather than unsigned.</u>
<u>45</u>	<u>21</u>	<u>DIM0 UTC LO</u> <u>WER</u>	<u>UTC</u> <u>string</u>	<u>Time</u>	<u>0th Dimension of DATA: Time - lower limit.</u> <u>See DIM0 UTC for description.</u>
<u>66</u>	<u>1</u>	<u>PACKET_SPEC</u> <u>IES</u>	<u>int8</u>	<u>None</u>	<u>Packet Species, describes type of plasma data.</u> <u>-1 = electrons</u> <u>0 = ion species 0, SP0</u> <u>1 = ion species 1, SP1</u> <u>2 = ion species 2, SP2</u> <u>3 = ion species 3, SP3</u> <u>4 = ion species 4, SP4</u> <u>5 = ion species 5, SP5</u> <u>6 = ion species 6, SP6</u> <u>7 = ion species 7, SP7</u> <u>8 = Sum of SP3, SP4 and SP5</u> <u>9 = All ions /* or any ion, e.g., TOF and LOG */</u> <u>10 = Single ion species derived from TOF data</u> <u>127 = Unknown</u> <u>255 = Wrong - but electrons, see below.</u> <u>If you have 255 then your code is incorrect, check you read a signed byte, rather than unsigned.</u>



<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>67</u>	<u>2</u>	<u>ACCUMULATI ON_TIME</u>	<u>uint16</u>	<u>SCLK ticks</u>	<p><u>Accumulation Time.</u>  <u>Number of seconds over which the data in this product was collected (Science Program).</u>  <u>Note: Duration of record can be found in S.I. seconds by DIM0.UTC_UPPER - DIM0.UTC_LOWER. Do not confuse this with the ACCUMULATION_TIME object, which is the number of spacecraft clock ticks for accumulation.</u>  <u>While 1 tick is approximately 1 second, it is not identical.</u>  <u>ACCUMULATION_TIME is left in spacecraft clock ticks to both aid matching with the level 2 data and to help filtering for data taken in a particular mode.</u></p>
<u>69</u>	<u>1</u>	<u>DATA_UNITS</u>	<u>uint8</u>	<u>None</u>	<p><u>Data units correspond to:</u>  <u>0 = All counts in the accumulation period</u>  <u>1 = All counts divided by number of views</u>  <u>2 = Counts per second</u>  <u>/* S.I. science units: */</u>  <u>3 = Differential Energy Flux [1/( m^2 sr s )]</u>  <u>4 = Differential Number Flux [1/( m^2 sr s J)]</u>  <u>5 = Phase Space Density [ m^-6 s^3 ]</u>  <u>/* Convenient (non-S.I.) science units: */</u>  <u>6 = Differential Energy Flux [1/(cm^2 sr s )]</u>  <u>7 = Differential Number Flux [1/(cm^2 sr s keV)]</u>  <u>8 = Phase Space Density [ cm^-6 s^3 ]</u>  <u>/* As new products are developed this list will increase */</u>  <u>/* If a number is not listed, */</u>  <u>/* try a LBL/FMT file from a recent date. */</u>  <u>255 = Unknown.</u></p>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>70</u>	<u>1</u>	<u>SOURCE_BAC</u> <u>KGROUND</u>	<u>uint8</u>	<u>None</u>	<p><u>Source of Background values (see BACKGROUND object) that have been removed from the DATA object.</u></p> <p><u>0 = None: No background has been removed</u></p> <p><u>1 = Background anode (electron sensors only)</u></p> <p><u>2 = Background anode (JADE-I only)</u></p> <p><u>3 = Derived from Background anode :</u></p> <p><u>Method 1:</u></p> <p><u>Background coefficients are time independent.</u></p> <p><u>See file in CALIB directory for description.</u></p> <p><u>4 = Derived from Background anode :</u></p> <p><u>Method 2:</u></p> <p><u>Background coefficients are per orbit.</u></p> <p><u>See file in CALIB directory for description.</u></p> <p><u>/* As new background removal methods are developed this list will increase */</u></p> <p><u>255 = Unknown.</u></p>
<u>71</u>	<u>1</u>	<u>SOURCE_SPECIES_REMAP</u> <u>PE</u>	<u>uint8</u>	<u>None</u>	<p><b><u>Source of ion remapping for ION Species/TOF data products:</u></b></p> <p><b><u>0 = None: Data has not been remapped on the ground.</u></b></p> <p><b><u>255 = Unknown.</u></b></p> <p><i><u>A new object for Version 4 files (TOF and ion species only), and for V04 files SOURCE_SPECIES_REMAPPED = 0 always. The JADE team has no current plans to remap the data, but this otherwise spare byte would allow us to track any remapping if carried out.</u></i></p> <p><i><u>Replaced SOURCE_DEAD_TIME from the version 01, 02 and 03 files.</u></i></p> <p><b><u>Or</u></b></p> <p><b><u>Spare Zeroes. Always zero.</u></b></p> <p><b><u>PDS3 format required a padding byte, e.g., a 4-byte integer/float will always start on the 1st or 5th or 9th or 13th... byte of the record.</u></b></p> <p><i><u>A new object for Version 4 files (Electrons or ion logicals only).</u></i></p> <p><i><u>Replaced SOURCE_DEAD_TIME from the version 01, 02 and 03 files.</u></i></p>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>72</u>	<u>1</u>	<u>SOURCE_MAG</u>	<u>uint8</u>	<u>None</u>	<p><u>Source of MAG data</u>  <u>Except case 0 and 1, PAYLOAD (pl) coordinate MAG files were used at 1s (or 2s if no 1s) resolution.</u>  <u>0 = None: No MAG data in this product.</u>  <u>1 = From Juno JADE's Level 2 files. (From spacecraft and therefore uncalibrated.) This is independent to JADE Level 2 version number as it does not change with versions. [Note MAG data in JADE files may be affected by the Juno time stutter.]</u>  <u>3n = Juno's MAG's Level 3 version n calibrated files, e.g., 34 means version 4, so:</u>  <u>30 = From Juno MAG's Level 3 version 00 quicklook payload files. (These are temporary files not in PDS.)</u>  <u>31 = From Juno MAG's Level 3 version 01 calibrated payload files.</u>  <u>32 = From Juno MAG's Level 3 version 02 calibrated payload files.</u>  <u>Likewise, 33 to 39 being Level 3 version 3 to 9.</u>  <u>255 = Unknown.</u></p> <p><u>If you see a number not listed above, there may be later versions of MAG data - find the latest available LBL file for this product and see what that has listed.</u></p>
<u>73</u>	<u>2</u>	<u>SOURCE_JADE_METAKERNEL</u>	<u>int16</u>	<u>None</u>	<p><u>The JADE SPICE metakernel used to get the time, position, velocity, orientation and transformation objects in this file. The metakernel lists the many individual spice kernels used, which are archived by NAIF and not in this PDS volume. The JADE SPICE metakernel may be found in the CALIB directory of this PDS volume, with filenames of:</u>  <u>JAD L30 SPICE METAKERNEL_nnnnn.TXT</u>  <u>where nnnnn is the SOURCE JADE METAKERNEL object number (with leading zeros and positive). If any of the kernels within the metakernel are not reconstructed (but reference or predicted) for the time in question, this value will be negative. Within the JADE PDS archive this value should always be positive.</u></p>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>75</u>	<u>2</u>	<u>SOURCE_JADE_CALIB</u>	<u>int16</u>	<u>None</u>	<p><u>The JADE calibration files list used to convert the engineering units of Level 2 data to the scientific units in this file. Similar to the SPICE metakernel list, this lists the many individual calibration files used, each of which may be found in the CALIB directory on this PDS volume.</u></p> <p><u>This list may be found in the CALIB directory of this PDS volume, with filenames of:</u>  <u>    JAD_L30_CALIB_LIST_nnnnn.TXT</u>  <u>where nnnnn is the SOURCE_JADE_CALIB object number (with leading zeros and positive).</u>  <u>If any of the calibration files listed are not final at the time in question, this value will be negative. (Newer calibration files will have a higher version and simply be listed in a newer SOURCE_JADE_CALIB file.)</u>  <u>Within the JADE PDS archive this value should always be positive. However, a version 00 file (for team use or uploaded to JSOC, not PDS) may have negative values with predicted positions/orientations/transformations.</u></p>
<u>77</u>	<u>4</u>	<u>FSW_VERSION</u>	<u>f</u>	<u>None</u>	<p><u>Flight Software version used.</u>  <u>Number should be to 2 decimal places, with rounding. e.g., 4.00, 4.10, 4.20. i.e., 4.1999998 means 4.20.</u></p>
<u>81</u>	<u>4</u>	<u>LUT_VERSION</u>	<u>f</u>	<u>None</u>	<p><u>LUT (Look Up Table) Version used on JADE.</u>  <u>Number should be to 2 decimal places, with rounding. e.g., 4.00, 4.10, 4.20. i.e., 4.1999998 means 4.20.</u></p>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>85</u>	<u>2</u>	<u>LUT_VERSION</u> <u>_SUB_LETTER</u>	<u>string</u>	<u>None</u>	<p>The letter (if any) associated with the energy table used at the time of this record</p> <p>-- -&gt; No sub letter for this LUT Version</p> <p>-A -&gt; Sub letter is A for this LUT Version</p> <p>-B -&gt; Sub letter is B for this LUT Version</p> <p>-C -&gt; Sub letter is C for this LUT Version</p> <p>etc.</p> <p>For instance, the energy table files are in the CALIB directory of this PDS volume, with names like:</p> <p><u>LUT_4_00_ENERGY_V01.CSV</u> (LUT_VERSION 4.00, no sub letter)</p> <p>or</p> <p><u>LUT_5_01_K_ENERGY_V01.CSV</u> (LUT_VERSION 5.01, sub letter K).</p>
<u>87</u>	<u>1</u>	<u>LUT_SWEEP</u> <u>TABLE</u>	<u>uint8</u>	<u>None</u>	<p><b>The sweep tables the ion sensor used. A level 2 packet will report this as 0-3, However, it requires 2 packets (a ping and a pong) to make a level 3 record: either 0 and 1, or 2 and 3. Therefore, a value of 1 (= 01) means sweep tables 0 and 1 were used, while a value of 23 means sweep tables 2 and 3 were used. This object can only have the value of 1 or 23.</b></p> <p><i>There is a different description for low rate electrons, and different again for high rate electrons.</i></p>
<u>88</u>	<u>1</u>	<u>FILE_VERSION</u>	<u>uint8</u>	<u>None</u>	<p>The version number of the file this record came from.</p> <p>e.g., if you loaded file <u>JAD_L30_LRS_ION_ANY_CNT_2016240_V04.DAT</u> then <u>FILE_VERSION = 4</u>. [<u>FILE_VERSION = 0</u> is never in the PDS, but is used by the JADE team prior to having required calibrations.]</p>
<u>89</u>	<u>4</u>	<u>SC_POS_R</u>	<u>f</u>	<u>R<sub>J</sub></u>	<p>Juno radial distance at time <u>DIM0.UTC</u>, from Jupiter, in units of Jupiter Radii (R<sub>J</sub>). (1 R<sub>J</sub> = 71492.0 km)</p> <p>[Values may be greater than <u>VALID_MAXIMUM</u> during cruise to Jupiter before primary mission.]</p>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>93</u>	<u>4</u>	<u>SC_POS_R_UP PER</u>	<u>f</u>	<u>R<sub>J</sub></u>	<u>Juno radial distance at time DIM0 UTC UPPER, from Jupiter, in units of Jupiter Radii (R<sub>J</sub>). (1 R<sub>J</sub> = 71492.0 km) SC_POS_R_UPPER could be smaller or larger than SC_POS_R, depending if moving inbound or outbound. [Values may be greater than VALID_MAXIMUM during cruise to Jupiter before primary mission.]</u>
<u>97</u>	<u>4</u>	<u>SC_POS_R_LO WER</u>	<u>f</u>	<u>R<sub>J</sub></u>	<u>Juno radial distance at time DIM0 UTC LOWER, from Jupiter, in units of Jupiter Radii (R<sub>J</sub>). (1 R<sub>J</sub> = 71492.0 km) SC_POS_R_LOWER could be smaller or larger than SC_POS_R, depending if moving inbound or outbound. [Values may be greater than VALID_MAXIMUM during cruise to Jupiter before primary mission.]</u>
<u>101</u>	<u>4</u>	<u>SC_POS_LAT</u>	<u>f</u>	<u>Degrees</u>	<u>Juno Latitude at time DIM0 UTC, in both the IAU_JUPITER and JUNO_JSS frames, in units of degrees. (0 = Equatorial) (JUNO_JSS is a despun version of IAU_JUPITER, hence they have identical latitudes.)</u>
<u>105</u>	<u>4</u>	<u>SC_POS_LAT_ UPPER</u>	<u>f</u>	<u>Degrees</u>	<u>Juno Latitude at time DIM0 UTC UPPER, in both the IAU_JUPITER and JUNO_JSS frames, in units of degrees. (0 = Equatorial) SC_POS_LAT_UPPER could be smaller or larger than SC_POS_LAT. (JUNO_JSS is a despun version of IAU_JUPITER, hence they have identical latitudes.)</u>
<u>109</u>	<u>4</u>	<u>SC_POS_LAT_ LOWER</u>	<u>f</u>	<u>Degrees</u>	<u>Juno Latitude at time DIM0 UTC LOWER, in both the IAU_JUPITER and JUNO_JSS frames, in units of degrees. (0 = Equatorial) SC_POS_LAT_LOWER could be smaller or larger than SC_POS_LAT. (JUNO_JSS is a despun version of IAU_JUPITER, hence they have identical latitudes.)</u>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>113</u>	<u>4</u>	<u>SC_POS_LOCAL_TIME</u>	<u>f</u>	<u>Hours</u>	<u>Juno's (jovian) Local Time at time DIM0 UTC, in units of hours.</u> <u>00 = Midnight</u> <u>06 = Dawn</u> <u>12 = Noon</u> <u>18 = Dusk</u>
<u>117</u>	<u>4</u>	<u>SC_POS_LOCAL_TIME_UPPER</u>	<u>f</u>	<u>Hours</u>	<u>Juno's (jovian) Local Time at time DIM0 UTC UPPER, in units of hours.</u> <u>00 = Midnight</u> <u>06 = Dawn</u> <u>12 = Noon</u> <u>18 = Dusk</u>
<u>121</u>	<u>4</u>	<u>SC_POS_LOCAL_TIME_LOWER</u>	<u>f</u>	<u>Hours</u>	<u>Juno's (jovian) Local Time at time DIM0 UTC LOWER, in units of hours.</u> <u>00 = Midnight</u> <u>06 = Dawn</u> <u>12 = Noon</u> <u>18 = Dusk</u>
<u>125</u>	<u>4</u>	<u>SC_POS_SYSIII_ELONG</u>	<u>f</u>	<u>Hours</u>	<u>Juno's (jovian) SYSIII (East) Longitude at time DIM0 UTC, in units of degrees.</u>
<u>129</u>	<u>4</u>	<u>SC_POS_SYSIII_ELONG_UPPER</u>	<u>f</u>	<u>Hours</u>	<u>Juno's (jovian) SYSIII (East) Longitude at time DIM0 UTC UPPER, in units of degrees.</u>
<u>133</u>	<u>4</u>	<u>SC_POS_SYSIII_ELONG_LOWER</u>	<u>f</u>	<u>Hours</u>	<u>Juno's (jovian) SYSIII (East) Longitude at time DIM0 UTC LOWER, in units of degrees.</u>
<u>137</u>	<u>12</u>	<u>SC_POS_JUPITER_J2000XYZ</u>	<u>f</u>	<u>km</u>	<u>Juno position from Jupiter in J2000 Cartesian co-ordinates [x,y,z] (units km).</u> <u>[Values may be outside of VALID_MIN/MAX range (~140Rj) during cruise to Jupiter before primary mission.]</u>
<u>149</u>	<u>12</u>	<u>SC_VEL_JUPITER_J2000XYZ</u>	<u>f</u>	<u>km/s</u>	<u>Juno Velocity with respect to Jupiter in J2000 Cartesian co-ordinates [Vx,Vy,Vz] (units km/s).</u>
<u>161</u>	<u>12</u>	<u>SC_VEL_ANGULAR_J2000XYZ</u>	<u>f</u>	<u>rads/s</u>	<u>Juno Angular Velocity in Cartesian co-ordinates [AVx,AVy,AVz] (units radians/s).</u> <u>(This is calculated with the SPICE ckgpav command where ref=J2000. SPICE defines it as 'This is the axis about which the reference frame tied to the instrument is rotating in the right-handed sense.')</u>
<u>173</u>	<u>4</u>	<u>SC_SPIN_PERIOD</u>	<u>f</u>	<u>Seconds</u>	<u>Juno spin period (seconds).</u> <u>This is not useful during spacecraft maneuvers.</u>
<u>177</u>	<u>4</u>	<u>SC_SPIN_PHASE</u>	<u>f</u>	<u>Seconds</u>	<u>Juno's spin phase at time DIM0 UTC, in units of degrees.</u>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<a href="#">181</a>	<a href="#">4</a>	<a href="#">SC_SPIN_PHASE_UPPER</a>	<a href="#">f</a>	<a href="#">Seconds</a>	<a href="#">Juno's spin phase at time DIM0 UTC UPPER, in units of degrees.</a>
<a href="#">185</a>	<a href="#">4</a>	<a href="#">SC_SPIN_PHASE_LOWER</a>	<a href="#">f</a>	<a href="#">Seconds</a>	<a href="#">Juno's spin phase at time DIM0 UTC LOWER, in units of degrees.</a>
<a href="#">189</a>	<a href="#">36</a>	<a href="#">DESPUN_SC_TO_J2000</a>	<a href="#">f</a>	<a href="#">None</a>	<a href="#">Rotation matrix from despun spacecraft coordinates to J2000. This is a 3x3 matrix, but if read in as a 1x9 stream then the 1D stream is [a,b,c, d,e,f, g,h,i] and the 2D matrix would be [a,b,c d,e,f g,h,i]</a>
<a href="#">225</a>	<a href="#">36</a>	<a href="#">J2000_TO_JSS_XYZ</a>	<a href="#">f</a>	<a href="#">None</a>	<a href="#">Rotation matrix from J2000 co-ordinates to JSS xyz (JSS = Jupiter-De-Spun-Sun, see SIS for details). This is a 3x3 matrix, but if read in as a 1x9 stream then the 1D stream is [a,b,c, d,e,f, g,h,i] and the 2D matrix would be [a,b,c d,e,f g,h,i]</a>
<a href="#">261</a>	<a href="#">36</a>	<a href="#">J2000_TO_JSS_RTP</a>	<a href="#">f</a>	<a href="#">None</a>	<a href="#">Rotation matrix from J2000 co-ordinates to JSS RTP, where RTP is Jupiter centered right handed R-Theta-Phi. (JSS = Jupiter-De-Spun-Sun, see SIS for details.) This is a 3x3 matrix, but if read in as a 1x9 stream then the 1D stream is [a,b,c, d,e,f, g,h,i] and the 2D matrix would be [a,b,c d,e,f g,h,i]</a>
<a href="#">297</a>		<a href="#">MCP_VOLTAGE</a>			<a href="#">The last 4 objects of this header all start at byte 297 and have the same names, but three different sizes depending on the JADE product. For the ion products go to Table 69. For the HRS electrons (all) go to Table 70, or Table 71 for HRS electrons (two). For the LRS electrons go to Table 72.</a>
		<a href="#">ISSUES</a>			
		<a href="#">TIMESTAMP_WHOLE</a>			
		<a href="#">TIMESTAMP_SUB</a>			

Fmt\* is shortened for the table and is decoded in PDS format as: f = PC\_REAL (float), uint8/uint16/uint32 are = one/two/four-byte LSB\_UNSIGNED\_INTEGER and int8/int16/int32 = one/two/four byte LSB\_INTEGER.



Table 69: Format of Level 3 data record subheader for Level 3 ion products for V04+

Byte	Length (bytes)	Name	Fmt*	Units	Description
297	4	MCP_VOLTAGE	f	Volts	MCP Voltage on sensor.
301	8	ISSUES	uint32	None	Issues or potential issues in this data record. [Two values for ions as this is the ISSUES object from both the ping and pong level 2 packets used to create this record.]... The rest is a direct copy of the Level 2 ISSUES object, see Table 38 for description.
309	8	TIMESTAMP_WHOLE	uint32	Ticks	Timestamps (Whole Second) of JADE Level 2 packets used to make this Level 3 record. (Both the ping and pong level 2 packets.)
317	4	TIMESTAMP_SUB	uint16	Subticks	Timestamps (Subsecond) of JADE Level 2 packets used to make this Level 3 record. (Both the ping and pong level 2 packets.)

Table 70: Format of Level 3 data record subheader for JAD L30 HRS ELC ALL \*for V04+

Byte	Length (bytes)	Name	Fmt*	Units	Description
297	12	MCP_VOLTAGE	f	Volts	MCP Voltages on the three electron sensors, E060, E180 and E300 respectively.
309	4	ISSUES	uint32	None	Issues or potential issues in this data record. ... The rest is a direct copy of the Level 2 ISSUES object, see Table 38 for description.
313	4	TIMESTAMP_WHOLE	uint32	Ticks	Timestamp (Whole Second) of JADE Level 2 packet used to make this Level 3 record.
317	2	TIMESTAMP_SUB	uint16	Subticks	Timestamp (Subsecond) of JADE Level 2 packet used to make this Level 3 record.

Table 71: Format of Level 3 data record subheader for JAD L30 HRS ELC TWO \*for V04+

Byte	Length (bytes)	Name	Fmt*	Units	Description
297	8	MCP_VOLTAGE	f	Volts	MCP Voltages on the two electron sensors in this product, E060 and E180 respectively.
305	4	ISSUES	uint32	None	Issues or potential issues in this data record. ... The rest is a direct copy of the Level 2 ISSUES object, see Table 38 for description.
309	4	TIMESTAMP_WHOLE	uint32	Ticks	Timestamp (Whole Second) of JADE Level 2 packet used to make this Level 3 record.
313	2	TIMESTAMP_SUB	uint16	Subticks	Timestamp (Subsecond) of JADE Level 2 packet used to make this Level 3 record.

Table 72: Format of Level 3 data record subheader for JAD L30 LRS ELC ANY \*for V04+

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>297</u>	<u>4</u>	<u>MCP_VOLTAGE</u>	<u>f</u>	<u>Volts</u>	<u>MCP Voltage on sensor.</u>
<u>301</u>	<u>4</u>	<u>ISSUES</u>	<u>uint32</u>	<u>None</u>	<u>Issues or potential issues in this data record. ... The rest is a direct copy of the Level 2 ISSUES object, see Table 38 for description.</u>
<u>305</u>	<u>4</u>	<u>TIMESTAMP WHOLE</u>	<u>uint32</u>	<u>Ticks</u>	<u>Timestamp (Whole Second) of JADE Level 2 packet used to make this Level 3 record.</u>
<u>309</u>	<u>2</u>	<u>TIMESTAMP SUB</u>	<u>uint16</u>	<u>Subticks</u>	<u>Timestamp (Subsecond) of JADE Level 2 packet used to make this Level 3 record.</u>

In general, the rest of the format for the different products have the same object names (see Figure 11), however their size (byte length) and start bytes will differ. The descriptions are also much the same when they have the same object name, with only DATA really changing (text that may alter between products is shown in **blue boldface**).

## 6.2.10.1 Electron Data for V04+

### 6.2.10.1.1 JAD\_L30\_HRS\_ELC\_ALL\_CNT\_\* for V04+

The electron product for high rate science is PACKETID 0x8E and includes data from all three electron sensors.

The DATA object is 2-D, 64 energies x 48 look directions, and is described in Table 73, and continues over the next 3 pages.

This product is a combination of look directions from all 3 JADE-E sensors, but E300 was turned off in 2016, hence those anodes that would have been from E300 are populated with the MISSING\_CONSTANT (-1) value.

If E300 was off on a given day, from Level 3 Version 04 we no longer generate the daily file, since JAD\_L30\_HRS\_ELC\_TWO\_CNT files (still generated, see Table 74) have the exact same information. Thus if there is a JAD\_L30\_HRS\_ELC\_ALL\_CNT\_\*V04 file, all 3 JADE-E sensors were on.

Table 73: Format of Level 3 data records for JAD\_L30\_HRS\_ELC\_ALL\_CNT for V04+

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 68 and Table 70 for bytes 1 to 318.</i>					
<u>319</u>	<u>12288</u>	<u>DATA</u>	f	Counts/s	<u>DATA: Counts/Second</u> <u>64 Energy x 48 Look Directions.</u> <u>[Note: E300 was turned off in 2016, so the last 16 look directions (32-47) are usually populated with the MISSING_CONSTANT value of -999999.]</u>
<u>12607</u>	<u>12288</u>	<u>DATA_SIGM</u> <u>A</u>	f	Counts/s	<u>DATA_SIGMA</u> <u>1-sigma uncertainties on values in object DATA, such that</u> <u>true value = DATA +/- DATA_SIGMA.</u> <u>See DATA entry above for size information.</u>
<u>24895</u>	<u>12288</u>	<u>BACKGROUN</u> <u>D</u>	f	Counts/s	<u>Background value removed from DATA.</u> <u>If you wish to do your own background removal, add this object to DATA then you can remove a background via your own method.</u> <u>See the SOURCE_BACKGROUND object for the background method used per record.</u> <u>The background values here were generated from a background anode or JADE's own ground method, or are all zeros if no background was removed.</u>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>37183</u>	<u>12288</u>	<u>BACKGROUND_SIGMA</u>	<u>f</u>	<u>Counts/s</u>	<u>BACKGROUND_SIGMA</u> <u>1-sigma uncertainties on values in object BACKGROUND, such that true value = BACKGROUND +/- BACKGROUND_SIGMA. See BACKGROUND entry above for size information.</u>
<u>49471</u>	<u>12288</u>	<u>DIM1_E</u>	<u>f</u>	<u>eV/q</u>	<u>1st Dimension of DATA: Energy (center) in eV/q.</u>
<u>61759</u>	<u>12288</u>	<u>DIM2_ELEVATION</u>	<u>f</u>	<u>Degrees</u>	<u>2nd Dimension of DATA: Spacecraft elevation - center value. Spacecraft elevation (degs) is analogous to latitude on a sphere. In spacecraft xyz co-ords: +z is equivalent to elevation = +90 degs -z is equivalent to elevation = -90 degs (The communication dish is directed along +z) xy-plane at z = 0 is equivalent to elevation = 0.  Note, 2nd dimension is really look direction which has an elevation and azimuth; hence two objects describe this: <u>DIM2_ELEVATION</u> and <u>DIM2_AZIMUTH_DESPUN</u>.</u>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>74047</u>	<u>12288</u>	<u>DIM2_AZIMUTH_DESPUN</u>	<u>f</u>	<u>Degrees</u>	<p><u>2nd Dimension of DATA: Despun S/C azimuth - center value. Spacecraft azimuth (degs) is analogous to longitude on a sphere.</u></p> <p><u>In spacecraft xyz co-ords:</u></p> <p><u>+x is equivalent to azimuth = 0 degs</u></p> <p><u>+y is equivalent to azimuth = 90 degs</u></p> <p><u>-x is equivalent to azimuth = 180 degs</u></p> <p><u>-y is equivalent to azimuth = 270 degs</u></p> <p><u>+x is equivalent to azimuth = 360 degs</u></p> <p><u>+y is equivalent to azimuth = 450 degs</u></p> <p><u>The 'Despun' azimuth angle varies because Juno spins, where azimuth = 0 is defined as +x when spin phase equals zero (e.g. despun x-z plane contains the ECLIPJ2000 north).</u></p> <p><u>The relationship between despun azimuth and spin phase (which decreases during a spin) is simply:</u></p> <p><u>Despun Azimuth = 360 degrees - Spin Phase</u></p> <p><u>Note, 2nd dimension is really look direction which has an elevation and azimuth; hence two objects describe this:</u></p> <p><u>DIM2_ELEVATION and</u></p> <p><u>DIM2_AZIMUTH_DESPUN.</u></p>
<u>86335</u>	<u>12</u>	<u>MAG_VECTOR</u>	<u>f</u>	<u>nT</u>	<p><u>MAG vector in nT, 3 components [X, Y, Z]</u></p> <p><u>MAG range is +/- 16 G, hence limits.</u></p> <p><u>This xyz coordinate system is despun spacecraft; see the definitions of</u></p> <p><u>DIM2_ELEVATION and</u></p> <p><u>DIM2_AZIMUTH:</u></p> <p><u>+X is when [azimuth, elevation] = [ 0, 0] degrees,</u></p> <p><u>+Y is when [azimuth, elevation] = [ 90, 0] degrees,</u></p> <p><u>+Z is when elevation = 90 degrees.</u></p>

#### 6.2.10.1.2 JAD\_L30\_HRS\_ELC\_TWO\_CNT \* for V04+

This is a repeat of the JAD\_L30\_HRS\_ELC\_ALL\_CNT \* file, but with E300 data removed to provide a smaller (but still large) file, thus only contains E060 and E180 data. This product was introduced when it was decided not to use sensor E300 in flight operations, however the HRS electron data packet would still return zeros for E300.

The DATA object is 2-D, 64 energies x 32 look directions (rather than 48 look directions), and is described in Table 74.

Table 74: Format of Level 3 data records for JAD L30 HRS ELC TWO CNT for V04+

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<i>See Level 2 binary header from Table 68 and Table 71 for bytes 1 to 314.</i>					
<a href="#">315</a>	<a href="#">8192</a>	<a href="#">DATA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">DATA: Counts/Second 64 Energy x 32 Look Directions.</a>
<a href="#">8507</a>	<a href="#">8192</a>	<a href="#">DATA_SIGMA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">16699</a>	<a href="#">8192</a>	<a href="#">BACKGROUND</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">24891</a>	<a href="#">8192</a>	<a href="#">BACKGROUND_SIGMA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">33083</a>	<a href="#">8192</a>	<a href="#">DIM1_E</a>	<a href="#">f</a>	<a href="#">eV/q</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">41275</a>	<a href="#">8192</a>	<a href="#">DIM2_ELEVATION</a>	<a href="#">f</a>	<a href="#">Degrees</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">49467</a>	<a href="#">8192</a>	<a href="#">DIM2_AZIMUTH_DESPUN</a>	<a href="#">f</a>	<a href="#">Degrees</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">57659</a>	<a href="#">12</a>	<a href="#">MAG_VECTOR</a>	<a href="#">f</a>	<a href="#">nT</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>

6.2.10.1.3 JAD\_L30\_LRS\_ELC\_ANY\_CNT\_\* for V04+

The electron products for low rate science are PACKETIDs 0x68, 0x6A and 0x6B, and includes data from one electron sensor per record (only one sensor is on at any given time).

The DATA object is 2-D, 64 energies x 48 look directions, and is described in Table 75.

Practically there are only two differences between this and the

JAD\_L30\_HRS\_ELC\_ALL\_CNT\_\* file:

- 3) The MCP\_VOLTAGE object is a singular value here (for the one sensor) as opposed to 3 values for the HRS case (one for each of the sensors). This in turn makes the start byte of all following objects 8 bytes earlier in the LRS product compared to the HRS product. The description of MCP\_VOLTAGE in the FMT file is slightly different to reflect this.
- 4) This product has an extra object at the end; called ESENSOR that states which of the three sensors is in use (60, 180 or 300). This does not exist in the HRS product as the data array always includes all three sensors.

So the only difference between tables Table 61 and Table 63 are the first column byte values are offset by 8 (as indicated in the first red row), and Table 63 has the ESENSOR product at the end.

If using FSW4.00 (April 2015 only) data for this product (cruise solar wind only, no Jupiter science use) all DIM2\_AZIMUTH\_DESPUN values are replaced with the fill value 65535 due to the reverse anode mapping bug (see section 6.2.8.1.4).

Table 75: *Format of Level 3 data records for JAD\_L30\_LRS\_ELC\_ANY\_CNT for V04+*

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 68 and Table 72 for bytes 1 to 310.</i>					
<a href="#">311</a>	<a href="#">12288</a>	<a href="#">DATA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">DATA: Counts/Second</a> <a href="#">64 Energy x 48 Look Directions.</a>
<a href="#">12599</a>	<a href="#">12288</a>	<a href="#">DATA_SIGM</a> <a href="#">A</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for</a> <a href="#">JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">24887</a>	<a href="#">12288</a>	<a href="#">BACKGROUN</a> <a href="#">D</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for</a> <a href="#">JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">37175</a>	<a href="#">12288</a>	<a href="#">BACKGROUN</a> <a href="#">D_SIGMA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for</a> <a href="#">JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">49463</a>	<a href="#">12288</a>	<a href="#">DIM1_E</a>	<a href="#">f</a>	<a href="#">eV/q</a>	<a href="#">Same description as from Table 73 for</a> <a href="#">JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">61751</a>	<a href="#">12288</a>	<a href="#">DIM2_ELEVA</a> <a href="#">TION</a>	<a href="#">f</a>	<a href="#">Degrees</a>	<a href="#">Same description as from Table 73 for</a> <a href="#">JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">74039</a>	<a href="#">12288</a>	<a href="#">DIM2_AZIMU</a> <a href="#">TH_DESPUN</a>	<a href="#">f</a>	<a href="#">Degrees</a>	<a href="#">Same description as from Table 73 for</a> <a href="#">JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">86327</a>	<a href="#">12</a>	<a href="#">MAG_VECTO</a> <a href="#">R</a>	<a href="#">f</a>	<a href="#">nT</a>	<a href="#">Same description as from Table 73 for</a> <a href="#">JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">86339</a>	<a href="#">2</a>	<a href="#">ESENSOR</a>	<a href="#">uint16</a>	<a href="#">None</a>	<a href="#">ESENSOR - which one of the three electron</a> <a href="#">sensors is this record for. Values can only be</a> <a href="#">60, 180 or 300 for electron sensor E060,</a> <a href="#">E180 or E300 respectively. Note: each sensor</a> <a href="#">also has a different PACKETID.</a>

## 6.2.10.2 Ion Species Data for V04+

### 6.2.10.2.1 JAD\_L30\_HRS\_ION\_ANY\_CNT \* for V04+

The ion species products for high rate science cover PACKETIDs 0x80-0x87. Each ion species has its own packet; therefore several packets of different species may have the same time stamp. The DATA object is 2-D, 64 energies x 12 look directions, and is described in Table 76.

Table 76: Format of Level 3 data records for JAD\_L30\_HRS\_ION\_ANY\_CNT for V04+

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<i>See Level 2 binary header from Table 68 and Table 69 for bytes 1 to 320.</i>					
<a href="#">321</a>	<a href="#">3072</a>	<a href="#">DATA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">DATA: Counts/Second 64 Energy x 12 Look Directions.</a>
<a href="#">3393</a>	<a href="#">3072</a>	<a href="#">DATA_SIGMA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">6465</a>	<a href="#">3072</a>	<a href="#">BACKGROUND</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">9537</a>	<a href="#">3072</a>	<a href="#">BACKGROUND_SIGMA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">12609</a>	<a href="#">3072</a>	<a href="#">DIM1_E</a>	<a href="#">f</a>	<a href="#">eV/q</a>	<a href="#">Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">15681</a>	<a href="#">3072</a>	<a href="#">DIM2_ELEVATION</a>	<a href="#">f</a>	<a href="#">Degrees</a>	<a href="#">Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</a>
<a href="#">18753</a>	<a href="#">3072</a>	<a href="#">DIM2_AZIMUTH_DESPUN</a>	<a href="#">f</a>	<a href="#">Degrees</a>	<a href="#">Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</a>



6.2.10.2.2 JAD\_L30\_LRS\_ION\_ANY\_CNT\_\* for V04+

The ion species products for low rate science (PACKETID 0x60-0x67). Each ion species has its own packet; therefore several packets of different species may have the same time stamp.

The DATA object is 2-D, 64 energies x 78 look directions, and is described in Table 77.

The basic format of this file is identical to the HRS counterpart, except there are 78 look directions here instead of 12. As such the start byte and lengths change, but the object names and descriptions are the same (except for the description of the DATA object).

Table 77: Format of Level 3 data records for JAD\_L30\_LRS\_ION\_ANY\_CNT for V04+

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<i>See Level 2 binary header from Table 68 and Table 69 for bytes 1 to 320.</i>					
<u>321</u>	<u>19968</u>	<u>DATA</u>	<u>f</u>	<u>Counts/s</u>	<u>DATA: Counts/Second 64 Energy x 78 Look Directions.</u>
<u>20289</u>	<u>19968</u>	<u>DATA_SIGM A</u>	<u>f</u>	<u>Counts/s</u>	<u>Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</u>
<u>40257</u>	<u>19968</u>	<u>BACKGROUN D</u>	<u>f</u>	<u>Counts/s</u>	<u>Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</u>
<u>60225</u>	<u>19968</u>	<u>BACKGROUN D_SIGMA</u>	<u>f</u>	<u>Counts/s</u>	<u>Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</u>
<u>80193</u>	<u>19968</u>	<u>DIM1_E</u>	<u>f</u>	<u>eV/q</u>	<u>Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</u>
<u>100161</u>	<u>19968</u>	<u>DIM2_ELEVA TION</u>	<u>f</u>	<u>Degrees</u>	<u>Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</u>
<u>120129</u>	<u>19968</u>	<u>DIM2_AZIMU TH_DESPUN</u>	<u>f</u>	<u>Degrees</u>	<u>Same description as from Table 73 for JAD_L30_HRS_ELC_ALL_CNT.</u>

### 6.2.10.3 Ion Time of Flight Data for V04+

#### 6.2.10.3.1 JAD\_L30\_HLS\_ION\_TOF\_CNT \* for V04+

The ion time of flight products for high and low rate science, covering PACKETIDs 0x69 and 0x89.

The DATA object is 3-D, 64 energies x 1 look direction x 93 TOF channels, and is described in Table 78 (over 2 pages). This product usually has 96 TOF channels with the last 3 having special meanings, but for level 3 data the last 3 channels have been removed and given their own objects within this file.

This product is usually considered to be a 2 dimensional array of energy by TOF channel. However all other JADE data is Energy by look direction, so to keep things similar, this product is a 3 dimensional array of 64 energies by 1 look direction by 93 TOF channels. There is only 1 look direction, but given the ion instrument covers 270 degrees field of view in elevation over the 12 anodes, and this product sums all 12 anodes, this leads to some interesting azimuth and elevation numbers. The DIM2\_AZIMUTH objects will use the respective azimuth of anodes 4-11 (anodes 0-3 azimuths would normally be 180 degrees from those). However DIM2\_ELEVATION will range from -90 to +180 degrees (spanning 270 degrees) with a center value of +45 degrees. As such, elevation of +90 to +180 is being used to describe the contribution of anodes 3, 2, 1 and 0 that are technically covering elevations of +90 down to 0 degrees but with an azimuth 180 degrees different.

The object names (and descriptions, DATA description excepted) are identical to the other level 3 ion products, but with 6 TOF only objects on the end. (Text that may alter between products is shown in **blue boldface**, e.g. version number of files should match the version number of the DAT files.)

Table 78: Format of Level 3 data records for JAD L30 HLS ION TOF CNT for V04+

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 68 and Table 69 for bytes 1 to 320.</i>					
<a href="#">321</a>	<a href="#">23808</a>	<a href="#">DATA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">DATA: Counts/Second</a> 64 Energy x 1 Look Direction x 93 bins. These bins are expressed as a duration in seconds in object DIM3_TOF, and for more details see the <a href="#">TOF_CHANNEL_TO_SECONDS_HLC_V04.CSV</a> file in the CALIB directory of this PDS archive. The Level 2 data had 96 bins, those last 3 are now objects <a href="#">TOF_WITH_START_OVERLOAD</a> , <a href="#">TOF_TOO_SHORT</a> and <a href="#">TOF_TOO_LONG</a> respectively.
<a href="#">24129</a>	<a href="#">23808</a>	<a href="#">DATA_SIGMA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">47937</a>	<a href="#">23808</a>	<a href="#">BACKGROUND</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">71745</a>	<a href="#">23808</a>	<a href="#">BACKGROUND_SIGMA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">95553</a>	<a href="#">256</a>	<a href="#">DIM1_E</a>	<a href="#">f</a>	<a href="#">eV/q</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">95809</a>	<a href="#">256</a>	<a href="#">DIM2_ELEVATION</a>	<a href="#">f</a>	<a href="#">Degrees</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">96065</a>	<a href="#">256</a>	<a href="#">DIM2_AZIMUTH_DESPUN</a>	<a href="#">f</a>	<a href="#">Degrees</a>	<a href="#">Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</a>
<a href="#">96321</a>	<a href="#">372</a>	<a href="#">DIM3_TOF</a>	<a href="#">f</a>	<a href="#">Seconds</a>	<a href="#">3rd Dimension of DATA: Time Of Flight - center value. (Seconds)</a>
<a href="#">96693</a>	<a href="#">256</a>	<a href="#">TOF_WITH_START_OVERLOAD</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">TOF with start overload: Counts/Second</a> A signal pulse that is too strong (above a threshold) in the electronics. Multiple start-overloads that occur within a 330ns event window are counted each time in the <a href="#">Logicals Start Overload</a> , but only once here.
<a href="#">96949</a>	<a href="#">256</a>	<a href="#">TOF_WITH_START_OVERLOAD_SIGMA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">TOF with start overload uncertainty: Counts/Second</a> 1-sigma uncertainties on values in object <a href="#">TOF_WITH_START_OVERLOAD</a> such that true value = <a href="#">TOF_WITH_START_OVERLOAD +/- TOF_WITH_START_OVERLOAD_SIGMA</a> . See <a href="#">TOF_WITH_START_OVERLOAD</a> entry above for size information.

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<a href="#">97205</a>	<a href="#">256</a>	<a href="#">TOF_TOO_SHORT</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">TOF too short: Counts/Second</a> <a href="#">TOF underflow: Count of TOF</a> <a href="#">measurements that did not timeout, but</a> <a href="#">resulted in a measurement smaller than the</a> <a href="#">sensor could measure.</a>
<a href="#">97461</a>	<a href="#">256</a>	<a href="#">TOF_TOO_SHORT_SIGMA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">TOF too short uncertainty: Counts/Second</a> <a href="#">1-sigma uncertainties on values in object</a> <a href="#">TOF_TOO_SHORT such that true value =</a> <a href="#">TOF_TOO_SHORT +/-</a> <a href="#">TOF_TOO_SHORT_SIGMA.</a> <a href="#">See TOF_TOO_SHORT entry above for size</a> <a href="#">information.</a>
<a href="#">97717</a>	<a href="#">256</a>	<a href="#">TOF_TOO_LONG</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">TOF too long: Counts/Second</a> <a href="#">TOF overflow: Count of TOF measurements</a> <a href="#">that resulted in no stop signal arriving within</a> <a href="#">330ns of the start signal.</a>
<a href="#">97973</a>	<a href="#">256</a>	<a href="#">TOF_TOO_LONG_SIGMA</a>	<a href="#">f</a>	<a href="#">Counts/s</a>	<a href="#">TOF too long uncertainty: Counts/Second</a> <a href="#">1-sigma uncertainties on values in object</a> <a href="#">TOF_TOO_LONG such that true value =</a> <a href="#">TOF_TOO_LONG +/-</a> <a href="#">TOF_TOO_LONG_SIGMA.</a> <a href="#">See TOF_TOO_LONG entry above for size</a> <a href="#">information.</a>

## 6.2.10.4 Ion Logicals Data for V04+

### 6.2.10.4.1 JAD\_L30\_HLS\_ION\_LOG\_CNT\_\* for V04+

The ion logicals products for high and low rate science, covering PACKETID 0x6C and 0x8C. The DATA object is 2-D, 64 energies x 25 logicals (each with variable look directions), and is described in Table 79 (over 3 pages).

Given the ion instrument covers 270 degrees field of view in elevation, this leads to some interesting azimuth and elevation numbers, as elevation can range from -90 to +180 degrees; see the descriptions below. e.g. if Azimuth is 200 degrees and elevation is 100 degrees, that's equivalent to an azimuth of 20 (200-180) degrees and an elevation of 80 (180-100) degrees. That is anode 0 will have an azimuth 180 degrees from anode's 7, which is described in the DIM2 objects, however the logicals that combine all individual anodes the DIM2 values will use the azimuth from anodes 4-11 for all, but the elevations range will be -90 to +180 degrees.

The 25 logical counters here are the same as for level 2 data.

The PDS ion logicals datasets do not have a background removed from DATA, hence SOURCE\_BACKGROUND should always be 0, and BACKGROUND and BACKGROUND\_SIGMA should always be zero too.

Table 79: Format of Level 3 data records for JAD L30 HLS ION LOG CNT for V04+

Byte	Length (bytes)	Name	Fmt*	Units	Description
<i>See Level 2 binary header from Table 68 and Table 69 for bytes 1 to 320.</i>					
321	6400	DATA	f	Counts/s	<p>DATA: Counts/Second 64 Energy x 25 Logicals. The 25 Logical counters are:</p> <p>[ 0]: Anode 0 Events [ 1]: Anode 1 Events [ 2]: Anode 2 Events ... [10]: Anode 10 Events [11]: Anode 11 Events [12]: Background Events</p> <p>The above 13 logicals are raw count hits, independent of whether a TOF Event has begun. Adjacent and Non-Adjacent hits will be counted in both anodes. As such, anode counts can exceed All Stops [15] counts. The Background anode [12] is not included in Adjacent and Non-Adjacent calculations.</p> <p>[13]: Start Overload Start signal exceeds threshold level.</p> <p>[14]: All Starts Independent of whether a TOF Event has begun, usually starts a TOF Event.</p> <p>[15]: All Stops Independent of whether a TOF Event has begun, usually ends a TOF Event.</p> <p>If an event is seen on multiple anodes this counter is still only incremented once, therefore this is usually less than the sum of anodes 0 to 11.</p> <p>The Background anode is not included in All Stops, just anodes 0 to 11.</p> <p>[16]: Non-Adjacent Anodes This is either two non-neighbor anodes (anodes 0-11 only), or more than 2 anodes.</p> <p>[17]: Adjacent Anodes A count hit was measured in neighboring anodes; other products (e.g. Ion Species) will assign this to just the lower anode.</p> <p>[18]: Stop without Start A stop signal was received before a TOF Event was initiated by a start.</p> <p><i>Continues on next page.</i></p>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
					<p><u>Continues from previous page.</u></p> <p><u>[19]: Dual Start</u>  A TOF Event had started but one or more other start signals were received before a stop signal or the TOF Event overflowed.</p> <p><u>[20]: Start in Process Time</u>  The number of TOF Events started, can be less than All Starts [14].</p> <p><u>[21]: TOF Underflow</u>  Received a stop event before 1 tap, that is 1.45ns, the base unit of TOF times.</p> <p><u>[22]: TOF Overflow</u>  No stop signal arrived within timeout of 330ns.</p> <p><u>[23]: Invalid TOF Event</u>  If the TOF Event is measured in 1 anode (anodes 0-11 only) or two neighboring anodes (anodes 0-11 only) it is valid. Otherwise it is invalid, unless it was an underflow in which case the Underflow [21] counter is increased instead of this counter (i.e. an Underflow event is considered valid). Therefore, if the event is not an Underflow event, it will be invalid if one of these three situations is met:</p> <ul style="list-style-type: none"> <li>- hit in more than two anodes, or</li> <li>- hit in two non-neighbor anodes, or</li> <li>- no anodes hit at all.</li> </ul> <p>The latter is different to overflow events [22] which are considered valid.</p> <p>The Background anode is not considered in any of these calculations.</p> <p><u>[24]: Event Strobe</u>  The number of TOF Events completed, by a stop signal or over/underflow, usually the same as Start in Process Time [20].</p> <p><u>For the above, a TOF Event is a start signal followed by either a stop signal or timeout.</u></p> <p><u>Note that the look directions of logicals 12-24 cover the combined look directions of logicals 0-11.</u>  Anodes 0-3 will have an azimuth 180 degrees greater than anodes 4-11. For logicals 12-24 that cover all 12 anodes, the azimuth of anodes 4-11 will be used, but elevation will be -90 to +180 degrees, centered at +45 degrees (between anodes 5 and 6).</p>

<u>Byte</u>	<u>Length (bytes)</u>	<u>Name</u>	<u>Fmt*</u>	<u>Units</u>	<u>Description</u>
<u>6721</u>	<u>6400</u>	<u>DATA_SIGM A</u>	<u>f</u>	<u>Counts/s</u>	<u>Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</u>
<u>13121</u>	<u>6400</u>	<u>BACKGROUN D</u>	<u>f</u>	<u>Counts/s</u>	<u>Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</u>
<u>19521</u>	<u>6400</u>	<u>BACKGROUN D_SIGMA</u>	<u>f</u>	<u>Counts/s</u>	<u>Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</u>
<u>25921</u>	<u>6400</u>	<u>DIM1_E</u>	<u>f</u>	<u>eV/q</u>	<u>Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</u>
<u>32321</u>	<u>6400</u>	<u>DIM2_ELEVA TION</u>	<u>f</u>	<u>Degrees</u>	<u>Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</u>
<u>38721</u>	<u>6400</u>	<u>DIM2_AZIMU TH_DESPUN</u>	<u>f</u>	<u>Degrees</u>	<u>Same description as from Table 73 for JAD L30 HRS ELC ALL CNT.</u>

### 6.2.10.5 Level 3 conversion of data for V04+

Moved to section 6.2.11 (as it's independent of version number).



### **6.2.106.2.11 Level 3 conversion of data**

This section summarizes the equations used to convert from level 2 to level 3 data, in the order each is encountered in the production code used by the JADE team for level 3 ~~version 01~~ files. Specific calibration values are listed in the CALIB directory of the Level 3 PDS volume in the JAD\_L30\_CALIB\_LIST\_#####.TXT file, where the value for ##### is given in level 3 SOURCE\_JADE\_CALIB object for each record. This text file may point to other files in the CALIB directory.

Note that MISSING\_CONSTANT (also known as fill) values may be present in the DATA object or any other level 2 or level 3 object, and all the codes have to check for these and react accordingly. For instance, if a DATA element is a MISSING\_CONSTANT value, then the level 3 DATA element in counts per second (and DATA\_SIGMA too) will also be set to the appropriate MISSING\_CONSTANT value. This greatly complicates the coding, but is safer to propagate MISSING\_CONSTANT values in DATA, energy or look directions when necessary.

### **6.2.10.16.2.11.1 Remove any records where the level 2 MCP\_COMMANDERED\_VALUE object is zero**

This may be just a few records as JADE is turning on, or during cruise it may be all values that day for some electron files (where essentially the electron sensor was ‘off’). If no records are left, then do not make a level 3 file at all.

### **6.2.10.26.2.11.2 Correct timestamps affected by the Juno time stutter**

Check the ISSUES object (bit 10) of each record to see if it was affected by the Juno time stutter. If so, remove 1 tick from the TIMESTAMP\_WHOLE value (leave TIMESTAMP\_SUB as is) and calculate the new UTC time. Set bit 10 of the ISSUES object to 0 (False) for that record, and set bit 5 to 1 (True) (to note that the time has been corrected).

### **6.2.10.36.2.11.3 Check for FSW 4.00 LRS/CAL ion species bug (early 2015 data only)**

If the LRS/CAL ion species bug is present then all accumulation times are fill values, and the reported start time is actually the end time of the record (see ISSUES description). The level 3 data has been corrected for this; now reporting the correct start time (at least to within 1 ms) and accumulation time.

### **6.2.10.46.2.11.4 If ion data, merge ping and pong records to put all 64 energies in one record**

In level 2 data a full sweep of energies for ion data must be split over two telemetry packets (and therefore two level 2 records) for transmission. Here we recombine them and re-order in increasing energy. There are four possible sweep tables for ion data, 0 to 3, with either 0 & 1 or 2 & 3 used, e.g. sweep tables will flip 0,1,0,1,0,1,0,1,... When JADE turns to a new telemetry mode (e.g. HRS to LRS) it may do so on any second even if a pair of sweep tables is not

complete. Generally the first one it hits is called the ping, the second the pong, however that first one may be either an odd or even sweep table number. HRS data is the exception, where the ping is always a 0 or 2, and a pong always a 1 or 3 (this is so that HRS products can be compared on the same time boundaries). Not all pings may have a corresponding pong, nor all pongs a corresponding ping, either due to a data gap or a pair not being complete due to a mode change.

For HRS data, each ping or pong takes 1 spacecraft tick (`ACCUMULATION_TIME = 1`), so when merged `ACCUMULATION_TIME` of those records is set to 2. For LRS or CAL data `ACCUMULATION_TIME` is unchanged as those already assume you're using both ping and pong. This is important for the conversion to counts/second later.

#### **6.2.10-56.2.11.5** Remap energy steps in to ascending eV/q order

The Level 2 data records list energy steps in the order they were taken (e.g. every 2<sup>nd</sup> step up, then back down with every 2<sup>nd</sup> step of the ones that were missed going up, such that they interleave over a whole record). This step order is re-ordered in to one of increased eV/q. (See the `LUT_m_nn_ENERGY_Vvv.CSV` files for the eV/q values of the Level 2 files, which allows one to work out how to remap them to be increasing in eV/q.)

#### **6.2.10-66.2.11.6** Convert MCP\_CMDANDED\_VALUE to units of volts

The Level 2 data has object `MCP_CMDANDED_VALUE` which is a digital value that needs to be converted to a Level 3 object `MCP_VOLTAGE` (in volts).

The equations to use are listed in the `JAD_L30_CALIB_LIST_nnnnn.TXT` file.

Note that if `MCP_CMDANDED_VALUE = 0` then `MCP_VOLTAGE = 0V`, but for non-zero values use the equations in the above file.

#### **6.2.10-76.2.11.7** Use SPICE to calculate auxiliary information

Use the latest (at time of processing) version metakernel file from the CALIB directory to find position, orientation, velocities, spin period and co-ordinate transformation matrices, as well as the start/center/stop spin-phase values for each record. (Metakernel files are named `JAD_L30_SPICE_METAKERNEL_nnnnn.TXT` where each level 3 files has an object named `SOURCE_JADE_METAKERNEL` that contains the `nnnnn` value of the metakernel used to create that particular record.)

#### **6.2.10-86.2.11.8** Apply any dead time ~~correction or cross-talk~~ corrections.

~~If applicable, correct for dead time and/or cross-talk.~~—Currently there is no known reason to correct for either. ~~[Not yet implemented—as so far nothing to do.]~~dead time.

Since no dead time correction is applied (record object `SOURCE_DEAD_TIME = 0` in all Level 3 version 01, 02 or 03 files), the object `SOURCE_DEAD_TIME` was removed from Level 3 version 04(+) files.

### **6.2.10.96.2.11.9 Convert level 2 counts to a more representative value and work out uncertainties**

Level 2 DATA are all integers, which required some rounding, whereas Level 3 DATA are floats, so here we swap out the integers for the floats they would have been (using the lossy LUT compression tables) and calculate an uncertainty for each value to populate DATA\_SIGMA. This is a much more complex procedure than you would like; hence we do it for you. It is explained in great detail in the CALIB directory file DATA\_UNCERTAINTY\_EQNS\_Vnn.PDF (See JAD\_L30\_CALIB\_LIST\_nnnnn.TXT file for which Vnn you should use for each record.)

### **6.2.10.106.2.11.10 Convert Data and uncertainties to counts per second.**

At this point the DATA (and DATA\_SIGMA) objects are in units of counts per accumulation or counts per view, both need converting to counts per second.

It should be noted that during each spacecraft clock tick (assumed to be 1 S.I. second, although technically not true, but extremely close) the electron sensors sweep 64 energy steps per tick, while the ion sensor sweeps 32 energy steps (such that the ion sensor requires 2 seconds to measure all 64 energy steps). For both electron and ion sensors, the first 2 ms at each step is a settling period where no data is recorded while the voltage stabilizes. Hence the  $(1/64 - 0.002)$  and  $(1/32 - 0.002)$  terms in the following equations.

So while these conversion are quoted as to counts/second, they are technically counts per spacecraft clock tick. During flight so far, 1 spacecraft clock tick is within 0.0002% of 1 S.I. second, so assuming 1 tick equal 1 second is suitable (see the SPICE SCLKSCET kernel for variations in ticks compared to S.I. seconds).

For counts per accumulation products (where the level 2 object is total counts measured over a time period) the conversion to counts per second is as follows:

For electron HRS and electron CAL data:

$$C/sec = \frac{C}{ACCUMULATION\_TIME \left( \frac{1}{64} - 0.002 \right)} \quad (Eqn. 1)$$

Note that for HRS electron data, ACCUMULATION\_TIME = 1, so this simplifies to:

$$C/sec = \frac{C}{\frac{1}{64} - 0.002} \quad (Eqn. 2)$$

For **merged ping-pong** ion data (a record with 64 energy steps) for all TOF and LOG data, and HRS ion species:

$$C/sec = \frac{2C}{ACCUMULATION\_TIME \left( \frac{1}{32} - 0.002 \right)} \quad (Eqn. 3)$$

Note that for HRS **merged ping-pong** ion species data, ACCUMULATION\_TIME = 2, so this simplifies to:

$$C/sec = \frac{C}{\frac{1}{32} - 0.002} \quad (Eqn. 4)$$

The uncertainty (DATA\_SIGMA) of the DATA is calculated with similar equations to give the uncertainty counts per second.

For rate products the level 2 data returns a ‘per view’ average value so that the conversion of data is simpler, but the uncertainty is much more complex.

For electron LRS data:

$$C/sec = \frac{C/View}{\left(\frac{1}{64} - 0.002\right)} \quad (Eqn. 5)$$

For ion species data (merged ping-pong or not) for both LRS and CAL data:

$$C/sec = \frac{C/View}{\left(\frac{1}{32} - 0.002\right)} \quad (Eqn. 6)$$

Similar calculations are done for any level 2 background anodes used for a background later, although beware that some rate products have a background object that is total counts (and may be compressed differently to its corresponding DATA object), so must be converted accordingly. However the Level 3 TOF products TOF\_WITH\_START\_OVERLOAD, TOF\_TOO\_SHORT and TOF\_TOO\_LONG and their uncertainties are calculated as above for TOF data.

#### **6.2.10.116.2.11.11 Remove non-DATA elements from DATA arrays**

For high rate and calibration electron data the DATA array is size 64x51, where 64x48 is the actual data, and 64x3 are the background anodes. The level 3 DATA object is just the 64x48 array, and the background data are discarded (unless used later as an input to the BACKGROUND object).

Likewise the level 2 ion TOF DATA object is size 64x1x96 where the actual data is 64x1x93, and the last 3 have special meaning. The Level 3 TOF DATA object is size 64x1x93, and the others are given their own objects in the TOF record: TOF\_WITH\_START\_OVERLOAD, TOF\_TOO\_SHORT and TOF\_TOO\_LONG – each of size 64.

#### **6.2.10.126.2.11.12 Remove an appropriate background to ‘clean’ the dataset.**

Remove a background and/or clean the data (e.g. remove false co-incidences (“ghost peaks” of other ion species) from ion species products), and remove that from the level 3 data object. Calculate the uncertainty on that background, and propagate that uncertainty with the data uncertainty to replace DATA\_SIGMA.

For ~~initial version 00 and Level 3~~ version 01 ~~and 02~~ files we are not removing a background nor ‘cleaning’ the data, hence the BACKGROUND object is zeros (and likewise BACKGROUND\_SIGMA is zeros).

For Level 3 version 03 files (electrons only, there are no version 3 ion files) a time-independent background is removed. (See next paragraph for how to find details of the version 03 background removal calculations.)

For Level 3 version 04 files a time-dependent (per orbit) background is removed from the electron, ion TOF and ion species data. No background is ever removed for ion logicals files. (See the JAD L30 CALIB LIST 00002.TXT file more details on the background removal calculations used for Level 3 versions 03 and 04.)

|

### **6.2.10-136.2.11.13 Assign correct energy table to the data**

Using the reported Look Up Table in Level 2 files (TABLES\_VERSION object) and sweep table number (SWEEP\_TABLE object), apply the corrected ground calibrated energy table to the data to fill DIM1\_E objects. Version 00 files may use a temporary estimated energy table, but Version 01 onwards files will have the specific energy table used at their time. The energy tables are in the CALIB/LUT\_m\_nn\_ENERGY\_Vvv.CSV or CALIB/LUT\_m\_nn\_T\_ENERGY\_Vvv.CSV files, with the particular one used listed in the JAD\_L30\_CALIB\_LIST\_nnnnn.TXT (each level 3 record lists nnnnn in the object SOURCE\_JADE\_CALIB). Alternatively, from level 3 V04 files, the objects LUT\_VERSION and LUT\_VERSION SUB LETTER were added to provide m.nn and T respectively (while LUT\_SWEEP\_TABLE is the sweep table number).

### **6.2.10-146.2.11.14 Populate azimuth and elevations angles in a despun frame.**

For each look direction populate the DIM2\_\* azimuth and elevation angles, and upper and lower limits. This is despun so requires using SPICE to find the spin phase (from earlier) and adjust accordingly.

Check here for FSW3 or FSW 4.00 data (2015-Jan and before only), and if so, set the LRS electron data azimuths to fill values. This was because prior to FSW 4.10 (August 2015) the anode mapping to electron spin-phase sector was incorrectly reversed in flight software and cannot be reversed. See the ISSUES object for more information. This will not apply to any data at Jupiter (2016+).

Azimuth and elevation information is provided in the CALIB directory files: ANODE\_LOOK\_ELC\_DEFL\_NONE\_Vvv and ANODE\_LOOK\_ION\_DEFL\_NONE\_Vvv. (Version 01 DAT files use vv = 02, vv = 01 is skipped.) When necessary for the product they are despun using spin phase. For HRS products, the values are given per energy step, accounting for the earlier 2ms settling time and smear introduced by the spacecraft spinning during each energy step. There may be a further correction to the elevation angle, which is dealt with later.

Ensure all azimuth angles (degrees) are positive, with the lower values being smaller than the center value, which itself is smaller than the upper value. It is possible some angles may be more than 360 degrees greater than the last, but in practice in *sin* or *cos* statements that has no effect.

### **6.2.10-156.2.11.15 If TOF data, Populate DIM3\_\* objects**

Convert ground [channelbin](#) numbers 0-92 (HRS, LRS or CAL) to a real time range in seconds. Onboard there are really 256 channels that are mapped down to the 96 (ground) bins of level 2 files, and these bins can have different widths.

The last three (onboard channels 253, 254 and 255 which map to ground [channelsbins](#) 93, 94 and 95) have special meanings, and are separated out as their own objects in level 3 files. Note that onboard channels 248-252 inclusive are not mentioned; these are used as padding onboard, so are always zero and never included in ground data.

See the CALIB file TOF\_CHANNEL\_TO\_SECONDS\_HLC\_Vvv.CSV for the final values in seconds, and see JAD\_L30\_CALIB\_LIST\_nnnnnn.TXT for the conversion equations. (For HVE TOF data (with 125 ground values (128 – 3 of special meaning) instead of 93 values) the situation is much the same, but use file TOF\_CHANNEL\_TO\_SECONDS\_HVE\_Vvv.CSV.)

**6.2.10.166.2.11.16 If Electron data, despin MAG vector to same despun frame as the azimuths.**

JADE Level 2 electron files have a MAG vector within them in spacecraft co-ordinates, ion data do not, so ion data do not have an included MAG\_VECTOR object. For electron data, use the MAG\_TIMESTAMP\_WHOLE:MAG\_TIMESTAMP\_SUB spacecraft clock timestamp from Level 2 files to find the spin phase (sp) at that instant, and rotate MAG\_VECTOR x and y components accordingly (z component does not change). If using SPICE to convert this MAG timestamp in to ephemeris time, be sure to use Juno’s high precision clock code (NAIF\_SPACECRAFT\_ID = -61999) since MAG\_TIMESTAMP\_SUB is a two-byte value. Unfortunately, our Level 3 version 01 code for LRS electrons used the standard precision clock (one-byte value) which caused errors, and this was fixed in Level 3 version 02 files – see the CALIB directory for more information in file:

JADE\_LEVEL3\_V02\_COMPARED\_TO\_V01\_DESCRIPTION\_V01.PDF

[Note that MAG\_TIMESTAMP\_WHOLE:MAG\_TIMESTAMP\_SUB if taken from JADE Level 2 files may be affected by the Juno time stutter, we do not attempt any correction for that.]

If the magnetic field is less than a commanded threshold (threshold was originally 200 nT, later changed to 25 nT, and could be altered in future) then the MAG\_VECTOR is not provided (just zeros in Level 2, and in Level 3 is set to MISSING\_CONSTANT), so MAG\_VECTOR is only populated at low radial distances such as perijove passes.

For HRS Level 2 files there is no MAG\_TIMESTAMP\_SUB object, so it is assumed to be 00000 in Level 3 version 01 files, meaning the spin phase angle can be off by up to ~12 degrees (based on a 30s spin period). For Level 3 version 02 files, MAG\_TIMESTAMP\_SUB is assumed to be 32768 (= half a MAG\_TIMESTAMP\_WHOLE) so that the spin phase angle can be off by up to ± 6 degrees (rather than +12 and -0 degrees of version 01). [More explanation is provided in the CALIB file JADE\_LEVEL3\_V02\_COMPARED\_TO\_V01\_DESCRIPTION\_V01.PDF ]

The equations used to despin the MAG vector are simply:

$$\begin{aligned}
 L3.MAG\_VECTOR\_X &= L2.MAG\_VECTOR\_X * \cos(sp) - L2.MAG\_VECTOR\_Y * \sin(sp) \\
 L3.MAG\_VECTOR\_Y &= L2.MAG\_VECTOR\_X * \sin(sp) + L2.MAG\_VECTOR\_Y * \cos(sp) \\
 L3.MAG\_VECTOR\_Z &= L2.MAG\_VECTOR\_Z
 \end{aligned}$$

**6.2.10.176.2.11.17 If HRS electron data at Jupiter, adjust the earlier elevation angles for the deflectors**

The electron sensors have deflectors that are only active for HRS when the magnitude of the MAG\_VECTOR is greater than a threshold magnitude, that was originally set to 200 nT (and later change to 25 nT, and could be altered again in future). As such this was first used during PJ1 (2016-240) and never used during cruise (as the magnetic field was far below the (200 nT)

threshold magnitude in the solar wind and magnetosphere). The deflectors adjust the elevation angle to track the magnetic field vector. This correction to DIM2\_ELEVATION values (including upper and lower) needs to be done. The calibration equations used for this correction are given in the CALIB directory file ANODE\_LOOK\_ELC\_DEFL\_EQNS\_Vvv.PDF. (See file JAD\_L30\_CALIB\_LIST\_nnnnn.TXT for which Vvv.) For all other times and modes (LRS/CAL or HRS with magnetic field magnitude under the threshold magnitude) the electron deflectors are off and the ANODE\_LOOK\_ELC\_DEFL\_NONE\_Vvv elevation angles are used.

[JADE-I does also have deflectors, however it was decided they would never be used.]

### **6.2.10-186.2.11.18 Level 2 records that do not get converted to Level 3**

Now remove any records that are not worthy of becoming Level 3 files. Any Level 2 record with ACCUM\_TRUNCATION = 1, or MCP\_COMMANDED\_VALUE = 0, or MCP\_NOT\_AT\_COMMANDED = 1 or TABLES\_VERSION = -99.99 (=MISSING\_CONSTANT) is excluded from becoming a Level 3 record and is removed. Records that have any MISSING\_CONSTANT values in the DATA object are still converted.

HRS/CAL/HVE electron products are unique in that they use three sensors per record, rather than just one sensor per record for JADE-I or LRS electrons. For HRS electron Level 3 version 01 files, if any one of the three sensors had MCP\_NOT\_AT\_COMMANDED = 1 then the entire record is excluded from level 3. However, it was realized that during certain situations (e.g. changing from LRS to HRS, or MCP dipping) it was possibly for an electron sensor to have MCP\_NOT\_AT\_COMMANDED at 0 and the other sensors to be at 1. For HRS Level 3 version 02 files, if at least one of the three electron sensors had MCP\_NOT\_AT\_COMMANDED = 0 then that record is kept for level 3 to keep the good data from that sensor(s), but the data for the other sensor(s) (with MCP\_NOT\_AT\_COMMANDED = 1) are set to fill values. For such cases, this is marked in the ISSUES object of the record as “Bit 21”. If all three electron sensors have MCP\_NOT\_AT\_COMMANDED = 0 then the whole record is still excluded from Level 3 version 02 files. For more information see the ISSUES object description and the CALIB file: JADE\_LEVEL3\_V02\_COMPARED\_TO\_V01\_DESCRIPTION\_V01.PDF [In the PDS this only applies to HRS electron data; however for the JADE operations team, the CAL electron files are filtered similarly.]

For Level 3 records of JAD\_L30\_LRS\_ELC\_ANY and JAD\_L30\_LRS\_ION\_ANY (and JAD\_L30\_CAL\_ION\_ANY, not in PDS) if the ACCUMULATION\_TIME of the record is less than the SC\_SPIN\_PERIOD (rounded to whole number) then remove it (as less than a whole spin for a spin product).

For Level 3 records of JAD\_L30\_HLS\_ION\_LOG (and JAD\_L30\_CAL\_ION\_LOG, not in PDS) if the ACCUMULATION\_TIME of the record is an odd number then remove it (as missing a ping or a pong).

What records remain are written to a level 3 PDS compliant DAT file, if no records remain then no file is written.



#### **6.2.11.19 Level 3 DATA and BACKGROUND MISSING CONSTANT (fill) values**

For Level 3 version 01, 02 and 03 data, the MISSING\_CONSTANT value (also known as the fill value) for objects DATA, DATA\_SIGMA, BACKGROUND and BACKGROUND\_SIGMA are -1. In the initial design, we were never going to remove a background, so all counts would be positive, hence -1 was a reasonable MISSING\_CONSTANT.

However, once we began removing background in version 03 files, it was possible for DATA to go negative. While our production code ensures that a background removed data value was never exactly -1, there was room for confusion as there were many valid DATA elements with counts near zero, positive or negative.

For Level 3 version 04(+) data, the MISSING\_CONSTANT value for objects DATA, DATA\_SIGMA, BACKGROUND and BACKGROUND\_SIGMA are -999999. This value is so negative that no valid DATA elements would be near.

If this change of MISSING\_CONSTANT value is an issue for your codes, you can easily do a find/where command in your code to turn any -999999s in these four objects back to -1.

#### **6.2.11.20 Use SPICE to add position and orientation information**

SPICE was used with reconstructed kernels to calculate the position, velocity, orientation and transformation matrix objects. (These objects all begin with SC\_\*, except for the transformation matrices DESPUN\_SC\_TO\_J2000, J2000\_TO\_JSSXYZ and J2000\_TO\_JSSRTP). Predicted kernels may have been used for version 00 test files, but never for non-zero version numbers.

While there is a SC\_POS\_SYSIII\_ELONG object in version 04 files, there is no System III LAT object since this value is identical to SC\_POS\_LAT that was already present in earlier versions.

### 6.2.10-196.2.11.21 The Jupiter De-Spun-Sun (JUNO\_JSS) co-ordinate System

The Juno Jupiter De-Spun-Sun system is the primary Jovian co-ordinate system the JADE team uses (Figure 4+12) and is known as JUNO\_JSS in the Juno SPICE frame kernel (file: fk/juno\_v09.tf or latest version of this file). It is Jupiter-centered, with the Z-axis aligned with the Jovian spin axis but does not spin with the planet. The X-axis is in the plane containing the spin axis and the Jupiter-Sun vector, where the Sun position has been aberration corrected.

If:

$$\begin{aligned} J_{\Omega} &= \text{unit vector of Jupiter spin axis} \\ R_{JS} &= \text{unit vector of Jupiter to Sun line} \end{aligned}$$

Then:

$$\begin{aligned} Z &= J_{\Omega} \\ Y &= Z \times R_{JS} \\ X &= Y \times Z \end{aligned}$$

If using SPICE, do not aberration correct (use `abcorr = 'none'` in SPICE commands such as `spkezr` or `spkpos`).

The R, Latitude and Local Time (LT) system is based on JUNO\_JSS where R is the magnitude of the  $[x,y,z]$  vector (in planetary radii,  $R_J$ ), Latitude is the inverse sine of  $z/R$  (degrees) and Local Time (0-24 hours, where 12 hours is along +X and 18 hours LT along +Y) is a different way of expressing *longitude* (degrees from +X, positive in the direction towards +Y), where:

$$\text{Local time} = [(longitude + 180^\circ) * 24/360] \text{ MOD } 24 = [(\text{atan}(y,x) + \pi) * 12/\pi] \text{ MOD } 24$$

("atan" is the four quadrant inverse tangent of y and x expressed in radians.)

To calculate LT using SPICE, the command `et2lst` with `type = 'PLANETOCENTRIC'` will provide Local (solar) Time values, which is aberration corrected (`abcorr = 'LT+S'`) unlike the above JUNO\_JSS *longitude* way. At Jupiter the difference between the methods is  $< 0.6$  s LT, and since `et2lst` returns whole seconds only, both methods are equivalent in practice.




Figure 12: The Jupiter De-Spun-Sun (JUNO\_JSS) co-ordinate system.

Note: System III latitude is identical to JUNO\_JSS latitude, since they share the same Z axis.

### 6.2.116.2.12 Level 4 data files

There are no CODMAC Level 4 JADE products, as this is a level more designed for cameras than particle data (see Table 5). As such JADE goes from Level 3 to level 5 directly.

### 6.2.126.2.13 Level 5 data files

Table 80: Format of Level 5 primary science data file records

Byte	Length (bytes)	Name	Fmt*	Units	Description
		[TBD]			

## Appendix A Support staff and cognizant persons

Table 81: Archive collection support staff

JADE team			
Name	Address	Phone	Email
<b>Dr Rob Wilson</b> JADE ground data processing / Archivist	LASP, Space Science Building, University of Colorado Boulder 3665 Discovery Drive Boulder, CO 80303-7813	+001 303 492 5476	Rob.Wilson@ lasp.colorado.edu
<b>Dr Frédéric Allegrini</b> JADE Lead and JADE Electron Instrument Scientist	Southwest Research Institute 6220 Culebra Road San Antonio, TX 78238-5166		fallegrini@swri.edu
<b>Dr Robert W. Ebert</b> JADE Ion Instrument Scientist	Southwest Research Institute 6220 Culebra Road San Antonio, TX 78238-5166		rebert@swri.edu
<b>Mr Chad Loeffler</b> JADE Flight Software	Southwest Research Institute 6220 Culebra Road San Antonio, TX 78238-5166		cloeffler@swri.edu

UCLA			
Name	Address	Phone	Email
<b>Dr. Steven Joy</b> PPI Operations Manager	IGPP, University of California 405 Hilgard Avenue Los Angeles, CA 90095-1567 USA	+001 310 825 3506	sjoy@igpp.ucla.edu
<b>Mr. Joseph Mafi</b> PPI Data Engineer	IGPP, University of California 405 Hilgard Avenue Los Angeles, CA 90095-1567 USA	+001 310 206 6073	jmafi@igpp.ucla.edu

JADE has had a turn-over in lead staff since launch.

- Build, pre-launch, launch to 2016-May-24:  
Dr David J. McComas was JADE Lead.  
Dr Philip Valek was the JADE Ion Instrument Scientist.  
Dr Frédéric Allegrini was the JADE Electron Instrument Scientist.
- 2016-May-24 to 2018-May-21:  
Dr Philip Valek was the JADE Lead and JADE Ion Instrument Scientist.  
Dr Frédéric Allegrini was the JADE Electron Instrument Scientist.
- 2018-May-21 onwards:  
Dr Frédéric Allegrini is the JADE Lead and JADE Electron Instrument Scientist.  
Dr Robert W. Ebert is the JADE Ion Instrument Scientist.

## Appendix B PDS label files

All JADE instrument data files are accompanied by PDS label files, possessing the same names as the files they describe, but with the extension LBL. The basic content for these label files is as follows, where the NOTE field is reserved for product-specific comments:

Font below is Courier New (to equally space characters) and size 9 in order to get 78 characters to a line. This matches the PDS files that are 80 characters to a line, but the last two are `\r\n`.

### B.1 Sample LBL file for JAD\_L20\_LRS\_ELC\_ANY\_\*

```
PDS_VERSION_ID = PDS3
DATA_SET_ID    = "JNO-J/SW-JAD-2-UNCALIBRATED-V1.0"

/* Input file : JAD_L20_LRS_ELC_ANY_2015090_V01.DAT */
/* File written: 2017/05/04 23:01:39 local time */

STANDARD_DATA_PRODUCT_ID = "JAD_L20_LRS_ELC_ANY"
PRODUCT_ID               = "JAD_L20_LRS_ELC_ANY_2015090"
PRODUCT_VERSION_ID      = "01"
PRODUCT_TYPE             = "DATA"
PRODUCT_CREATION_TIME   = 2017-125T05:01:39 /* UTC 2017-05-05 */
PROCESSING_LEVEL_ID     = "2"

RECORD_TYPE = FIXED_LENGTH
RECORD_BYTES = 12384
FILE_RECORDS = 2

START_TIME           = 2015-090T00:35:45.001 /* 2015-03-31 */
STOP_TIME            = 2015-090T00:43:16.004 /* 2015-03-31 */
SPACECRAFT_CLOCK_START_COUNT = "481034275.64325" /* WHOLE.SUB (SUB 0-65535) */
SPACECRAFT_CLOCK_STOP_COUNT = "481034727.00000" /* Rounded nearest */
/* JADE records have start time SPACECRAFT CLOCK, so to get end time */
/* of last record, I've added the Accumulation time value to both */
/* UTC seconds and SPACECRAFT CLOCK, - although those are not equal. */
/* Hence the SPACECRAFT_CLOCK_STOP_COUNT is rounded for now. */

INSTRUMENT_HOST_NAME = "JUNO"
INSTRUMENT_HOST_ID   = "JNO"
TARGET_NAME          = {"JUPITER"}
INSTRUMENT_NAME      = "JOVIAN AURORAL PLASMA DISTRIBUTIONS EXPERIMENT"
INSTRUMENT_ID        = "JAD" /* JADE */

DESCRIPTION = "This is the required LBL file to accompany DAT files of the
              data product JAD_L20_LRS_ELC_ANY."

MD5_CHECKSUM = "44e5efb1590fd55882dae9c00123d699"

NOTE = "See the PDS JADE SIS Document for more details on the formats."

^TABLE = "JAD_L20_LRS_ELC_ANY_2015090_V01.DAT"
OBJECT = TABLE
  INTERCHANGE_FORMAT = "BINARY"
  ROWS                = 2
  COLUMNS            = 32
  ROW_BYTES           = 12384
  DESCRIPTION         = "Describes the structure and content of the data file."

/* FMT file contents start here. */
/* Filename: Version01/JAD_L20_LRS_ELC_ANY_V01.FMT */
```

```

/* File written: 2017/05/02 15:42:00 */
/* Will code useful Python based letters to describe each object */
/* see http://docs.python.org/library/struct.html for codes */
/* formats will comma separated beginning with "R JW," as key then */
/* {NAME}, {FORMAT}, {Number of dims}, {Size Dim 1}, {Size Dim 2}, ... */
/* where {FORMAT} is the Python code for the type, i.e. I for uint32 */
/* and there are as many Size Dim's as number of dimensions. */
/* Remember to remove the comment markers at either end */

/* R JW, BYTES_PER_RECORD, 12384 */
/* R JW, OBJECTS_PER_RECORD, 32 */

OBJECT          = COLUMN
  NAME          = SYNC
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 1
  BYTES         = 4
  VALID_MINIMUM = 4210242563
  VALID_MAXIMUM = 4210242563
  MISSING_CONSTANT = 0 /* If no Sync pattern there is no record */
  DESCRIPTION    = "JADE Sync Pattern for IDP packets.
                   Hex value = 0xFAF33403, Decimal = 4210242563"
/* R JW, SYNC, I, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = DPID_COUNT
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 5
  BYTES         = 1
  VALID_MINIMUM = 0
  VALID_MAXIMUM = 255
  DESCRIPTION    = "DPID Count (Source Sequence Count)
                   Count of the number of times this product has been
                   generated since the startup (or reset) of the
                   generating application (Boot Program or Science
                   Program). This count resets to 0 upon entry to
                   the modes of BOOT, LVENG, HVENG, LOW_RATE_SCI,
                   MCP_CAL_SCI, HI_RATE_SCI, LOW_RATE_SCI2,
                   MCP_CAL_SCI2, HI_RATE_SCI2.
                   Note: starts with 0, increments by 1, eventually
                   rolls over at 255."
/* R JW, DPID_COUNT, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = COMPRESSION
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 6
  BYTES         = 1
  VALID_MINIMUM = 0
  VALID_MAXIMUM = 1
  MISSING_CONSTANT = 255
  DESCRIPTION    = "Lossless Compression Status.
                   Indicates whether the data (non-header) segment of
                   the IDP packet (IDP Data) was lossless compressed.
                   0 = Not Compressed
                   1 = Compressed"
/* R JW, COMPRESSION, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = IDPLENGTH

```

```

DATA_TYPE           = LSB_UNSIGNED_INTEGER
START_BYTE         = 7
BYTES              = 2
VALID_MINIMUM      = 60 /* Depends on onboard compression, if any. */
VALID_MAXIMUM      = 3128
MISSING_CONSTANT   = 65535
DESCRIPTION        = "IDP Length,
                    Byte Length of the IDP packet.
                    Uncompressed size for this product should be 3128."
/* RJW, IDPLENGTH, H, 1, 1 */
END_OBJECT         = COLUMN

OBJECT             = COLUMN
NAME              = PACKETID
DATA_TYPE         = LSB_UNSIGNED_INTEGER
START_BYTE       = 9
BYTES            = 1
VALID_MINIMUM    = 1 /* 0x01 - Range covers all JADE packets, */
VALID_MAXIMUM    = 163 /* 0xA3 - Even those not in the PDS. */
MISSING_CONSTANT = 255
DESCRIPTION      = "Packet ID (DPID), Data Product Identifier
                    Low Rate Science - Electron Histogram
                    Only one Sensor per packet: Either E060, E180 or E300.
                    Each packet is one of the following:
                    E060 only, PACKETID = 104 /* 0x68 */
                    E180 only, PACKETID = 106 /* 0x6A */
                    E300 only, PACKETID = 107 /* 0x6B */"
/* RJW, PACKETID, B, 1, 1 */
END_OBJECT         = COLUMN

OBJECT             = COLUMN
NAME              = FLIGHT_OR_STL
DATA_TYPE         = LSB_UNSIGNED_INTEGER
START_BYTE       = 10
BYTES            = 1
VALID_MINIMUM    = 0
VALID_MAXIMUM    = 2
MISSING_CONSTANT = 255
DESCRIPTION      = "In Flight data, or STL (ground EM tests):
                    0 = In flight, from JADE on Juno (via FEI)
                    1 = On ground, from STL tests (via FEI)
                    2 = On ground, from SwRI tests (not FEI)
                    255 = Unknown"
/* RJW, FLIGHT_OR_STL, B, 1, 1 */
END_OBJECT         = COLUMN

OBJECT             = COLUMN
NAME              = PACKET_MODE
DATA_TYPE         = LSB_INTEGER
START_BYTE       = 11
BYTES            = 1
VALID_MINIMUM    = -2
VALID_MAXIMUM    = 2
MISSING_CONSTANT = 127
DESCRIPTION      = "Packet Mode, describes type of data telemetry.
                    -2 = HSK / Housekeeping Engineering
                    -1 = HVE / High Voltage Engineering
                    0 = CAL / MCP Calibration Science
                    1 = LRS / Low Rate Science
                    2 = HRS / High Rate Science
                    127 = Unknown
                    254 = Wrong - but HSK, see below.
                    255 = Wrong - but HVE, see below."

```

```

                (Note, this could also be calculated via PACKETID.)
                If you have 254 or 255 then your code is incorrect,
                check you read a signed byte, rather than unsigned."
/* RJW, PACKET_MODE, b, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = PACKET_SPECIES
DATA_TYPE      = LSB_INTEGER
START_BYTE     = 12
BYTES          = 1
VALID_MINIMUM  = -1
VALID_MAXIMUM  = 9
MISSING_CONSTANT = 127
DESCRIPTION    = "Packet Species, describes type of plasma data.
                -1 = electrons
                0 = ion species 0, SP0
                1 = ion species 1, SP1
                2 = ion species 2, SP2
                3 = ion species 3, SP3
                4 = ion species 4, SP4
                5 = ion species 5, SP5
                6 = ion species 6, SP6
                7 = ion species 7, SP7
                8 = Not Used
                9 = All ions
                127 = Unknown
                255 = Wrong - but electrons, see below.
                If you have 255 then your code is incorrect,
                check you read a signed byte, rather than unsigned."
/* RJW, PACKET_SPECIES, b, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = TIMESTAMP_WHOLE
DATA_TYPE      = LSB_UNSIGNED_INTEGER
START_BYTE     = 13
BYTES          = 4
VALID_MINIMUM  = 365774402 /* 2011-Aug-05: Juno Launch */
VALID_MAXIMUM  = 599573000 /* ~ 2019-Jan-01 */
MISSING_CONSTANT = 0
DESCRIPTION    = "Timestamp (Whole Second).
                Timestamp (whole second) of the data for this packet
                when collection began.
                This is sometimes referred to as Mission Elapsed Time
                (MET) and is Referenced from 2000-001T12:00:00.000 UTC,
                but 1 tick is not exactly 1 S.I. second.
                See UTC object for corrected converted time.
                Note: Spacecraft Clock = TIMESTAMP_WHOLE:TIMESTAMP_SUB"
/* RJW, TIMESTAMP_WHOLE, I, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = TIMESTAMP_SUB
DATA_TYPE      = LSB_UNSIGNED_INTEGER
START_BYTE     = 17
BYTES          = 2
VALID_MINIMUM  = 0
VALID_MAXIMUM  = 65535
MISSING_CONSTANT = 0
DESCRIPTION    = "Timestamp (Subsecond).
                Timestamp subsecond of the data for this packet
                when collection began.

```



```

Unit: Microseconds scaled to 16 bits.
Note: Spacecraft Clock = TIMESTAMP_WHOLE:TIMESTAMP_SUB"
/* RJW, TIMESTAMP_SUB, H, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = ACCUMULATION_TIME
DATA_TYPE       = LSB_UNSIGNED_INTEGER
START_BYTE      = 19
BYTES           = 2
VALID_MINIMUM   = 1
VALID_MAXIMUM   = 1800
MISSING_CONSTANT = 65535
UNIT            = "SECONDS"
DESCRIPTION     = "Accumulation Time.
                  Number of seconds over which the data in this product
                  was collected (Science Program)."
```

```

/* RJW, ACCUMULATION_TIME, H, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = TABLES_VERSION
DATA_TYPE       = PC_REAL
START_BYTE      = 21
BYTES           = 4
VALID_MINIMUM   = 0.00
VALID_MAXIMUM   = 99.99
MISSING_CONSTANT = -99.99
DESCRIPTION     = "Look Up Tables (LUT) version used onboard.
                  All tables are combined (compression, sweeping,
                  macros, etc.) onboard in to a large image.
                  This is the image number, or table version.
                  Number should be to 2 decimal places."
```

```

/* RJW, TABLES_VERSION, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = FSW_VERSION
DATA_TYPE       = PC_REAL
START_BYTE      = 25
BYTES           = 4
VALID_MINIMUM   = 0.00
VALID_MAXIMUM   = 9.99
MISSING_CONSTANT = -99.99
DESCRIPTION     = "Flight Software version used.
                  Number should be to 2 decimal places."
```

```

/* RJW, FSW_VERSION, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = ACCUM_TRUNCATION
DATA_TYPE       = LSB_UNSIGNED_INTEGER
START_BYTE      = 29
BYTES           = 1
VALID_MINIMUM   = 0
VALID_MAXIMUM   = 1
MISSING_CONSTANT = 255
DESCRIPTION     = "Accumulation Truncation,
                  Whether commanded accumulation time ended early.
                  0 = Nominal
                  1 = Early
                  255 = Unknown"
```

```

/* RJW, ACCUM_TRUNCATION, B, 1, 1 */
```

```

END_OBJECT          = COLUMN

OBJECT              = COLUMN
  NAME              = DATA_UNITS /* Science Data Units only, not HSK */
  DATA_TYPE        = LSB_UNSIGNED_INTEGER
  START_BYTE        = 30
  BYTES             = 1
  VALID_MINIMUM     = 0
  VALID_MAXIMUM     = 1
  MISSING_CONSTANT  = 255
  DESCRIPTION       = "Science Data could be total counts (per accumulation)
                      or a rate, normalized to counts per view.
                      0 = All counts in the accumulation period (int)
                      1 = All counts divided by number of views (float)
                      2 = Counts per second (float)
                      255 = Not appropriate for this dataset, or Unknown."
/* RJW, DATA_UNITS, B, 1, 1 */
END_OBJECT          = COLUMN

OBJECT              = COLUMN
  NAME              = COMPRESSION_RATIO
  DATA_TYPE        = PC_REAL /* i.e. a float in little endian format */
  START_BYTE        = 31
  BYTES             = 4
  VALID_MINIMUM     = 1
  VALID_MAXIMUM     = 10
  MISSING_CONSTANT  = -1
  DESCRIPTION       = "Data compression ratio of data blob when it was
                      transmitted to Earth:
                      Ratio = {Uncompressed size}/{Compressed size}
                      This is the compression due to the lossless
                      scheme, and does not include any lossy compression
                      which may have occurred prior to it, such as the
                      32-bit to 8-bit or 16-bit to 8-bit look up tables
                      that are often used prior to the lossy compression.
                      A value of 1 means there was no lossless data
                      compression, i.e. it was turned off, and object
                      COMPRESSION should equal 1."
/* RJW, COMPRESSION_RATIO, f, 1, 1 */
END_OBJECT          = COLUMN

OBJECT              = COLUMN
  NAME              = UTC
  DATA_TYPE        = DATE /* ASCII character string */
  START_BYTE        = 35
  BYTES             = 21
  VALID_MINIMUM     = 2011-217T00:00:00.001
                      /* SC Clock 365774402:0, JUNO Launch */
  VALID_MAXIMUM     = 20192026-001T00:00:00.000 /* Expect~extended mission end */
  MISSING_CONSTANT  = 0001-001T00:00:00.000
  DESCRIPTION       = "UTC timestamp, of format yyyy-dddTHH:MM:SS.sss
                      where yyyy = year, ddd = day of year,
                      HH = hour, MM = minute,
                      SS.sss = decimal seconds to millisecond resolution.
                      Value calculated via SPICE from spacecraft clock time,
                      {TIMESTAMP WHOLE}:{TIMESTAMP SUB}"
/* RJW, UTC, c, 1, 21 */
END_OBJECT          = COLUMN

OBJECT              = COLUMN
  NAME              = LEAP_SECOND_VERSION
  DATA_TYPE        = LSB_UNSIGNED_INTEGER
  START_BYTE        = 56

```

```

BYTES = 1
VALID MINIMUM = 1
VALID MAXIMUM = 22 /* Unpredictable, but no more than 2 a year */
MISSING CONSTANT = 255
DESCRIPTION = "The NAIF SPICE kernel for lsk used to generate UTC.
The lsk (leap second kernels) files are used in time
conversions and have filenames naifnnnn.tls, where
is the lsk version number (with leading zeros)."
/* RJW, LEAP SECOND VERSION, B, 1, 1 */
END OBJECT = COLUMN

OBJECT = COLUMN
NAME = SCLKSCET VERSION
DATA TYPE = LSB INTEGER
START BYTE = 57
BYTES = 2
VALID MINIMUM = -32767
VALID MAXIMUM = 32767
MISSING CONSTANT = -32768
DESCRIPTION = "The NAIF SPICE kernel for sclk used to generate UTC.
The JUNO sclk files are used to convert the spacecraft
clock timestamps to UTC time, and all have filenames
JNO SCLKSCET.nnnnn.tsc, where nnnnn is the SCLKSCET
version number (with leading zeros and positive).
Each kernel has a reconstructed and predicted part for
it's values, typically any time after the last row of
the SCLK01 COEFFICIENTS 61999 table is predicted.
If TIMESTAMP WHOLE:TIMESTAMP SUB is in the predicted
part then SCLKSCET VERSION will be negative, the
absolute value would be the version number. If a later
SCLKSCET kernel version is used the UTC time will
likely be different.
If TIMESTAMP WHOLE:TIMESTAMP SUB is in the
reconstructed region the number will be positive
(equal to the version number) and will not vary with
later kernels.
e.g. If SCLKSCET VERSION = -17 then kernel
JNO SCLKSCET.00017.tsc was used to convert to UTC, but
it's a predicted UTC time.
If SCLKSCET VERSION = 18 then kernel
JNO SCLKSCET.00018.tsc was used to convert to UTC, and
it's a reconstructed UTC time that will not change with
later SCLKSCET kernel versions.
Within the PDS archive this value should always be
positive."
/* RJW, SCLKSCET VERSION, h, 1, 1 */
END OBJECT = COLUMN

OBJECT = COLUMN
NAME = ISSUES
DATA TYPE = LSB UNSIGNED INTEGER
START BYTE = 59
BYTES = 4
VALID MINIMUM = 0
VALID MAXIMUM = 4294967294
MISSING CONSTANT = 4294967295
DESCRIPTION = "Issues or potential issues in this data record.
These are issues that can be identified within the JADE
packet of data itself without any external information.
e.g. timing issues due to the MAG time stutter, or any
voltage pulsing, would not be included as there are no
indicators to them within this JADE packet.
[For a more comprehensive list of potential issues

```

from internal and external sources please see the  
Level 3 data.]

Level 2 issues of this JADE packet are flagged by  
individual bits, and several may be hit. If no issues  
are flagged then this 4-byte unsigned integer is zero.  
A value of 4294967295 is the MISSING CONSTANT and means  
that the issue status is currently unknown.

All bits at 0 implies all is okay as seen by this  
packet. If a bit is set to 1 then that bit is flagged,  
otherwise it is set to zero and unflagged.

The bits are set as followed, grouped in to seriousness:

Not very serious issues for doing science:

Bit 0 = UTC time is predicted, yet to be finalized.

Bit 1 = Position/Orientation values predicted, yet to  
be finalized. Level 3 (and above) data only.

Bit 2 = TABLES VERSION object was altered on the  
ground to accurately reflect a 'commanded  
parameter update' outside the initial  
per-orbit commands JADE is returning.  
[If changed, the original downlinked  
TABLES VERSION value can be found by cross-  
referencing the PARAM TABLE VER object in the  
JAD L20 HSK ALL SHK files. Note here the  
PARAM TABLE VER value is given as a unsigned  
integer of Hex Major-Middle-Minor, such that  
a value of 770 decimal is in hex 0x302,  
meaning Table Version 3.02 ]

Bit 3 = FSW VERSION 4.00 LRS/CAL Ion Species bug  
fixed on the ground by adjusting  
TIMESTAMP WHOLE, TIMESTAMP SUB, and  
ACCUMULATION TIME based on cross-referencing  
JADE commanding.

Bit 4 = LRS/CAL Ion Species record with unobserved  
look directions (views) populated using views  
from neighboring record. See Bit 12 for  
uncorrected/unpopulated description.  
(Only possible if ACCUMULATION TIME = 30.)

Bit 5 = TIMESTAMP WHOLE/SUB adjusted on the ground  
to mitigate any Juno time stutter affects.  
[Other TIMESTAMPS are susceptible to the  
onboard time stutter too, but only the JADE  
packet TIMESTAMP WHOLE/SUB is tracked here.]

Bit 6 = Currently unused.

Bit 7 = Warning, a leap second occurs during the  
accumulation period.

Data slightly different than expected, but can be used  
for science with a little extra coding:

Bit 8 = ACCUM TRUNCATION object flagged.

Bit 9 = Electron (HRS/LRS/CAL) MAG objects are not  
tracked, are either zeros or MISSING CONSTANT.  
[LRS and CAL did not have MAG objects prior  
to FSW VERSION 4.10, therefore those MAG  
objects here are set to MISSING CONSTANT  
when FSW VERSION < 4.10.]

Bit 10 = TIMESTAMP WHOLE/SUB affected by a Juno  
onboard time stutter, JADE reported timestamp  
is likely 1 whole tick too large.  
[Other TIMESTAMPS are susceptible to the

```

onboard time stutter too, but only the JADE
packet TIMESTAMP WHOLE/SUB is tracked here.1
Bit 11 = Currently unused.
Bit 12 = LRS/CAL Ion Species record potentially has
unobserved look directions (spin phase sectors
or views) present in the data, meaning the
record may not contain data for a full 4pi
steradians field-of-view.
Unobserved look directions have zero counts
per view (or counts per second) in the data,
although an observed look direction may also
have zero counts if no ions were measured.
Therefore there is a potential confusion over
zero measured counts or simply unmeasured.
e.g. if the spin period is 30.7 seconds, then
not all of the 78 spin phase sectors will be
sampled in 30 seconds. (Unobserved views are
only possible if ACCUMULATION TIME in 2018 */
MISSING_CONSTANT = 0001 001T00:00:00.000
DESCRIPTION = "UTC timestamp, of format yyyy dddTHH:MM:SS.sss
where yyyy = year, ddd = day of year,
HH = hour, MM = minute,
SS.sss = decimal seconds to millisecond resolution.
Value calculated via SPICE from spacecraft clock time,
(TIMESTAMP_WHOLE):(TIMESTAMP_SUB)"
/* RJW, UTC, e, 1, 21 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = LEAP_SECOND_VERSION
DATA_TYPE = LSB_UNSIGNED_INTEGER
START_BYTE = 56
BYTES = 1
VALID_MINIMUM = 1
VALID_MAXIMUM = 22 /* Unpredictable, but no more than 2 a year */
MISSING_CONSTANT = 255
DESCRIPTION = "The NAIF SPICE kernel for lsk used to generate UTC.
The lsk (leap second kernels) files are used in time
conversions and have filenames naifnnnn.tls, where
is the lsk version number (with leading zeros)."
/* RJW, LEAP_SECOND_VERSION, D, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = SCLKSCET_VERSION
DATA_TYPE = LSB_INTEGER
START_BYTE = 57
BYTES = 2
VALID_MINIMUM = 32767
VALID_MAXIMUM = 32767
MISSING_CONSTANT = 32768
DESCRIPTION = "The NAIF SPICE kernel for sclk used to generate UTC.
The JUNO sclk files are used to convert the spacecraft
clock timestamps to UTC time, and all have filenames
JNO_SCLKSCET.nnnnn.tsc, where nnnnn is the SCLKSCET
version number (with leading zeros and positive).
Each kernel has a reconstructed and predicted part for
it's values, typically any time after the last row of
the SCLK01_COEFFICIENTS_61999 table is predicted.
If TIMESTAMP_WHOLE:TIMESTAMP_SUB is in the predicted
part then SCLKSCET_VERSION will be negative, the
absolute value would be the version number. If a later
SCLKSCET kernel version is used the UTC time will

```

```

===== likely be different.
===== If TIMESTAMP_WHOLE:TIMESTAMP_GUD is in the
===== reconstructed region the number will be positive
===== (equal to the version number) and will not vary with
===== later kernels.
===== e.g. If SCLKSCET_VERSION = 17 then kernel
===== JNO_SCLKSCET.00017.tsc was used to convert to UTC, but
===== it's a predicted UTC time.
===== If SCLKSCET_VERSION = 18 then kernel
===== JNO_SCLKSCET.00018.tsc was used to convert to UTC, and
===== it's a reconstructed UTC time that will not change with
===== later SCLKSCET kernel versions.
===== Within the PDS archive this value should always be
===== positive."
/* RJW, SCLKSCET_VERSION, h, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = ISSUES
DATA_TYPE = LSB_UNSIGNED_INTEGER
START_BYTE = 59
BYTES = 4
VALID_MINIMUM = 0
VALID_MAXIMUM = 4294967294
MISSING_CONSTANT = 4294967295
DESCRIPTION = "Issues or potential issues in this data record.
===== These are issues that can be identified within the JADE
===== packet of data itself without any external information.
===== e.g. timing issues due to the MAG time stutter, or any
===== voltage pulsing, would not be included as there are no
===== indicators to them within this JADE packet.
===== [For a more comprehensive list of potential issues
===== from internal and external sources please see the
===== Level 3 data.]

===== Level 2 issues of this JADE packet are flagged by
===== individual bits, and several may be hit. If no issues
===== are flagged then this 4 byte unsigned integer is zero.
===== A value of 4294967295 is the MISSING_CONSTANT and means
===== that the issue status is currently unknown.

===== All bits at 0 implies all is okay as seen by this
===== packet. If a bit is set to 1 then that bit is flagged,
===== otherwise it is set to zero and unflagged.

===== The bits are set as followed, grouped in to seriousness:

===== Not very serious issues for doing science.
===== Bit 0 = UTC time is predicted, yet to be finalized.
===== Bit 1 = Position/Orientation values predicted, yet to
===== be finalized. Level 3 (and above) data only.
===== Bit 2 = TABLES_VERSION object was altered on the
===== ground to accurately reflect a 'commanded
===== parameter update' outside the initial
===== per orbit commands JADE is returning.
===== [If changed, the original downlinked
===== TABLES_VERSION value can be found by cross-
===== referencing the PARAM_TABLE_VER object in the
===== JAD I20 HSK ALL_SHK files. Note here the
===== PARAM_TABLE_VER value is given as a unsigned
===== integer of Hex Major Middle Minor, such that
===== a value of 770 decimal is in hex 0x302,
===== meaning Table Version 3.02 ]

```

~~Bit 3 = FSW\_VERSION 4.00 LRS/CAL Ion Species bug fixed on the ground by adjusting~~  
~~TIMESTAMP\_WHOLE, TIMESTAMP\_SUB, and~~  
~~ACCUMULATION\_TIME based on cross referencing~~  
~~JADE commanding.~~

~~Bit 4 = LRS/CAL Ion Species record with unobserved~~  
~~look directions (views) populated using views~~  
~~from neighboring record. See Bit 12 for~~  
~~uncorrected/unpopulated description.~~  
~~(Only possible if ACCUMULATION\_TIME = 30.)~~

~~Bit 5 = TIMESTAMP\_WHOLE/SUB adjusted on the ground~~  
~~to mitigate any Juno time stutter affects.~~  
~~[Other TIMESTAMPS are susceptible to the~~  
~~onboard time stutter too, but only the JADE~~  
~~packet TIMESTAMP\_WHOLE/SUB is tracked here.]~~

~~Bit 6 = Currently unused.~~

~~Bit 7 = Warning, a leap second occurs during the~~  
~~accumulation period.~~

~~Data slightly different than expected, but can be used~~  
~~for science with a little extra coding.~~

~~Bit 8 = ACCUM\_TRUNCATION object flagged.~~

~~Bit 9 = Electron (HRS/LRS/CAL) MAG objects are not~~  
~~tracked, are either zeros or MISSING\_CONSTANT.~~  
~~[LRS and CAL did not have MAG objects prior~~  
~~to FSW\_VERSION 4.10, therefore those MAG~~  
~~objects here are set to MISSING\_CONSTANT~~  
~~when FSW\_VERSION < 4.10.]~~

~~Bit 10 = TIMESTAMP\_WHOLE/SUB affected by a Juno~~  
~~onboard time stutter, JADE reported timestamp~~  
~~is likely 1 whole tick too large.~~  
~~[Other TIMESTAMPS are susceptible to the~~  
~~onboard time stutter too, but only the JADE~~  
~~packet TIMESTAMP\_WHOLE/SUB is tracked here.]~~

~~Bit 11 = Currently unused.~~

~~Bit 12 = LRS/CAL Ion Species record potentially has~~  
~~unobserved look directions (spin phase sectors~~  
~~or views) present in the data, meaning the~~  
~~record may not contain data for a full 4pi~~  
~~steradians field of view.~~  
~~Unobserved look directions have zero counts~~  
~~per view (or counts per second) in the data,~~  
~~although an observed look direction may also~~  
~~have zero counts if no ions were measured.~~  
~~Therefore there is a potential confusion over~~  
~~zero measured counts or simply unmeasured.~~  
~~e.g. if the spin period is 30.7 seconds, then~~  
~~not all of the 78 spin phase sectors will be~~  
~~sampled in 30 seconds. (Unobserved views are~~  
~~only possible if ACCUMULATION\_TIME <= 30.)~~  
~~See the JADE SIS for more information.~~

Bit 13 = At least one anode is blanked.  
See SIS document for further information.

Bit 14 = FSW\_VERSION 4.00 LRS/CAL Ion Species bug  
warning:

Not fixed as yet - when fixed it will  
become bit 3 of ISSUES instead.

Level 2 data only when FSW\_VERSION = 4.00,  
ACCUMULTION TIME object is MISSING\_CONSTANT.  
Also, TIMESTAMP\_WHOLE:TIMESTAMP\_SUB is the end  
of the packet rather than the usual start,  
see TIMESTAMP\_WHOLE object for more details.  
[Only affects data from 2015-089 to 2015-115.]

Bit 15 = Electron Anodes Reversed.  
 Level 2 data only when FSW\_VERSION < 4.10  
 and only electron packets. Electron anodes  
 are reversed in order and need to be  
 remapped, however electron Spin Phase data  
 (LRS data) cannot be remapped. See the SIS  
 document for more information about this.  
 [Affects all electron data 2011 to 2015-115.]

Data very different than expected, may not be suitable  
 for science - use with extreme caution.

Bit 16 = Data is not from flight instrument on Juno,  
 see FLIGHT\_OR\_STL object.

Bit 17 = MCP\_NOT\_AT\_COMMANDED object flagged.  
 Electron HRS/CAL/HVE packets use all three  
 electron sensors and therefore have three  
 MCP\_NOT\_AT\_COMMANDED values per packet.  
 Setting this flag means at least one of those  
 three mcps is not at its commanded value.

Bit 18 = Data includes some JADE-E300 sensor data.  
 (Only flagged for HRS, LRS, CAL and HVE data.)  
 E300 has a high voltage power supply issue  
 and reported energy steps may be incorrect.  
 If E300 is off but still reported in the data  
 product, it may be zeros of fill values.

Bit 19 = Ion packet abruptly truncated.  
 This packet should not be used. It had an  
 ACCUMULATION\_TIME = 1, ACCUM\_TRUNCATION = 1  
 and the DATA object is all zeros, with a  
 timestamp that matches an earlier valid packet  
 that was not truncated and has non-zero DATA.  
 e.g. TOF and LOG example in level 2 data at  
 TIMESTAMP\_WHOLE of 495879710 (UTC 2015-261).

Bit 20 = Currently unused.  
 Bit 21 = Currently unused.  
 Bit 22 = Currently unused.  
 Bit 23 = Currently unused.

Bit 24 = Currently unused.  
 Bit 25 = Currently unused.  
 Bit 26 = Currently unused.  
 Bit 27 = Currently unused.  
 Bit 28 = Currently unused.  
 Bit 29 = Currently unused.  
 Bit 30 = Currently unused.

Bit 31 = Reserved for MISSING\_CONSTANT use.

Each bit has a decimal value of  $2^{\{\text{bit number}\}}$ , and the  
 Issues flag is the sum of  $2^{\{\text{flagged bit numbers}\}}$ .  
 For instance, if this ISSUES flag = 131329, then in  
 binary that value is 0000000000000100000000100000001  
 showing bits 17, 8 and 0 are flagged.

[If a currently unused bit is set, please check the  
 latest LBL file for this product that you can find to  
 see if it now has a definition.]"

OBJECT = BIT\_COLUMN  
 NAME = ISSUES\_BITS  
 BIT\_DATA\_TYPE = BOOLEAN  
 START\_BIT = 1  
 BITS = 32  
 ITEMS = 32



```

        ITEM_BITS      = 1
        MINIMUM        = 0
        MAXIMUM        = 1
        DESCRIPTION    = "See ISSUES column object for description of bits."
    END_OBJECT
    END_OBJECT      = BIT_COLUMN
/* RJW, ISSUES, I, 1, 1 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = MIN_SUBTRACTED_VALUE
DATA_TYPE        = PC_REAL /* i.e. a float in little endian format */
START_BYTE       = 63
BYTES            = 4
VALID_MINIMUM    = 0
VALID_MAXIMUM    = 65535
MISSING_CONSTANT = 4294967295
UNIT             = "COUNTS/VIEW"
DESCRIPTION      = "Minimum Subtracted Value.
                    Minimum value subtracted from every element in
                    the array data blob for transmission to Earth.
                    (This has already been added back to the DATA.)
                    Note: the units are rates (counts per views),
                    are floats rather than integers, and are fractions
                    of 1/512."
/* RJW, MIN_SUBTRACTED_VALUE, f, 1, 1 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = MCP_NOT_AT_COMMANDED
DATA_TYPE        = LSB_UNSIGNED_INTEGER
START_BYTE       = 67
ITEMS            = 1
ITEM_BYTES       = 1
BYTES            = 1
VALID_MINIMUM    = 0
VALID_MAXIMUM    = 1
MISSING_CONSTANT = 255
DESCRIPTION      = "MCP not at Commanded flag. This denotes whether
                    the MCP voltage was reduced during the data collection.
                    0 = Nominal
                    1 = Reduced
                    255 = Unknown"
/* RJW, MCP_NOT_AT_COMMANDED, B, 1, 1 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = SWEEP_TABLE
DATA_TYPE        = LSB_UNSIGNED_INTEGER
START_BYTE       = 68
ITEMS            = 1
ITEM_BYTES       = 1
BYTES            = 1
VALID_MINIMUM    = 0
VALID_MAXIMUM    = 2
MISSING_CONSTANT = 255
DESCRIPTION      = "Which sweep table does the electron sensor have, 0-2.
                    (See PACKETID or ESENSOR object for which sensor.)"
/* RJW, SWEEP_TABLE, B, 1, 1 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = MCP_COMMANDED_VALUE
DATA_TYPE        = LSB_UNSIGNED_INTEGER

```

```

START_BYTE      = 69
ITEMS           = 1
ITEM_BYTES     = 2
BYTES          = 2
VALID_MINIMUM  = 0
VALID_MAXIMUM  = 4095 /* 12-bits */
MISSING_CONSTANT = 65535
DESCRIPTION    = "Electron MCP Commanded raw DAC value.
                  (See PACKETID or ESENSOR object for which sensor.)"
/* RJW, MCP_COMMANDED_VALUE, H, 1, 1 */
END_OBJECT     = COLUMN

/* The following object could be treated as a 1-dimensional column of data, */
/* however we will treat it using PDS containers that allows for 1-, 2-, or */
/* 3-dimensional data. The *.DAT file is the same for both, so we give the */
/* 1-dimension non-container description here (in comments) in case it is */
/* useful to others for comparison. */
/* */
/*OBJECT        = COLUMN */
/* NAME        = DATA */
/* DATA_TYPE  = PC_REAL */
/*            /* i.e. a float in little endian format */
/* START_BYTE  = 71 */
/* ITEMS      = 3072 */
/* ITEM_BYTES = 4 */
/* BYTES     = 12288 */
/* VALID_MINIMUM = 0 */
/* VALID_MAXIMUM = 65535 */
/* MISSING_CONSTANT = 4294967295 */
/* UNIT       = "COUNTS/VIEW" */
/* DESCRIPTION = "DATA: Counts */
/*            64 Energies x 48 Electron Spin Phase Sectors. */
/*            The formula for mapping anodes into spin-phase */
/*            sectors is described in full in the PDS JADE SIS */
/*            and simplifies to: */
/*            */
/*            
$$SP\_sector = ( (s\_phase + s\_id)/7.5 + 7 - a\_id ) \text{ MOD } 48$$

/*            */
/*            where: */
/*            SP_sector (electron spin phase sector) is 0 to */
/*            47 (rounded down to an integer). */
/*            s_phase is spin phase, 0 to 360 degrees. */
/*            s_id is the sensor in question, either 60, 180, */
/*            or 300. */
/*            a_id is one of the 16 anodes of the given sensor, */
/*            0-15. (This is anode, not the look direction.) */
/*            7.5 degrees is the width of one anode. */
/*            */
/*            Note the data units are rates (counts per views), */
/*            are floats rather than integers, and are fractions */
/*            of 1/512. */
/*            Note 2: Rate is independent of accumulation time. */
/*            Note 3: If the data is from FSW 4.00 (April 2015 */
/*            only, when anodes were reversed - see ISSUES */
/*            object) then the SP_sector calculation was done */
/*            incorrectly. If you must use this FSW4.00 data, */
/*            sum over electron spin phase sector to reduce the */
/*            data to energy by time and use that." */
/* Could be, DATA, f, 1, 3072 */
/*END_OBJECT    = COLUMN */
/* */
/* Now follows the 2-dimensional data version using containers: */

```

```

OBJECT          = CONTAINER
  NAME          = DATA_DIM1
  START_BYTE    = 71
  BYTES         = 192 /* = 48 * 4-bytes */
  REPETITIONS   = 64
  DESCRIPTION   = "DATA_DIM1, 2D array of data, 1st and 2nd Dimensions."

```

```

OBJECT          = CONTAINER
  NAME          = DATA_DIM2
  START_BYTE    = 1
  BYTES         = 4
  REPETITIONS   = 48
  DESCRIPTION   = "DATA_DIM2, 1D array of data, 2nd Dimension."

```

```

OBJECT          = COLUMN
  NAME          = DATA
  DATA_TYPE    = PC_REAL /* i.e. a float in little endian format */
  START_BYTE    = 1
  ITEMS         = 1
  ITEM_BYTES    = 4
  BYTES         = 4
  VALID_MINIMUM = 0
  VALID_MAXIMUM = 65535
  MISSING_CONSTANT = 4294967295
  UNIT          = "COUNTS/VIEW"
  DESCRIPTION   = "DATA: Counts

```

```

        64 Energies x 48 Electron Spin Phase Sectors.
        The formula for mapping anodes into spin-phase
        sectors is described in full in the PDS JADE SIS
        and simplifies to:

```

$$SP\_sector = ( (s\_phase + s\_id)/7.5 + 7 - a\_id ) \text{ MOD } 48$$

where:

```

    SP_sector (electron spin phase sector) is 0 to
    47 (rounded down to an integer).
    s_phase is spin phase, 0 to 360 degrees.
    s_id is the sensor in question, either 60, 180,
    or 300.
    a_id is one of the 16 anodes of the given sensor,
    0-15. (This is anode, not the look direction.)
    7.5 degrees is the width of one anode.

```

Note the data units are rates (counts per views), are floats rather than integers, and are fractions of 1/512.

Note 2: Rate is independent of accumulation time.

Note 3: If the data is from FSW 4.00 (April 2015 only, when anodes were reversed - see ISSUES object) then the SP\_sector calculation was done incorrectly. If you must use this FSW4.00 data, sum over electron spin phase sector to reduce the data to energy by time and use that."

```

/* RJW, DATA, f, 2, 64, 48 */
  END_OBJECT    = COLUMN
  END_OBJECT    = CONTAINER
END_OBJECT     = CONTAINER

```

```

OBJECT          = COLUMN
  NAME          = MAG_TIMESTAMP_WHOLE
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 12359
  BYTES         = 4

```

```

VALID_MINIMUM      = 365774402 /* 2011-Aug-05: Juno Launch */
VALID_MAXIMUM      = 599573000 /* ~ 2019-Jan-01          */
MISSING_CONSTANT   = 0
DESCRIPTION        = "MAG_TIMESTAMP_WHOLE
                    Whole-second timestamp of last received MAG vector
                    *before* data collection start.
                    Referenced from 12:00UTC 2000/01/01.
                    [May be affected by a Juno Time Stutter.]"
/* RJW, MAG_TIMESTAMP_WHOLE, I, 1, 1 */
END_OBJECT         = COLUMN

OBJECT             = COLUMN
NAME               = MAG_TIMESTAMP_SUB
DATA_TYPE          = LSB_UNSIGNED_INTEGER
START_BYTE        = 12363
BYTES              = 2
VALID_MINIMUM      = 0
VALID_MAXIMUM      = 65535
MISSING_CONSTANT   = 65535
DESCRIPTION        = "MAG_TIMESTAMP_SUB
                    Sub-second timestamp of last received MAG vector
                    *before* data collection start.
                    A value of 65535 could be real or a MISSING_CONSTANT,
                    however it is MISSING_CONSTANT only if
                    MAG_TIMESTAMP_WHOLE = 0, e.g. WHOLE and SUB must both
                    be real or both be MISSING_CONSTANT.
                    Unit: Microseconds scaled to 16 bits.
                    [May be affected by a Juno Time Stutter.]"
/* RJW, MAG_TIMESTAMP_SUB, H, 1, 1 */
END_OBJECT         = COLUMN

OBJECT             = COLUMN
NAME               = MAG_COUNT_VALID
DATA_TYPE          = LSB_UNSIGNED_INTEGER
START_BYTE        = 12365
BYTES              = 1
VALID_MINIMUM      = 0
VALID_MAXIMUM      = 255
MISSING_CONSTANT   = 255
DESCRIPTION        = "MAG_COUNT_VALID
                    Count of valid (above threshold and not saturated)
                    MAG vectors between start of *previous* packet and
                    start of this packet.
                    Note: This saturates at 255. e.g. if there is a 600s
                    accumulation period, and the MAG vector is given every
                    2-seconds, then that's 300 counts. If all are valid
                    then that 300 will be expressed as 255, however
                    MAG_COUNT_INVALID would still be zero."
/* RJW, MAG_COUNT_VALID, B, 1, 1 */
END_OBJECT         = COLUMN

OBJECT             = COLUMN
NAME               = MAG_COUNT_INVALID
DATA_TYPE          = LSB_UNSIGNED_INTEGER
START_BYTE        = 12366
BYTES              = 1
VALID_MINIMUM      = 0
VALID_MAXIMUM      = 255
MISSING_CONSTANT   = 255
DESCRIPTION        = "MAG_COUNT_INVALID
                    Count of invalid (below threshold or saturated)
                    MAG vectors between start of *previous* packet and
                    start of this packet.

```

Note: This saturates at 255. e.g. if there is a 600s accumulation period, and the MAG vector is given every 2-seconds, then that's 300 counts. If all are invalid then that 300 will be expressed as 255, however MAG\_COUNT\_VALID would still be zero."

```
/* RJW, MAG_COUNT_INVALID, B, 1, 1 */
END_OBJECT      = COLUMN
```

```
OBJECT          = COLUMN
NAME            = MAG_VECTOR
DATA_TYPE       = LSB_INTEGER
START_BYTE      = 12367
ITEMS           = 3
ITEM_BYTES      = 4
BYTES           = 12
VALID_MINIMUM   = -1600000
VALID_MAXIMUM   = 1600000
MISSING_CONSTANT = 2147483647
UNIT            = "nT"
DESCRIPTION     = "Last received MAG vector in nT before
data collection start: 3 components [X, Y, Z]
```

MAG range is +/- 16 G, hence limits.  
The coordinate system is spacecraft based, with:  
+X is between E060 and E300, along the 0 degree mark  
where E060 anode 0 starts  
+Y is 90 degrees, between E060 anodes 11 and 12,  
+Z is the spin axis.  
Note: these are signed integers.

A Mag vector of [0 0 0] has four meanings:  
[Meanings 1 and 2 require MAG\_TIMESTAMP\_WHOLE = 0.  
The MAG\_COUNT\_VALID and MAG\_COUNT\_INVALID objects  
can help distinguish meaning 1 from 2.]

- 1) JADE never received a mag vector at all.  
(So initialized to 0s.)  
e.g. MAG\_COUNT\_VALID = 0 for this record.
- 2) A 25s timeout has expired without JADE receiving a  
MAG vector over a threshold magnitude.  
[Meanings 3 and 4 require MAG\_TIMESTAMP\_WHOLE > 0]
- 3) The threshold parameter was set to 0 nT.  
(Some early HVCO1 check-out data may have this.)
- 4) The broadcast message was corrupted and the  
magnitude and components mismatched."

```
/* RJW, MAG_VECTOR, i, 1, 3 */
END_OBJECT      = COLUMN
```

```
OBJECT          = COLUMN
NAME            = BACKGROUND_COUNTS
DATA_TYPE       = LSB_UNSIGNED_INTEGER
START_BYTE      = 12379
BYTES           = 4
VALID_MINIMUM   = 0
VALID_MAXIMUM   = 4294967294
MISSING_CONSTANT = 4294967295 /* 4-byte limit, rolls over */
UNIT            = "COUNTS"
DESCRIPTION     = "Background counts (NOT a background rate).
The background counter for this record's electron
sensor (see ESENSOR object to know which sensor).
```

This is a total count, not a rate.

This is a 16-bit counter over 64 energies over the

```

        accumulation time (up to 1800 seconds), which means it
        could roll over the 4-byte word. i.e. 4294967296 = 0
        However this is unlikely, and even if so, should be
        obvious from the visible background in object DATA."
/* RJW, BACKGROUND_COUNTS, I, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = ESENSOR
DATA_TYPE       = LSB_UNSIGNED_INTEGER
START_BYTE      = 12383
BYTES           = 2
VALID_MINIMUM   = 060
VALID_MAXIMUM   = 300
MISSING_CONSTANT = 65535
DESCRIPTION      = "ESENSOR - which one of the three electron sensors is
                    this record for. Values can only be 60, 180 or 300
                    for electron sensor E060, E180 or E300 respectively.
                    Note: each sensor also has a different PACKETID."
/* RJW, ESENSOR, H, 1, 1 */
END_OBJECT      = COLUMN
/* FMT file contents end here.                                     */

END_OBJECT = TABLE
END

```

## B.2 Sample LBL file for JAD\_L20\_LRS\_ION\_ANY\_\*

```
PDS_VERSION_ID = PDS3
DATA_SET_ID    = "JNO-J/SW-JAD-2-UNCALIBRATED-V1.0"

/* Input file   : JAD_L20_LRS_ION_ANY_2015090_V01.DAT */
/* File written: 2017/05/04 23:03:56 local time */

STANDARD_DATA_PRODUCT_ID = "JAD_L20_LRS_ION_ANY"
PRODUCT_ID               = "JAD_L20_LRS_ION_ANY_2015090"
PRODUCT_VERSION_ID      = "01"
PRODUCT_TYPE             = "DATA"
PRODUCT_CREATION_TIME    = 2017-125T05:03:56 /* UTC 2017-05-05 */
PROCESSING_LEVEL_ID      = "2"

RECORD_TYPE = FIXED_LENGTH
RECORD_BYTES = 10054
FILE_RECORDS = 6

START_TIME          = 2015-090T00:40:45.004 /* 2015-03-31 */
STOP_TIME           = 2015-090T18:53:01.004 /* 2015-03-31 */
SPACECRAFT_CLOCK_START_COUNT = "481034575.64547" /* WHOLE.SUB (SUB 0-65535)*/
SPACECRAFT_CLOCK_STOP_COUNT  = "481100112.00000" /* Rounded nearest */
/* JADE records have start time SPACECRAFT CLOCK, so to get end time */
/* of last record, I've added the Accumulation time value to both */
/* UTC seconds and SPACECRAFT CLOCK, - although those are not equal. */
/* Hence the SPACECRAFT_CLOCK_STOP_COUNT is rounded for now. */

INSTRUMENT_HOST_NAME = "JUNO"
INSTRUMENT_HOST_ID   = "JNO"
TARGET_NAME          = {"JUPITER"}
INSTRUMENT_NAME      = "JOVIAN AURORAL PLASMA DISTRIBUTIONS EXPERIMENT"
INSTRUMENT_ID        = "JAD" /* JADE */

DESCRIPTION = "This is the required LBL file to accompany DAT files of the
              data product JAD_L20_LRS_ION_ANY."

MD5_CHECKSUM = "ee29f7aab018fdbabeb3f9f13c3fe4d79"

NOTE = "See the PDS JADE SIS Document for more details on the formats."

^TABLE = "JAD_L20_LRS_ION_ANY_2015090_V01.DAT"
OBJECT = TABLE
  INTERCHANGE_FORMAT = "BINARY"
  ROWS                = 6
  COLUMNS            = 25
  ROW_BYTES           = 10054
  DESCRIPTION         = "Describes the structure and content of the data file."

/* FMT file contents start here. */
/* Filename: Version01/JAD_L20_LRS_ION_ANY_V01.FMT */
/* File written: 2017/05/02 15:42:00 */
/* Will code useful Python based letters to describe each object */
/* see http://docs.python.org/library/struct.html for codes */
/* formats will comma separated beginning with "R JW," as key then */
/* {NAME}, {FORMAT}, {Number of dims}, {Size Dim 1}, {Size Dim 2}, ... */
/* where {FORMAT} is the Python code for the type, i.e. I for uint32 */
/* and there are as many Size Dim's as number of dimensions. */
/* Remember to remove the comment markers at either end */

/* RJW, BYTES_PER_RECORD, 10054 */
/* RJW, OBJECTS_PER_RECORD, 25 */
```

```

OBJECT          = COLUMN
  NAME          = SYNC
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 1
  BYTES         = 4
  VALID_MINIMUM = 4210242563
  VALID_MAXIMUM = 4210242563
  MISSING_CONSTANT = 0 /* If no Sync pattern there is no record */
  DESCRIPTION    = "JADE Sync Pattern for IDP packets.
                  Hex value = 0xFAF33403, Decimal = 4210242563"
/* RJW, SYNC, I, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = DPID_COUNT
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 5
  BYTES         = 1
  VALID_MINIMUM = 0
  VALID_MAXIMUM = 255
  DESCRIPTION    = "DPID Count (Source Sequence Count)
                  Count of the number of times this product has been
                  generated since the startup (or reset) of the
                  generating application (Boot Program or Science
                  Program). This count resets to 0 upon entry to
                  the modes of BOOT, LVENG, HVENG, LOW_RATE_SCI,
                  MCP_CAL_SCI, HI_RATE_SCI, LOW_RATE_SCI2,
                  MCP_CAL_SCI2, HI_RATE_SCI2.
                  Note: starts with 0, increments by 1, eventually
                  rolls over at 255."
/* RJW, DPID_COUNT, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = COMPRESSION
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 6
  BYTES         = 1
  VALID_MINIMUM = 0
  VALID_MAXIMUM = 1
  MISSING_CONSTANT = 255
  DESCRIPTION    = "Lossless Compression Status.
                  Indicates whether the data (non-header) segment of
                  the IDP packet (IDP Data) was lossless compressed.
                  0 = Not Compressed
                  1 = Compressed"
/* RJW, COMPRESSION, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = IDPLENGTH
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 7
  BYTES         = 2
  VALID_MINIMUM = 36 /* Depends on onboard compression, if any. */
  VALID_MAXIMUM = 2528
  MISSING_CONSTANT = 65535
  DESCRIPTION    = "IDP Length,
                  Byte Length of the IDP packet.
                  Uncompressed size for this product should be 2528."
/* RJW, IDPLENGTH, H, 1, 1 */
END_OBJECT      = COLUMN

```



```

OBJECT          = COLUMN
  NAME          = PACKETID
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 9
  BYTES         = 1
  VALID_MINIMUM = 1 /* 0x01 - Range covers all JADE packets, */
  VALID_MAXIMUM = 163 /* 0xA3 - Even those not in the PDS. */
  MISSING_CONSTANT = 255
  DESCRIPTION   = "Packet ID (DPID), Data Product Identifier
                  Low Rate Science - Ion Species Histogram
                  Each packet is one of the following ion species:
                    SP0, species 0, PACKETID = 96 /* 0x60 */
                    SP1, species 1, PACKETID = 97 /* 0x61 */
                    SP2, species 2, PACKETID = 98 /* 0x62 */
                    SP3, species 3, PACKETID = 99 /* 0x63 */
                    SP4, species 4, PACKETID = 100 /* 0x64 */
                    SP5, species 5, PACKETID = 101 /* 0x65 */
                    SP6, species 6, PACKETID = 102 /* 0x66 */
                    SP7, species 7, PACKETID = 103 /* 0x67 */"
/* RJW, PACKETID, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = FLIGHT_OR_STL
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 10
  BYTES         = 1
  VALID_MINIMUM = 0
  VALID_MAXIMUM = 2
  MISSING_CONSTANT = 255
  DESCRIPTION   = "In Flight data, or STL (ground EM tests):
                    0 = In flight, from JADE on Juno (via FEI)
                    1 = On ground, from STL tests (via FEI)
                    2 = On ground, from SwRI tests (not FEI)
                    255 = Unknown"
/* RJW, FLIGHT_OR_STL, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = PACKET_MODE
  DATA_TYPE    = LSB_INTEGER
  START_BYTE    = 11
  BYTES         = 1
  VALID_MINIMUM = -2
  VALID_MAXIMUM = 2
  MISSING_CONSTANT = 127
  DESCRIPTION   = "Packet Mode, describes type of data telemetry.
                    -2 = HSK / Housekeeping Engineering
                    -1 = HVE / High Voltage Engineering
                    0 = CAL / MCP Calibration Science
                    1 = LRS / Low Rate Science
                    2 = HRS / High Rate Science
                    127 = Unknown
                    254 = Wrong - but HSK, see below.
                    255 = Wrong - but HVE, see below.
                    (Note, this could also be calculated via PACKETID.)
                    If you have 254 or 255 then your code is incorrect,
                    check you read a signed byte, rather than unsigned."
/* RJW, PACKET_MODE, b, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = PACKET_SPECIES

```

```

DATA_TYPE           = LSB_INTEGER
START_BYTE         = 12
BYTES              = 1
VALID_MINIMUM      = -1
VALID_MAXIMUM      = 9
MISSING_CONSTANT   = 127
DESCRIPTION        = "Packet Species, describes type of plasma data.
                    -1 = electrons
                    0 = ion species 0, SP0
                    1 = ion species 1, SP1
                    2 = ion species 2, SP2
                    3 = ion species 3, SP3
                    4 = ion species 4, SP4
                    5 = ion species 5, SP5
                    6 = ion species 6, SP6
                    7 = ion species 7, SP7
                    8 = Not Used
                    9 = All ions
                    127 = Unknown
                    255 = Wrong - but electrons, see below.
                    If you have 255 then your code is incorrect,
                    check you read a signed byte, rather than unsigned."
/* RJW, PACKET_SPECIES, b, 1, 1 */
END_OBJECT         = COLUMN

OBJECT             = COLUMN
NAME               = TIMESTAMP_WHOLE
DATA_TYPE          = LSB_UNSIGNED_INTEGER
START_BYTE         = 13
BYTES              = 4
VALID_MINIMUM      = 365774402 /* 2011-Aug-05: Juno Launch */
VALID_MAXIMUM      = 599573000 /* ~ 2019-Jan-01 */
MISSING_CONSTANT   = 0
DESCRIPTION        = "Timestamp (Whole Second).
                    Timestamp (whole second) of the data for this packet
                    when collection began (for FSW 4.10 onwards).
                    For FSW 4.00 (April 2015 only) this is the time the
                    collection ended, rather than started, due to the LRS,
                    Ion Species Bug which was fixed in FSW 4.10.
                    This is sometimes referred to as Mission Elapsed Time
                    (MET) and is Referenced from 2000-001T12:00:00.000 UTC,
                    but 1 tick is not exactly 1 S.I. second.
                    See UTC object for corrected converted time.
                    Note: Spacecraft Clock = TIMESTAMP_WHOLE:TIMESTAMP_SUB"
/* RJW, TIMESTAMP_WHOLE, I, 1, 1 */
END_OBJECT         = COLUMN

OBJECT             = COLUMN
NAME               = TIMESTAMP_SUB
DATA_TYPE          = LSB_UNSIGNED_INTEGER
START_BYTE         = 17
BYTES              = 2
VALID_MINIMUM      = 0
VALID_MAXIMUM      = 65535
MISSING_CONSTANT   = 0
DESCRIPTION        = "Timestamp (Subsecond).
                    Timestamp subsecond of the data for this packet
                    when collection began (for FSW 4.10 onwards).
                    For FSW 4.00 (April 2015 only) this is the time the
                    collection ended, rather than started, due to the LRS,
                    Ion Species Bug which was fixed in FSW 4.10.
                    Unit: Microseconds scaled to 16 bits.
                    Note: Spacecraft Clock = TIMESTAMP_WHOLE:TIMESTAMP_SUB"

```

```

/* RJW, TIMESTAMP_SUB, H, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = ACCUMULATION_TIME
DATA_TYPE      = LSB_UNSIGNED_INTEGER
START_BYTE     = 19
BYTES          = 2
VALID_MINIMUM  = 1
VALID_MAXIMUM  = 1800
MISSING_CONSTANT = 65535
UNIT           = "SECONDS"
DESCRIPTION    = "Accumulation Time.
                  Number of seconds over which the data in this product
                  was collected (Science Program).
                  For FSW 4.00 (April 2015 only), Low Rate Science Ion
                  Species data had a bug where the value returned for
                  accumulation time was not relevant, and has been
                  replaced with a MISSING_CONSTANT value on the ground.
                  Use difference between time stamps to estimate
                  accumulation time."

/* RJW, ACCUMULATION_TIME, H, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = TABLES_VERSION
DATA_TYPE      = PC_REAL
START_BYTE     = 21
BYTES          = 4
VALID_MINIMUM  = 0.00
VALID_MAXIMUM  = 99.99
MISSING_CONSTANT = -99.99
DESCRIPTION    = "Look Up Tables (LUT) version used onboard.
                  All tables are combined (compression, sweeping,
                  macros, etc.) onboard in to a large image.
                  This is the image number, or table version.
                  Number should be to 2 decimal places."

/* RJW, TABLES_VERSION, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = FSW_VERSION
DATA_TYPE      = PC_REAL
START_BYTE     = 25
BYTES          = 4
VALID_MINIMUM  = 0.00
VALID_MAXIMUM  = 9.99
MISSING_CONSTANT = -99.99
DESCRIPTION    = "Flight Software version used.
                  Number should be to 2 decimal places."

/* RJW, FSW_VERSION, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = ACCUM_TRUNCATION
DATA_TYPE      = LSB_UNSIGNED_INTEGER
START_BYTE     = 29
BYTES          = 1
VALID_MINIMUM  = 0
VALID_MAXIMUM  = 1
MISSING_CONSTANT = 255
DESCRIPTION    = "Accumulation Truncation,
                  Whether commanded accumulation time ended early.

```

```

                                0 = Nominal
                                1 = Early
                                255 = Unknown"
/* RJW, ACCUM_TRUNCATION, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = DATA_UNITS /* Science Data Units only, not HSK */
DATA_TYPE      = LSB_UNSIGNED_INTEGER
START_BYTE     = 30
BYTES          = 1
VALID_MINIMUM  = 0
VALID_MAXIMUM  = 1
MISSING_CONSTANT = 255
DESCRIPTION    = "Science Data could be total counts (per accumulation)
                  or a rate, normalized to counts per view.
                  0 = All counts in the accumulation period (int)
                  1 = All counts divided by number of views (float)
                  2 = Counts per second (float)
                  255 = Not appropriate for this dataset, or Unknown."
/* RJW, DATA_UNITS, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = COMPRESSION_RATIO
DATA_TYPE      = PC_REAL /* i.e. a float in little endian format */
START_BYTE     = 31
BYTES          = 4
VALID_MINIMUM  = 1
VALID_MAXIMUM  = 10
MISSING_CONSTANT = -1
DESCRIPTION    = "Data compression ratio of data blob when it was
                  transmitted to Earth:
                  Ratio = {Uncompressed size}/{Compressed size}
                  This is the compression due to the lossless
                  scheme, and does not include any lossy compression
                  which may have occurred prior to it, such as the
                  32-bit to 8-bit or 16-bit to 8-bit look up tables
                  that are often used prior to the lossy compression.
                  A value of 1 means there was no lossless data
                  compression, i.e. it was turned off, and object
                  COMPRESSION should equal 1."
/* RJW, COMPRESSION_RATIO, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = UTC
DATA_TYPE      = DATE /* ASCII character string */
START_BYTE     = 35
BYTES          = 21
VALID_MINIMUM  = 2011-217T00:00:00.001
                /* SC Clock 365774402:0, JUNO Launch */
VALID_MAXIMUM  = 20192026-001T00:00:00.000 /* Expect~extended mission end */
MISSING_CONSTANT = 0001-001T00:00:00.000
DESCRIPTION    = "UTC timestamp, of format yyyy-dddTHH:MM:SS.sss
                  where yyyy = year, ddd = day of year,
                  HH = hour, MM = minute,
                  SS.sss = decimal seconds to millisecond resolution.
                  Value calculated via SPICE from spacecraft clock time,
                  {TIMESTAMP WHOLE}:{TIMESTAMP SUB}."
/* RJW, UTC, c, 1, 21 */
END_OBJECT      = COLUMN

```

```

OBJECT          = COLUMN
  NAME          = LEAP SECOND VERSION
  DATA TYPE    = LSB UNSIGNED INTEGER
  START BYTE    = 56
  BYTES         = 1
  VALID MINIMUM = 1
  VALID MAXIMUM = 22 /* Unpredictable, but no more than 2 a year */
  MISSING CONSTANT = 255
  DESCRIPTION   = "The NAIF SPICE kernel for lsk used to generate UTC.
                  The lsk (leap second kernels) files are used in time
                  conversions and have filenames naifnnnn.tls, where
                  is the lsk version number (with leading zeros)."
```

```

/* RJW, LEAP SECOND VERSION, B, 1, 1 */
END OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = SCLKSCET VERSION
  DATA TYPE    = LSB INTEGER
  START BYTE    = 57
  BYTES         = 2
  VALID MINIMUM = -32767
  VALID MAXIMUM = 32767
  MISSING CONSTANT = -32768
  DESCRIPTION   = "The NAIF SPICE kernel for sclk used to generate UTC.
                  The JUNO sclk files are used to convert the spacecraft
                  clock timestamps to UTC time, and all have filenames
                  JNO SCLKSCET.nnnnn.tsc, where nnnnn is the SCLKSCET
                  version number (with leading zeros and positive).
                  Each kernel has a reconstructed and predicted part for
                  it's values, typically any time after the last row of
                  the SCLK01 COEFFICIENTS 61999 table is predicted.
                  If TIMESTAMP WHOLE:TIMESTAMP SUB is in the predicted
                  part then SCLKSCET VERSION will be negative, the
                  absolute value would be the version number. If a later
                  SCLKSCET kernel version is used the UTC time will
                  likely be different.
                  If TIMESTAMP WHOLE:TIMESTAMP SUB is in the
                  reconstructed region the number will be positive
                  (equal to the version number) and will not vary with
                  later kernels.
                  e.g. If SCLKSCET VERSION = -17 then kernel
                  JNO SCLKSCET.00017.tsc was used to convert to UTC, but
                  it's a predicted UTC time.
                  If SCLKSCET VERSION = 18 then kernel
                  JNO SCLKSCET.00018.tsc was used to convert to UTC, and
                  it's a reconstructed UTC time that will not change with
                  later SCLKSCET kernel versions.
                  Within the PDS archive this value should always be
                  positive."
```

```

/* RJW, SCLKSCET VERSION, h, 1, 1 */
END OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = ISSUES
  DATA TYPE    = LSB UNSIGNED INTEGER
  START BYTE    = 59
  BYTES         = 4
  VALID MINIMUM = 0
  VALID MAXIMUM = 4294967294
  MISSING CONSTANT = 4294967295
  DESCRIPTION   = "Issues or potential issues in this data record.
                  These are issues that can be identified within the JADE
                  packet of data itself without any external information."

```

e.g. timing issues due to the MAG time stutter, or any voltage pulsing, would not be included as there are no indicators to them within this JADE packet.

[For a more comprehensive list of potential issues from internal and external sources please see the Level 3 data.]

Level 2 issues of this JADE packet are flagged by individual bits, and several may be hit. If no issues are flagged then this 4-byte unsigned integer is zero. A value of 4294967295 is the MISSING CONSTANT and means that the issue status is currently unknown.

All bits at 0 implies all is okay as seen by this packet. If a bit is set to 1 then that bit is flagged, otherwise it is set to zero and unflagged.

The bits are set as followed, grouped in to seriousness:

Not very serious issues for doing science:

Bit 0 = UTC time is predicted, yet to be finalized.

Bit 1 = Position/Orientation values predicted, yet to be finalized. Level 3 (and above) data only.

Bit 2 = TABLES VERSION object was altered on the ground to accurately reflect a 'commanded parameter update' outside the initial per-orbit commands JADE is returning. [If changed, the original downlinked TABLES VERSION value can be found by cross-referencing the PARAM TABLE VER object in the JAD L20 HSK ALL SHK files. Note here the PARAM TABLE VER value is given as a unsigned integer of Hex Major-Middle-Minor, such that a value of 770 decimal is in hex 0x302, meaning Table Version 3.02 ]

Bit 3 = FSW VERSION 4.00 LRS/CAL Ion Species bug fixed on the ground by adjusting TIMESTAMP WHOLE, TIMESTAMP SUB, and ACCUMULATION TIME based on cross-referencing JADE commanding.

Bit 4 = LRS/CAL Ion Species record with unobserved look directions (views) populated using views from neighboring record. See Bit 12 for uncorrected/unpopulated description. (Only possible if ACCUMULATION TIME = 30.)

Bit 5 = TIMESTAMP WHOLE/SUB adjusted on the ground to mitigate any Juno time stutter affects. [Other TIMESTAMPS are susceptible to the onboard time stutter too, but only the JADE packet TIMESTAMP WHOLE/SUB is tracked here.]

Bit 6 = Currently unused.

Bit 7 = Warning, a leap second occurs during the accumulation period.

Data slightly different than expected, but can be used for science with a little extra coding:

Bit 8 = ACCUM TRUNCATION object flagged.

Bit 9 = Electron (HRS/LRS/CAL) MAG objects are not tracked, are either zeros or MISSING CONSTANT. [LRS and CAL did not have MAG objects prior to FSW VERSION 4.10, therefore those MAG objects here are set to MISSING CONSTANT when FSW VERSION < 4.10.]

```

Bit 10 = TIMESTAMP WHOLE/SUB affected by a Juno
onboard time stutter, JADE reported timestamp
is likely 1 whole tick too large.
[Other TIMESTAMPS are susceptible to the
onboard time stutter too, but only the JADE
packet TIMESTAMP WHOLE/SUB is tracked here.]
Bit 11 = Currently unused.
Bit 12 = LRS/CAL Ion Species record potentially has
unobserved look directions (spin phase sectors
or views) present in the data, meaning the
record may not contain data for a full 4pi
steradians field-of-view.
Unobserved look directions have zero counts
per view (or counts per second) in the data,
although an observed look direction may also
have zero counts if no ions were measured.
Therefore there is a potential confusion over
zero measured counts or simply unmeasured.
e.g. if the spin period is 30.7 seconds, then
not all of the 78 spin phase sectors will be
sampled in 30 seconds. (Unobserved views are
only possible if ACCUMULATION TIME in 2018 */
MISSING_CONSTANT = 0001_001T00:00:00.000
DESCRIPTION = "UTC timestamp, of format yyyy dddTHH:MM:SS.sss
where yyyy = year, ddd = day of year,
HH = hour, MM = minute,
SS.sss = decimal seconds to millisecond resolution.
Value calculated via SPICE from spacecraft clock time,
(TIMESTAMP_WHOLE):(TIMESTAMP_SUB)"
/* RJW, UTC, e, 1, 21 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = LEAP_SECOND_VERSION
DATA_TYPE = LSB_UNSIGNED_INTEGER
START_BYTE = 56
BYTES = 1
VALID_MINIMUM = 1
VALID_MAXIMUM = 22 /* Unpredictable, but no more than 2 a year */
MISSING_CONSTANT = 255
DESCRIPTION = "The NAIF SPICE kernel for lsk used to generate UTC.
The lsk (leap second kernels) files are used in time
conversions and have filenames naifnnnn.tlc, where
is the lsk version number (with leading zeros)."
/* RJW, LEAP_SECOND_VERSION, D, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = SCLKCSET_VERSION
DATA_TYPE = LSB_INTEGER
START_BYTE = 57
BYTES = 2
VALID_MINIMUM = 32767
VALID_MAXIMUM = 32767
MISSING_CONSTANT = 32769
DESCRIPTION = "The NAIF SPICE kernel for selk used to generate UTC.
The JUNO selk files are used to convert the spacecraft
clock timestamps to UTC time, and all have filenames
JNO_SCLKCSET.nnnnn.tsc, where nnnnn is the SCLKCSET
version number (with leading zeros and positive).
Each kernel has a reconstructed and predicted part for
it's values, typically any time after the last row of
the SCLK01_COEFFICIENTS_61999 table is predicted.

```

```

===== If TIMESTAMP_WHOLE:TIMESTAMP_SUB is in the predicted
===== part then SCLKSCET_VERSION will be negative, the
===== absolute value would be the version number. If a later
===== SCLKSCET kernel version is used the UTC time will
===== likely be different.
===== If TIMESTAMP_WHOLE:TIMESTAMP_SUB is in the
===== reconstructed region the number will be positive
===== (equal to the version number) and will not vary with
===== later kernels.
===== e.g. If SCLKSCET_VERSION = 17 then kernel
===== JNO_SCLKSCET.00017.tsc was used to convert to UTC, but
===== it's a predicted UTC time.
===== If SCLKSCET_VERSION = 18 then kernel
===== JNO_SCLKSCET.00018.tsc was used to convert to UTC, and
===== it's a reconstructed UTC time that will not change with
===== later SCLKSCET kernel versions.
===== Within the PDS archive this value should always be
===== positive."
/* RJW, SCLKSCET_VERSION, h, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = ISSUES
DATA_TYPE = LSB_UNSIGNED_INTEGER
START_BYTE = 59
BYTES = 4
VALID_MINIMUM = 0
VALID_MAXIMUM = 4294967294
MISSING_CONSTANT = 4294967295
DESCRIPTION = "Issues or potential issues in this data record.
===== These are issues that can be identified within the JADE
===== packet of data itself without any external information.
===== e.g. timing issues due to the MAG time stutter, or any
===== voltage pulsing, would not be included as there are no
===== indicators to them within this JADE packet.
===== [For a more comprehensive list of potential issues
===== from internal and external sources please see the
===== Level 3 data.]

===== Level 2 issues of this JADE packet are flagged by
===== individual bits, and several may be hit. If no issues
===== are flagged then this 4 byte unsigned integer is zero.
===== A value of 4294967295 is the MISSING_CONSTANT and means
===== that the issue status is currently unknown.

===== All bits at 0 implies all is okay as seen by this
===== packet. If a bit is set to 1 then that bit is flagged,
===== otherwise it is set to zero and unflagged.

===== The bits are set as followed, grouped in to seriousness:

===== Not very serious issues for doing science+
===== Bit 0 = UTC time is predicted, yet to be finalized.
===== Bit 1 = Position/Orientation values predicted, yet to
===== be finalized. Level 3 (and above) data only.
===== Bit 2 = TABLES_VERSION object was altered on the
===== ground to accurately reflect a 'commanded
===== parameter update' outside the initial
===== per orbit commands JADE is returning.
===== [If changed, the original downlinked
===== TABLES_VERSION value can be found by cross
===== referencing the PARAM_TABLE_VER object in the
===== JAD_L20_HSK_ALL_SHK files. Note here the

```



~~PARAM\_TABLE\_VER value is given as a unsigned integer of Hex Major Middle Minor, such that a value of 770 decimal is in hex 0x302, meaning Table Version 3.02.]~~

~~Bit 3 = FSW\_VERSION 4.00 LRS/CAL Ion Species bug fixed on the ground by adjusting TIMESTAMP\_WHOLE, TIMESTAMP\_SUD, and ACCUMULATION\_TIME based on cross referencing JADE commanding.~~

~~Bit 4 = LRS/CAL Ion Species record with unobserved look directions (views) populated using views from neighboring record. See Bit 12 for uncorrected/unpopulated description. (Only possible if ACCUMULATION\_TIME = 30.)~~

~~Bit 5 = TIMESTAMP\_WHOLE/SUD adjusted on the ground to mitigate any June time stutter affects. [Other TIMESTAMPS are susceptible to the onboard time stutter too, but only the JADE packet TIMESTAMP\_WHOLE/SUD is tracked here.]~~

~~Bit 6 = Currently unused.~~

~~Bit 7 = Warning, a leap second occurs during the accumulation period.~~

~~Data slightly different than expected, but can be used for science with a little extra coding.~~

~~Bit 8 = ACCUM\_TRUNCATION object flagged.~~

~~Bit 9 = Electron (HRS/LRS/CAL) MAG objects are not tracked, are either zeros or MISSING\_CONSTANT. [LRS and CAL did not have MAG objects prior to FSW\_VERSION 4.10, therefore those MAG objects here are set to MISSING\_CONSTANT when FSW\_VERSION < 4.10.]~~

~~Bit 10 = TIMESTAMP\_WHOLE/SUD affected by a June onboard time stutter, JADE reported timestamp is likely 1 whole tick too large. [Other TIMESTAMPS are susceptible to the onboard time stutter too, but only the JADE packet TIMESTAMP\_WHOLE/SUD is tracked here.]~~

~~Bit 11 = Currently unused.~~

~~Bit 12 = LRS/CAL Ion Species record potentially has unobserved look directions (spin phase sectors or views) present in the data, meaning the record may not contain data for a full 4pi steradians field of view.~~

~~Unobserved look directions have zero counts per view (or counts per second) in the data, although an observed look direction may also have zero counts if no ions were measured. Therefore there is a potential confusion over zero measured counts or simply unmeasured. e.g. if the spin period is 30.7 seconds, then not all of the 78 spin phase sectors will be sampled in 30 seconds. (Unobserved views are only possible if ACCUMULATION\_TIME <= 30.)~~

~~See the JADE SIS for more information.~~

Bit 13 = At least one anode is blanked.  
See SIS document for further information.

Bit 14 = FSW\_VERSION 4.00 LRS/CAL Ion Species bug warning:

Not fixed as yet - when fixed it will become bit 3 of ISSUES instead.

Level 2 data only when FSW\_VERSION = 4.00, ACCUMULTION\_TIME object is MISSING\_CONSTANT.

Also, `TIMESTAMP_WHOLE:TIMESTAMP_SUB` is the end of the packet rather than the usual start, see `TIMESTAMP_WHOLE` object for more details. [Only affects data from 2015-089 to 2015-115.]

Bit 15 = Electron Anodes Reversed.

Level 2 data only when `FSW_VERSION < 4.10` and only electron packets. Electron anodes are reversed in order and need to be remapped, however electron Spin Phase data (LRS data) cannot be remapped. See the SIS document for more information about this. [Affects all electron data 2011 to 2015-115.]

Data very different than expected, may not be suitable for science - use with extreme caution.

Bit 16 = Data is not from flight instrument on Juno, see `FLIGHT_OR_STL` object.

Bit 17 = `MCP_NOT_AT_COMMAND` object flagged.

Electron HRS/CAL/HVE packets use all three electron sensors and therefore have three `MCP_NOT_AT_COMMAND` values per packet. Setting this flag means at least one of those three mcps is not at its commanded value.

Bit 18 = Data includes some JADE-E300 sensor data. (Only flagged for HRS, LRS, CAL and HVE data.)

E300 has a high voltage power supply issue and reported energy steps may be incorrect. If E300 is off but still reported in the data product, it may be zeros or fill values.

Bit 19 = Ion packet abruptly truncated.

This packet should not be used. It had an `ACCUMULATION_TIME = 1`, `ACCUM_TRUNCATION = 1` and the `DATA` object is all zeros, with a timestamp that matches an earlier valid packet that was not truncated and has non-zero `DATA`. e.g. TOF and LOG example in level 2 data at `TIMESTAMP_WHOLE` of 495879710 (UTC 2015-261).

Bit 20 = Currently unused.

Bit 21 = Currently unused.

Bit 22 = Currently unused.

Bit 23 = Currently unused.

Bit 24 = Currently unused.

Bit 25 = Currently unused.

Bit 26 = Currently unused.

Bit 27 = Currently unused.

Bit 28 = Currently unused.

Bit 29 = Currently unused.

Bit 30 = Currently unused.

Bit 31 = Reserved for `MISSING_CONSTANT` use.

Each bit has a decimal value of  $2^{\{\text{bit number}\}}$ , and the Issues flag is the sum of  $2^{\{\text{flagged bit numbers}\}}$ .

For instance, if this `ISSUES` flag = 131329, then in binary that value is 000000000000001000000000100000001 showing bits 17, 8 and 0 are flagged.

[If a currently unused bit is set, please check the latest LBL file for this product that you can find to see if it now has a definition.]"

OBJECT = `BIT_COLUMN`  
NAME = `ISSUES_BITS`

```

        BIT_DATA_TYPE      = BOOLEAN
        START_BIT         = 1
        BITS              = 32
        ITEMS             = 32
        ITEM_BITS        = 1
        MINIMUM          = 0
        MAXIMUM          = 1
        DESCRIPTION      = "See ISSUES column object for description of bits."
    END_OBJECT          = BIT_COLUMN
/* RJW, ISSUES, I, 1, 1 */
END_OBJECT            = COLUMN

OBJECT                = COLUMN
    NAME                = MIN_SUBTRACTED_VALUE
    DATA_TYPE          = PC_REAL /* i.e. a float in little endian format */
    START_BYTE         = 63
    BYTES               = 4
    VALID_MINIMUM      = 0
    VALID_MAXIMUM      = 65535
    MISSING_CONSTANT   = 4294967295
    UNIT                = "COUNTS/VIEW"
    DESCRIPTION        = "Minimum Subtracted Value.
                          Minimum value subtracted from every element in
                          the array data blob for transmission to Earth.
                          (This has already been added back to the DATA.)
                          Note: the units are rates (counts per views),
                          are floats rather than integers, and are fractions
                          of 1/512."
/* RJW, MIN_SUBTRACTED_VALUE, f, 1, 1 */
END_OBJECT            = COLUMN

OBJECT                = COLUMN
    NAME                = MCP_NOT_AT_COMMANDED
    DATA_TYPE          = LSB_UNSIGNED_INTEGER
    START_BYTE         = 67
    ITEMS              = 1
    ITEM_BYTES         = 1
    BYTES              = 1
    VALID_MINIMUM      = 0
    VALID_MAXIMUM      = 1
    MISSING_CONSTANT   = 255
    DESCRIPTION        = "MCP not at Commanded flag. This denotes whether
                          the MCP voltage was reduced during the data collection.
                          0 = Nominal
                          1 = Reduced
                          255 = Unknown"
/* RJW, MCP_NOT_AT_COMMANDED, B, 1, 1 */
END_OBJECT            = COLUMN

OBJECT                = COLUMN
    NAME                = SWEEP_TABLE
    DATA_TYPE          = LSB_UNSIGNED_INTEGER
    START_BYTE         = 68
    ITEMS              = 1
    ITEM_BYTES         = 1
    BYTES              = 1
    VALID_MINIMUM      = 0
    VALID_MAXIMUM      = 3
    MISSING_CONSTANT   = 255
    DESCRIPTION        = "Which sweep table does the ion sensor have, 0-3."
/* RJW, SWEEP_TABLE, B, 1, 1 */
END_OBJECT            = COLUMN

```

```

OBJECT          = COLUMN
  NAME          = MCP_COMMANDED_VALUE
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 69
  ITEMS         = 1
  ITEM_BYTES    = 2
  BYTES         = 2
  VALID_MINIMUM = 0
  VALID_MAXIMUM = 4095 /* 12-bits */
  MISSING_CONSTANT = 65535
  DESCRIPTION   = "Ion MCPs Commanded raw DAC value."
/* RJW, MCP_COMMANDED_VALUE, H, 1, 1 */
END_OBJECT     = COLUMN

/* The following object could be treated as a 1-dimensional column of data, */
/* however we will treat it using PDS containers that allows for 1-, 2-, or */
/* 3-dimensional data. The *.DAT file is the same for both, so we give the */
/* 1-dimension non-container description here (in comments) in case it is */
/* useful to others for comparison. */
/* */
/*OBJECT          = COLUMN */
/* NAME          = DATA */
/* DATA_TYPE    = PC_REAL */
/* i.e. a float in little endian format */
/* START_BYTE    = 71 */
/* ITEMS         = 2496 */
/* ITEM_BYTES    = 4 */
/* BYTES         = 9984 */
/* VALID_MINIMUM = 0 */
/* VALID_MAXIMUM = 65535 */
/* MISSING_CONSTANT = 4294967295 */
/* UNIT          = "COUNTS/VIEW" */
/* DESCRIPTION   = "DATA: Counts per view */
/*               32 Energies x 78 Ion Spin Phase Sectors */
/*               The formula for mapping anodes into spin-phase */
/*               sectors is described in the PDS JADE SIS */
/*               and as follows: */
/*               */
/*               Each Spin Phase Sector has contributions from */
/*               multiple spin phases, but always the same anode. */
/*               The spin phase is calculated from the start of */
/*               the record. */
/*               Only anodes 4-11 are used, 0-3 are not reported. */
/*               There are 78 Spin Phase sectors [0-77] over the */
/*               eight anodes and thirty 12-degree wide sectors, */
/*               with spin phase sectors given in the following */
/*               table of anode by start spin phase: */
/*               */
/*               Ion Start | Ion Anode */
/*               Spin Phase | ----- */
/*               (Degrees) | 4  5  6  7  8  9 10 11*/
/*               ----- */
/*               195-207   0  3  9 24 39 54 69 75*/
/*               207-219   0  3  9 24 39 54 69 75*/
/*               219-231   0  3 10 25 40 55 69 75*/
/*               231-243   0  3 10 25 40 55 69 75*/
/*               243-255   0  3 11 26 41 56 70 75*/
/*               255-267   0  3 11 26 41 56 70 75*/
/*               267-279   0  4 12 27 42 57 70 75*/
/*               279-291   0  4 12 27 42 57 70 75*/
/*               291-303   0  4 13 28 43 58 70 75*/
/*               303-315   0  4 13 28 43 58 70 75*/
/*               315-327   1  5 14 29 44 59 71 76*/

```

```

/*          327-339          1   5   14   29   44   59   71   76*/
/*          339-351          1   5   15   30   45   60   71   76*/
/*          351-003          1   5   15   30   45   60   71   76*/
/*          003-015          1   5   16   31   46   61   72   76*/
/*          015-027          1   5   16   31   46   61   72   76*/
/*          027-039          1   6   17   32   47   62   72   76*/
/*          039-051          1   6   17   32   47   62   72   76*/
/*          051-063          1   6   18   33   48   63   72   76*/
/*          063-075          1   6   18   33   48   63   72   76*/
/*          075-087          2   7   19   34   49   64   73   77*/
/*          087-099          2   7   19   34   49   64   73   77*/
/*          099-111          2   7   20   35   50   65   73   77*/
/*          111-123          2   7   20   35   50   65   73   77*/
/*          123-135          2   7   21   36   51   66   74   77*/
/*          135-147          2   7   21   36   51   66   74   77*/
/*          147-159          2   8   22   37   52   67   74   77*/
/*          159-171          2   8   22   37   52   67   74   77*/
/*          171-183          2   8   23   38   53   68   74   77*/
/*          183-195          2   8   23   38   53   68   74   77*/
/*          -----*/
/*
/*          [The onboard software triggers on the spin phase of*/
/*          the s/c +X axis, but JADE-I is 195 degrees further */
/*          around, so the Ion Start Spin Phase starts at 195.]*/
/*
/*          The meaning of each species is described in */
/*          the JADE instrument paper. */
/*          Note the data units are rates (counts per views), */
/*          are floats rather than integers, and are fractions */
/*          of 1/512. */
/*          Note 2: Rate is independent of accumulation time." */
/* Could be, DATA, f, 1, 2496 */
/*END_OBJECT          = COLUMN */
/*
/* Now follows the 2-dimensional data version using containers: */

OBJECT              = CONTAINER
NAME                = DATA_DIM1
START_BYTE         = 71
BYTES              = 312 /* = 78 * 4-bytes */
REPETITIONS        = 32
DESCRIPTION        = "DATA_DIM1, 2D array of data, 1st and 2nd Dimensions."

OBJECT              = CONTAINER
NAME                = DATA_DIM2
START_BYTE         = 1
BYTES              = 4
REPETITIONS        = 78
DESCRIPTION        = "DATA_DIM2, 1D array of data, 2nd Dimension."

OBJECT              = COLUMN
NAME                = DATA
DATA_TYPE          = PC_REAL /* i.e. a float in little endian format */
START_BYTE         = 1
ITEMS              = 1
ITEM_BYTES         = 4
BYTES              = 4
VALID_MINIMUM      = 0
VALID_MAXIMUM      = 65535
MISSING_CONSTANT   = 4294967295
UNIT                = "COUNTS/VIEW"
DESCRIPTION        = "DATA: Counts per view
                    32 Energies x 78 Ion Spin Phase Sectors

```

The formula for mapping anodes into spin-phase sectors is described in the PDS JADE SIS and as follows:

Each Spin Phase Sector has contributions from multiple spin phases, but always the same anode.

The spin phase is calculated from the start of the record.

Only anodes 4-11 are used, 0-3 are not reported.

There are 78 Spin Phase sectors [0-77] over the eight anodes and thirty 12-degree wide sectors, with spin phase sectors given in the following table of anode by start spin phase:

Ion Start Spin Phase (Degrees)	Ion Anode							
	4	5	6	7	8	9	10	11
195-207	0	3	9	24	39	54	69	75
207-219	0	3	9	24	39	54	69	75
219-231	0	3	10	25	40	55	69	75
231-243	0	3	10	25	40	55	69	75
243-255	0	3	11	26	41	56	70	75
255-267	0	3	11	26	41	56	70	75
267-279	0	4	12	27	42	57	70	75
279-291	0	4	12	27	42	57	70	75
291-303	0	4	13	28	43	58	70	75
303-315	0	4	13	28	43	58	70	75
315-327	1	5	14	29	44	59	71	76
327-339	1	5	14	29	44	59	71	76
339-351	1	5	15	30	45	60	71	76
351-003	1	5	15	30	45	60	71	76
003-015	1	5	16	31	46	61	72	76
015-027	1	5	16	31	46	61	72	76
027-039	1	6	17	32	47	62	72	76
039-051	1	6	17	32	47	62	72	76
051-063	1	6	18	33	48	63	72	76
063-075	1	6	18	33	48	63	72	76
075-087	2	7	19	34	49	64	73	77
087-099	2	7	19	34	49	64	73	77
099-111	2	7	20	35	50	65	73	77
111-123	2	7	20	35	50	65	73	77
123-135	2	7	21	36	51	66	74	77
135-147	2	7	21	36	51	66	74	77
147-159	2	8	22	37	52	67	74	77
159-171	2	8	22	37	52	67	74	77
171-183	2	8	23	38	53	68	74	77
183-195	2	8	23	38	53	68	74	77

[The onboard software triggers on the spin phase of the s/c +X axis, but JADE-I is 195 degrees further around, so the Ion Start Spin Phase starts at 195.]

The meaning of each species is described in the JADE instrument paper.

Note the data units are rates (counts per views), are floats rather than integers, and are fractions of 1/512.

Note 2: Rate is independent of accumulation time."

```
/* RJW, DATA, f, 2, 32, 78 */
  END_OBJECT      = COLUMN
  END_OBJECT      = CONTAINER
```

```
END_OBJECT          = CONTAINER
/* FMT file contents end here.
```

```
*/
```

```
END_OBJECT = TABLE
END
```

## Appendix C Level 2 data record formats

This section describes the format of the Level 2 data files.

While Section 6.2.8 (“Level 2 data files”) cover this to some level, the real description is within the FMT files for each product, which themselves are embedded within the LBL files.

For details of the (very long) FMT files, please refer to the previous section (Appendix B) about label files, and the FMT files are quoted in full between these two lines within those examples:

```
/* FMT file contents start here.                               */
                                                                [FMT file in here]
/* FMT file contents end here.                                 */
```



## Appendix D Level 3 data record formats

This section describes the format of the Level 3 data files.

While Section 6.2.9 (“Level 3 data files”) cover this to some level, the real description is within the FMT files for each product. Here are two examples in full, but see the FMT files in the LABEL directory for specifics.

Font below is Courier New (to equally space characters) and size 9 in order to get 78 characters to a line. This matches the PDS files that are 80 characters to a line, but the last two are `\r\n`.

### D.1 Sample FMT file for JAD\_L30\_HRS\_ELC\_ALLTWO\_CNT\_V02V04.FMT

```
/* Filename: Version02Version04/JAD_L30_HRS_ELC_ALLTWO_CNT_V02V04.FMT
*/
/* File written: 2021/10/22 16:29:57 */
/* Will code useful Python based letters to describe each object */
/* see http://docs.python.org/library/struct.html for codes */
/* formats will comma separated beginning with "R JW," as key then */
/* {NAME}, {FORMAT}, {Number of dims}, {Size Dim 1}, {Size Dim 2}, ... */
/* where {FORMAT} is the Python code for the type, i.e. I for uint32 */
/* and there are as many Size Dim's as number of dimensions. */
/* Remember to remove the comment markers at either end */

/* R JW, BYTES PER RECORD, 2018/01/24 14:08:2357670 */
/*
/* Will code useful Python based letters to describe each object */
/* see http://docs.python.org/library/struct.html for codes */
/* formats will comma separated beginning with "R JW," as key then */
/* {NAME}, {FORMAT}, {Number of dims}, {Size Dim 1}, {Size Dim 2}, ... */
/* where {FORMAT} is the Python code for the type, i.e. I for uint32 */
/* and there are as many Size Dim's as number of dimensions. */
/* Remember to remove the comment markers at either end */
*/

/* R JW, BYTES PER RECORD, 160042 */
/* R JW, OBJECTS PER RECORD, 4852 */

OBJECT          = COLUMN
NAME            = DIM0.UTC
DATA TYPE      = DATE /* ASCII character string */
START_BYTE     = 1
BYTES          = 21
VALID_MINIMUM  = 2011-217T00:00:00.001
                /* SC Clock 365774402:0, JUNO Launch */
VALID_MAXIMUM  = 20192026-001T00:00:00.000 /* Expect mission end in 20182025 */
MISSING_CONSTANT = 0001-001T00:00:00.000
DESCRIPTION    = "UTC timestamp at center (not start) of record.
                  Format is yyyy-dddTHH:MM:SS.sss
                  where yyyy = year, ddd = day of year,
                  HH = hour, MM = minute,
                  SS.sss = decimal seconds to millisecond resolution.
                  Note: Duration of record can be found in S.I. seconds
                  by DIM0.UTC UPPER - DIM0.UTC LOWER. Do not confuse
                  this with the ACCUMULATION_TIME object, which is the
                  number of spacecraft clock ticks for accumulation.
                  While 1 tick is approximately 1 second, it is not
                  identical."
```

```

/* RJW, DIM0.UTC, c, 1, 21 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = PACKETID
DATA_TYPE       = LSB_UNSIGNED_INTEGER
START_BYTE      = 22
BYTES           = 1
VALID_MINIMUM   = 142 /* (0x8E) */
VALID_MAXIMUM   = 142 /* (0x8E) */
MISSING_CONSTANT = 255 /* Unknown, or a mix of packets */
DESCRIPTION     = "Packet ID (DPID), Data Product Identifier
                  High Rate Science - Electron
                  All 3Two Electron sensors per record: E060r and E180r.
                  (This is the same data as for JAD L30 HRS ELC ALL
                  but with E300r data removed for a smaller file.)
                  PACKETID = 142 (0x8E)"

/* RJW, PACKETID, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = DIM0.UTC_UPPER
DATA_TYPE       = DATE /* ASCII character string */
START_BYTE      = 23
BYTES           = 21
VALID_MINIMUM   = 2011-217T00:00:00.001
VALID_MAXIMUM   = 20192026-001T00:00:00.000
MISSING_CONSTANT = 0001-001T00:00:00.000
DESCRIPTION     = "0th Dimension of DATA: Time - upper limit.
                  See DIM0.UTC for description."

/* RJW, DIM0.UTC_UPPER, c, 1, 21 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = PACKET_MODE
DATA_TYPE       = LSB_INTEGER
START_BYTE      = 44
BYTES           = 1
VALID_MINIMUM   = 2
VALID_MAXIMUM   = 2
MISSING_CONSTANT = 127
DESCRIPTION     = "Packet Mode, describes type of data telemetry.
                  -2 = HSK / Housekeeping Engineering (Level 2 only)
                  -1 = HVE / High Voltage Engineering (Level 2 only)
                  0 = CAL / MCP Calibration Science (Level 2 only)
                  1 = LRS / Low Rate Science
                  2 = HRS / High Rate Science
                  3 = DRS / DeRived Science from LRS and/or HRS
                  127 = Unknown
                  254 = Wrong - but HSK, see below. (Level 2 only)
                  255 = Wrong - but HVE, see below. (Level 2 only)
                  (Note, this could also be calculated via PACKETID.)
                  If you have 254 or 255 then your code is incorrect,
                  check you read a signed byte, rather than unsigned."

/* RJW, PACKET_MODE, b, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = DIM0.UTC_LOWER
DATA_TYPE       = DATE /* ASCII character string */
START_BYTE      = 45
BYTES           = 21
VALID_MINIMUM   = 2011-217T00:00:00.001

```

```

VALID_MAXIMUM      = 20192026-001T00:00:00.000
MISSING_CONSTANT   = 0001-001T00:00:00.000
DESCRIPTION        = "0th Dimension of DATA: Time - lower limit.
                    See DIM0.UTC for description."
/* RJW, DIM0.UTC_LOWER, c, 1, 21 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = PACKET_SPECIES
DATA_TYPE        = LSB_INTEGER
START_BYTE       = 66
BYTES            = 1
VALID_MINIMUM    = -1
VALID_MAXIMUM    = -1
MISSING_CONSTANT = 127
DESCRIPTION      = "Packet Species, describes type of plasma data.
                    -1 = electrons
                     0 = ion species 0, SP0
                     1 = ion species 1, SP1
                     2 = ion species 2, SP2
                     3 = ion species 3, SP3
                     4 = ion species 4, SP4
                     5 = ion species 5, SP5
                     6 = ion species 6, SP6
                     7 = ion species 7, SP7
                     8 = Sum of SP3, SP4 and SP5
                     9 = All ions /* or any ion, e.g., TOF and LOG */
                    10 = Single ion species derived from TOF data
                    127 = Unknown
                    255 = Wrong - but electrons, see below.
                    If you have 255 then your code is incorrect,
                    check you read a signed byte, rather than unsigned."
/* RJW, PACKET_SPECIES, b, 1, 1 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = ACCUMULATION_TIME
DATA_TYPE        = LSB_UNSIGNED_INTEGER
START_BYTE       = 67
BYTES            = 2
VALID_MINIMUM    = 1
VALID_MAXIMUM    = 1
MISSING_CONSTANT = 65535
UNIT             = "SECONDS" /* Not S.I. Seconds, but SCLK ticks */
DESCRIPTION      = "Accumulation Time.
                    Number of seconds over which the data in this product
                    was collected (Science Program).
                    Note: Duration of record can be found in S.I. seconds
                    by DIM0.UTC_UPPER - DIM0.UTC_LOWER. Do not confuse
                    this with the ACCUMULATION_TIME object, which is the
                    number of spacecraft clock ticks for accumulation.
                    While 1 tick is approximately 1 second, it is not
                    identical.
                    ACCUMULATION_TIME is left in spacecraft clock ticks to
                    both aid matching with the level 2 data and to help
                    filtering for data taken in a particular mode."
/* RJW, ACCUMULATION_TIME, H, 1, 1 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = DATA_UNITS
DATA_TYPE        = LSB_UNSIGNED_INTEGER
START_BYTE       = 69

```

```

BYTES          = 1
VALID_MINIMUM  = 2
VALID_MAXIMUM  = 2
MISSING_CONSTANT = 255
DESCRIPTION    = "Data units correspond to:
                  0 = All counts in the accumulation period
                  1 = All counts divided by number of views
                  2 = Counts per second
                    /* S.I. science units: */
                  3 = Differential Energy Flux [1/( m^2 sr s   )]
                  4 = Differential Number Flux [1/( m^2 sr s   J)]
                  5 = Phase Space Density    [  m^-6 s^3   ]
                    /* Convenient (non-S.I.) science units: */
                  6 = Differential Energy Flux [1/(cm^2 sr s   )]
                  7 = Differential Number Flux [1/(cm^2 sr s keV)]
                  8 = Phase Space Density    [  cm^-6 s^3   ]
                /* As new products are developed this list will increase */
                /* If a number is not listed, */
                /* try a LBL/FMT file from a recent date. */
                255 = Unknown."
/* RJW, DATA_UNITS, B, 1, 1 */
END_OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = SOURCE_BACKGROUND
DATA_TYPE     = LSB_UNSIGNED_INTEGER
START_BYTE    = 70
BYTES         = 1
VALID_MINIMUM = 0
VALID_MAXIMUM = 1
MISSING_CONSTANT = 255
DESCRIPTION   = "Source of Background values (see BACKGROUND object)
                that have been removed from the DATA object.
                0 = None: No background has been removed
                1 = Background anode (electron sensors only)
                /* As new background removal methods are developed this list will increase */
                255 = Unknown."
/* RJW, SOURCE_BACKGROUND, B, 1, 1 */
END_OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = SOURCE_DEAD_TIME
DATA_TYPE     = LSB_UNSIGNED_INTEGER
START_BYTE    =
MISSING_CONSTANT = 255
DESCRIPTION   = "Source of Background values (see BACKGROUND object)
                that have been removed from the DATA object.
                0 = None: No background has been removed
                1 = Background anode (electron sensors only)
                2 = Background anode (JADE-I only)
                3 = Derived from Background anode : Method 1:
                    Background coefficients are time independent.
                    See file in CALIB directory for description.
                4 = Derived from Background anode : Method 2:
                    Background coefficients are per orbit.
                    See file in CALIB directory for description.
                /* As new background removal methods are developed this list will increase */
                255 = Unknown."
/* RJW, SOURCE_BACKGROUND, B, 1, 1 */
END_OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = SPARE_ZEROS

```

```

DATA_TYPE      = LSB UNSIGNED INTEGER
START_BYTE     = 71
BYTES          = 1
VALID_MINIMUM  = 0
VALID_MAXIMUM  = 0
MISSING_CONSTANT = 255
DESCRIPTION    = "Source of Dead Time Correction Method Spare Zeroes. Always
zero.
           0 = None: Data has not been Dead Time corrected. PDS3 format
required a padding byte, e.g., a 4-byte
           255 = Unknown." integer/float will
always start on the 1st or 5th
           or 9th or 13th... byte of the record."
*/ RJW, SOURCE_DEAD_TIMESPARE ZEROS, B, 1, 1 */
END_OBJECT     = COLUMN

```

```

OBJECT        = COLUMN
NAME          = SOURCE_MAG
DATA_TYPE     = LSB_UNSIGNED_INTEGER
START_BYTE    = 72
BYTES        = 1
VALID_MINIMUM = 0
VALID_MAXIMUM = 39
MISSING_CONSTANT = 255
DESCRIPTION   = "Source of MAG data
Except case 0 and 1, PAYLOAD (pl) co-ordinate MAG files
were used at 1s (or 2s if no 1s) resolution.
0 = None: No MAG data in this product.
1 = From Juno JADE's Level 2 files.
   (From spacecraft and therefore uncalibrated.)
   This is independent to JADE Level 2 version
   number as it does not change with versions.
   [Note MAG data in JADE files may be affected
   by the Juno time stutter.]
3n = Juno's MAG's Level 3 version n calibrated
files, e.g., 34 means version 4, so:
30 = From Juno MAG's Level 3 version 00 quicklook
payload files.
   (These are temporary files not in PDS.)
31 = From Juno MAG's Level 3 version 01 calibrated
payload files.
32 = From Juno MAG's Level 3 version 02 calibrated
payload files.
30 = From Juno MAG's Level 3 version 00 quicklook
payload files.
   (These are temporary files not in PDS.)
31 = From Juno MAG's Level 3 version 01 calibrated
payload files.
32 = From Juno MAG's Level 3 version 02 calibrated
payload files.
Likewise, 33 to 39 being Level 3 version 3 to 9.
255 = Unknown.

```

```

           If you see a number not listed above, there may be
           later versions of MAG data - find the latest
           available LBL file for this product and see what that
           has listed."

```

```

/* RJW, SOURCE_MAG, B, 1, 1 */
END_OBJECT     = COLUMN

OBJECT        = COLUMN
NAME          = SOURCE_JADE_METAKERNEL

```

```

DATA_TYPE          = LSB_INTEGER
START_BYTE        = 73
BYTES             = 2
VALID_MINIMUM     = -32767
VALID_MAXIMUM     = 32767
MISSING_CONSTANT  = -32768
DESCRIPTION       = "The JADE SPICE metakernel used to get the time,
                    position, velocity, orientation and transformation
                    objects in this file.  The metakernel lists the
                    many individual spice kernels used, which are
                    archived by NAIF and not in this PDS volume.
                    The JADE SPICE metakernel may be found in the CALIB
                    directory of this PDS volume, with filenames of:
                        JAD_L30_SPICE_METAKERNEL_nnnnn.TXT
                    where nnnnn is the SOURCE_JADE_METAKERNEL object
                    number (with leading zeros and positive).
                    If any of the kernels within the metakernel are not
                    reconstructed (but reference or predicted) for the
                    time in question, this value will be negative.
                    Within the JADE PDS archive this value should always
                    be positive."

/* RJW, SOURCE_JADE_METAKERNEL, h, 1, 1 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = SOURCE_JADE_CALIB
DATA_TYPE        = LSB_INTEGER
START_BYTE       = 75
BYTES            = 2
VALID_MINIMUM    = -32767 0
VALID_MAXIMUM    = 32767
MISSING_CONSTANT = -32768
DESCRIPTION      = "The JADE calibration files list used to convert the
                    engineering units of Level 2 data to the scientific
                    units in this file.  Similar to the SPICE metakernel
                    list, this lists the many individual calibration files
                    used, each of which may be found in the CALIB
                    directory on this PDS volume.

                    This list may be found in the CALIB directory of this
                    PDS volume, with filenames of:
                        JAD_L30_CALIB_LIST_nnnnn.TXT
                    where nnnnn is the SOURCE_JADE_CALIB object
                    number (with leading zeros and positive).
                    If any of the calibration files listed are not final
                    at the time in question, this value will be negative.
                    (Newer calibration files will have a higher version and
                    simply be listed in a newer SOURCE_JADE_CALIB file.)
                    Within the JADE PDS archive this value should always
                    be positive. However, a version 00 file (for team use
                    or uploaded to JSOC, not PDS) may have negative values
                    with predicted positions/orientations/transformations."

/* RJW, SOURCE_JADE_CALIB, h, 1, 1 */
END_OBJECT          = COLUMN

OBJECT              = COLUMN
NAME                = FSW_VERSION
DATA_TYPE           = PC_REAL
START_BYTE          = 77
BYTES               = 4
VALID_MINIMUM       = 0.00
VALID_MAXIMUM       = 9.99
MISSING_CONSTANT    = -99.99

```

```

DESCRIPTION      = "Flight Software version used.
                  Number should be to 2 decimal places, with rounding.
                  e.g., 4.00, 4.10, 4.20. i.e., 4.1999998 means 4.20."
/* RJW, FSW_VERSION, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME           = LUT_VERSION
DATA_TYPE      = PC_REAL
START_BYTE     = 81
BYTES         = 4
VALID_MINIMUM  = -a version 00 file (for team use
                  or uploaded to JSOC, not PDS) may have negative values
                  with predicted positions/orientations/transformations.

                  /* Rob Note: ensure this file says which version of
                  Level 2 JADE files were used to make this L3 file. */"
/* RJW, SOURCE_JADE_CALIB, h, 1, 1 */0.00
VALID_MAXIMUM  = 9.99
MISSING_CONSTANT = -99.99
DESCRIPTION    = "LUT (Look Up Table) Version
END_OBJECT    = COLUMN

OBJECT        = COLUMN
NAME         = FSW_VERSION
DATA_TYPE    = PC_REAL
START_BYTE   = 77
BYTES       = 4
VALID_MINIMUM = 0.00
VALID_MAXIMUM = 9.99
MISSING_CONSTANT = -99.99
DESCRIPTION  = "Flight Software version used. on JADE.
                  Number should be to 2 decimal places, with rounding.
                  e.g., 4.00, 4.10, 4.20." . i.e.,
                  4.1999998 means 4.20."
/* RJW, FSWLUT_VERSION, f, 1, 1 */
END_OBJECT   = COLUMN

OBJECT      = COLUMN
NAME       = LUT_VERSION_SUB_LETTER
DATA_TYPE  = CHARACTER
START_BYTE = 85
BYTES     = 2
FORMAT    = "A2"
DESCRIPTION = "The letter (if any) associated with the energy table
                  used at the time of this record
                  -- -> No sub letter for this LUT Version
                  -A -> Sub letter is A for this LUT Version
                  -B -> Sub letter is B for this LUT Version
                  -C -> Sub letter is C for this LUT Version
                  etc.
                  For instance, the energy table files are in the CALIB
                  directory of this PDS volume, with names like:
                  LUT 4 00 ENERGY V01.CSV
                  (LUT_VERSION 4.00, no sub letter)
                  or
                  LUT 5 01 K ENERGY V01.CSV
                  (LUT_VERSION 5.01, sub letter K)."
/* RJW, LUT_VERSION_SUB_LETTER, c, 1, 2 */
END_OBJECT = COLUMN

OBJECT      = COLUMN
NAME       = LUT_SWEEP_TABLE

```

```

DATA TYPE      = LSB UNSIGNED INTEGER
START BYTE    = 87
BYTES         = 1
VALID MINIMUM = 1
VALID MAXIMUM = 23
MISSING CONSTANT = 255
DESCRIPTION   = "The sweep tables the ion sensor used.
                A level 2 packet will report this as 0-3,
                However, it requires 2 packets (a ping and a pong)
                to make a level 3 record: either 0 and 1, or 2 and 3.
                Therefore, a value of 1 (= 01) means sweep tables
                0 and 1 were used, while a value of 23 means sweep
                tables 2 and 3 were used.
                This object can only have the value of 1 or 23."
/* RJW, LUT SWEEP_TABLE, B, 1, 1 */
END OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = FILE_VERSION
DATA TYPE    = LSB UNSIGNED INTEGER
START BYTE   = 88
BYTES        = 1
VALID MINIMUM = 0
VALID MAXIMUM = 4
MISSING CONSTANT = 255
DESCRIPTION  = "The version number of the file this record came from.
                e.g., if you loaded file
                JAD L30 LRS ION ANY CNT 2016240 V04.DAT
                then FILE_VERSION = 4.
                [FILE_VERSION = 0 is never in the PDS, but is used by
                the JADE team prior to having required calibrations.]"
/* RJW, FILE_VERSION, B, 1, 1 */
END OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = SC_POS_R
DATA TYPE    = PC_REAL
START BYTE   = 89
DATA TYPE = PC_REAL
START BYTE = 81
BYTES        = 4
VALID MINIMUM = 0.000
VALID MAXIMUM = 140130.000 /* Excluding Cruise to Jupiter */
MISSING CONSTANT = 65535.000
UNIT         = "Jupiter Radii"
DESCRIPTION  = "Juno radial distance, can refine later */
MISSING_CONSTANT = 65535.000
UNIT = "Jupiter Radii"
DESCRIPTION = "Juno radial distance at time DIM0 UTC, from Jupiter.
                Jupiter, in units of Jupiter Radii (Rj).
                (1 Rj = 71492.0 km)
                [Values may be greater than VALID_MAXIMUM
                during cruise to Jupiter before primary mission.]"
/* RJW, SC_POS_R, f, 1, 1 */
END OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = SC_POS_R_UPPER
DATA TYPE = PC_REAL
START BYTE = 85
BYTES = 4
VALID_MINIMUM = 0.000
VALID_MAXIMUM = 140.000 /* Excluding Cruise, can refine later */

```



```

MISSING_CONSTANT = 65535.000
UNIT = "Jupiter Radii"
DESCRIPTION = "Juno radial distance from Jupiter - upper limit.
See SC_POS_R for description."
/* RJW, SC_POS_R_UPPER, f, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_POS_R_LOWER
DATA_TYPE = PC_REAL
START_BYTE = 89
BYTES = 4
VALID_MINIMUM = 0.000
VALID_MAXIMUM = 140.000 /* Excluding Cruise, can refine later */
MISSING_CONSTANT = 65535.000
UNIT = "Jupiter Radii"
DESCRIPTION = "Juno radial distance from Jupiter - lower limit.
See SC_POS_R for description."
/* RJW, SC_POS_R_LOWER, f, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_POS_LAT
DATA_TYPE = PC_REAL
START_BYTE = 93
BYTES = 4
VALID_MINIMUM = 90 0.000
VALID_MAXIMUM = 90130.000
MISSING_CONSTANT = 65535.000
UNIT = "Degrees"
DESCRIPTION = "Juno Latitude above/* Excluding Cruise to Jupiter */
MISSING_CONSTANT = 65535.000
UNIT = "Jupiter Radii"
DESCRIPTION = "Juno radial distance -
(at time DIM0 UTC UPPER, from
Jupiter, in units of Jupiter Radii (Rj).
(1 Rj = 71492.0 Equatorial)"
km)
SC_POS R UPPER could be smaller or larger than
SC POS R, depending if moving inbound or outbound.
[Values may be greater than VALID MAXIMUM
during cruise to Jupiter before primary mission.]"
/* RJW, SC_POS_LATR_UPPER, f, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_POS_LAT_UPPER LOWER
DATA_TYPE = PC_REAL
START_BYTE = 97
BYTES = 4
VALID_MINIMUM = 0.000
VALID_MAXIMUM = 130.000 /* Excluding Cruise to Jupiter */
MISSING_CONSTANT = 65535.000
UNIT = "90.000
VALID_MAXIMUM = 90.000
MISSING_CONSTANT = 65535.000
UNIT = "Degrees"
DESCRIPTION = "Juno Latitude above Jupiter - upper limit.Radii"
See DESCRIPTION = "Juno radial distance at time
DIM0 UTC LOWER, from
Jupiter, in units of Jupiter Radii (Rj).
(1 Rj = 71492.0 km)

```

```

SC_POS_LAT for description."-----R LOWER could be
smaller or larger than
SC POS R, depending if moving inbound or outbound.
[Values may be greater than VALID MAXIMUM
during cruise to Jupiter before primary mission.]"
/* RJW, SC_POS_LAT_UPPER LOWER, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = SC_POS_LAT      LOWER
DATA_TYPE       = PC_REAL
START_BYTE      = 101
BYTES           = 4
VALID_MINIMUM   = -90.000
VALID_MAXIMUM   = 90.000
MISSING_CONSTANT = 65535.000
UNIT            = "Degrees"
DESCRIPTION     = "Juno Latitude above Jupiter lower limit. at time DIM0 UTC, in
both the
See SC_POS_LAT for description."IAU JUPITER and JUNO JSS
frames, in units of degrees.
(0 = Equatorial)
(JUNO JSS is a despun version of IAU JUPITER, hence
they have identical latitudes.)"
/* RJW, SC_POS_LAT_LOWER, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = SC_POS_LAT_UPPER
DATA_TYPE       = PC_REAL
LOCAL_TIME
DATA_TYPE       = PC_REAL
START_BYTE      = 105
BYTES           = 4
VALID_MINIMUM   = -90.000
VALID_MAXIMUM   = 90.000
MISSING_CONSTANT = 65535.000
UNIT            = "Degrees"
DESCRIPTION     = "Juno Latitude 0.000
VALID_MAXIMUM   = 24.000
MISSING_CONSTANT = 65535.000
UNIT            = "Hours"
DESCRIPTION     = "Juno Local Time from Jupiter.
00 = Midnight
06 = Dawn
12 = Noon
18 = Dusk"-----at time DIM0 UTC UPPER, in both
the
IAU JUPITER and JUNO JSS frames, in units of degrees.
(0 = Equatorial)
SC POS LAT UPPER could be smaller or larger than
SC POS LAT.
(JUNO JSS is a despun version of IAU JUPITER, hence
they have identical latitudes.)"
/* RJW, SC_POS_LOCAL_TIME_LAT_UPPER, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = SC_POS_LOCAL_TIME_UPPER_LAT_LOWER
DATA_TYPE       = PC_REAL
START_BYTE      = 109
BYTES           = 4
VALID_MINIMUM   = 0-90.000

```

```

VALID_MAXIMUM      = 2490.000
MISSING_CONSTANT   = 65535.000
UNIT               = "Hours" "Degrees"
DESCRIPTION        = "Juno Local Time from Jupiter - upper limit. Latitude at
time DIM0 UTC LOWER, in both the
                    See IAU JUPITER and JUNO_JSS frames, in units of degrees.
                    (0 = Equatorial)
                    SC_POS_LOCAL_TIME for description. LAT LOWER could be smaller
or larger than
                    SC POS LAT.
                    (JUNO_JSS is a despun version of IAU JUPITER, hence
                    they have identical latitudes.)"
/* RJW, SC_POS_LOCAL_TIME_UPPERLAT_LOWER, f, 1, 1 */
END_OBJECT         = COLUMN

```

```

OBJECT             = COLUMN
NAME               = SC_POS_LOCAL_TIME
DATA_TYPE          = PC_REAL
START_BYTE         = 113
BYTES              = 4
VALID_MINIMUM      = 0.000
VALID_MAXIMUM      = 24.000
MISSING_CONSTANT   = 65535.000
UNIT               = "Hours"
DESCRIPTION        = "Juno's (jovian) Local Time at time DIM0 UTC,
                    in units of hours.
                    00 = Midnight
                    06 = Dawn
                    12 = Noon
                    18 = Dusk"
/* RJW, SC POS LOCAL TIME, f, 1, 1 */
END_OBJECT         = COLUMN

```

```

OBJECT             = COLUMN
NAME               = SC_POS_LOCAL_TIME_LOWER
DATA_TYPE          = PC_REAL
START_BYTE         = 113UPPER
DATA_TYPE          = PC_REAL
START_BYTE         = 117
BYTES              = 4
VALID_MINIMUM      = 0.000
VALID_MAXIMUM      = 24.000
MISSING_CONSTANT   = 65535.000
UNIT               = "Hours"
DESCRIPTION        = "Juno's (jovian) Local Time at time DIM0 UTC UPPER,
                    in units of hours.
                    00 = Midnight
                    06 = Dawn
                    12 = Noon
                    18 = Dusk"
/* RJW, SC POS LOCAL TIME UPPER, f, 1, 1 */
END_OBJECT         = COLUMN

```

```

OBJECT             = COLUMN
NAME               = SC_POS_LOCAL_TIME_LOWER
DATA_TYPE          = PC_REAL
START_BYTE         = 121
BYTES              = 4
VALID_MINIMUM      = 0.000
VALID_MAXIMUM      = 24.000
MISSING_CONSTANT   = 65535.000
UNIT               = "Hours"

```

```

DESCRIPTION      = "JuneJuno's (jovian) Local Time from Jupiter - lower limit.
at time DIM0 UTC LOWER,
                  See SC_POS_LOCAL_TIME for description.in units of hours.
                  00 = Midnight
                  06 = Dawn
                  12 = Noon
                  18 = Dusk"
/* RJW, SC_POS_LOCAL_TIME_LOWER, f, 1, 1 */
END_OBJECT       = COLUMN

OBJECT           = COLUMN
NAME             = SC_POS_SYSIII_ELONG
DATA_TYPE       = PC_REAL
START_BYTE      = 125
BYTES           = 4
VALID_MINIMUM   = 0.000
VALID_MAXIMUM   = 360.000
MISSING_CONSTANT = 65535.000
UNIT            = "Degrees"
DESCRIPTION      = "Juno's (jovian) SYSIII (East) Longitude at time
                  DIM0 UTC, in units of degrees."
/* RJW, SC POS SYSIII ELONG, f, 1, 1 */
END_OBJECT       = COLUMN

OBJECT           = COLUMN
NAME             = SC POS SYSIII_ELONG_UPPER
DATA_TYPE       = PC_REAL
START_BYTE      = 129
BYTES           = 4
VALID_MINIMUM   = 0.000
VALID_MAXIMUM   = 360.000
MISSING_CONSTANT = 65535.000
UNIT            = "Degrees"
DESCRIPTION      = "Juno's (jovian) SYSIII (East) Longitude at time
                  DIM0 UTC UPPER, in units of degrees."
/* RJW, SC POS SYSIII ELONG UPPER, f, 1, 1 */
END_OBJECT       = COLUMN

OBJECT           = COLUMN
NAME             = SC POS SYSIII_ELONG_LOWER
DATA_TYPE       = PC_REAL
START_BYTE      = 133
BYTES           = 4
VALID_MINIMUM   = 0.000
VALID_MAXIMUM   = 360.000
MISSING_CONSTANT = 65535.000
UNIT            = "Degrees"
DESCRIPTION      = "Juno's (jovian) SYSIII (East) Longitude at time
                  DIM0 UTC LOWER, in units of degrees."
/* RJW, SC POS SYSIII ELONG LOWER, f, 1, 1 */
END_OBJECT       = COLUMN

OBJECT           = COLUMN
NAME             = SC POS JUPITER_J2000XYZ
DATA_TYPE       = PC_REAL
START_BYTE      =
DATA_TYPE       = PC_REAL
START_BYTE      = 117
137
ITEMS           = 3
ITEM_BYTES      = 4
BYTES           = 12
VALID_MINIMUM   = -10008880.0 /* ~ -140 Rj */

```

```

VALID_MAXIMUM      = 10008880.0 /* ~ +140 Rj */
MISSING_CONSTANT   = 65535.0 /* ~ +0.917 Rj */
UNIT               = "km"
DESCRIPTION        = "Juno position from Jupiter in J2000 Cartesian
                    co-ordinates [x,y,z] (units km).
                    [Values may be outside of VALID_MIN/MAX range (~140Rj)
                    during cruise to Jupiter before primary mission.]"
/* RJW, SC_POS_JUPITER_J2000XYZ, f, 1, 3 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = SC_VEL_JUPITER_J2000XYZ
DATA_TYPE       = PC_REAL
START_BYTE     = 129
DATA_TYPE        = PC_REAL
START_BYTE       = 149
ITEMS            = 3
ITEM_BYTES       = 4
BYTES            = 12
VALID_MINIMUM    = -70.0
refine with V_mag during JOI */
VALID_MAXIMUM    = 70.0
MISSING_CONSTANT = 65535.0
UNIT             = "km/s"
DESCRIPTION      = "Juno Velocity with respect to Jupiter in J2000
                    Cartesian co-ordinates [Vx,Vy,Vz] (units km/s)."  

/* RJW, SC_VEL_JUPITER_J2000XYZ, f, 1, 3 */
END_OBJECT       = COLUMN

OBJECT          = COLUMN
NAME            = SC_VEL_ANGULAR_J2000XYZ
DATA_TYPE      = PC_REAL
START_BYTE     = 161
ITEMS          = 3
ITEM_BYTES     = 4
BYTES          = 12
VALID_MINIMUM  = -1.0 /* General limit */
VALID_MAXIMUM  = 1.0 /* General limit */
MISSING_CONSTANT = 65535.0
UNIT           = "radians/s"
DESCRIPTION    = "Juno Angular Velocity in Cartesian co-ordinates
                    [AVx,AVy,AVz] (units radians/s).
                    (This is calculated with the SPICE ckgpav command
                    where ref=J2000. SPICE defines it as 'This is the
                    axis about which the reference frame tied to the
                    instrument is rotating in the right-handed sense.')"
/* RJW, SC_VEL_ANGULAR_J2000XYZ, f, 1, 3 */
END_OBJECT     = COLUMN

OBJECT          = COLUMN
NAME            = SC_SPIN_PERIOD
DATA_TYPE      = PC_REAL
START_BYTE     = /* Need to refine with V_mag during JOI */
MISSING_CONSTANT = 65535.0
UNIT           = "km/s"
DESCRIPTION    = "Juno Velocity with respect to Jupiter in J2000
                    Cartesian co-ordinates [Vx,Vy,Vz] (units km/s)."
/* RJW, SC_VEL_JUPITER_J2000XYZ, f, 1, 3 */
END_OBJECT     = COLUMN

OBJECT          = COLUMN
NAME            = SC_VEL_ANGULAR_J2000XYZ
DATA_TYPE      = PC_REAL

```

```

START_BYTE = 141
ITEMS = 3
ITEM_BYTES = 4
BYTES = 12
VALID_MINIMUM = 1.0 /* General limit */
VALID_MAXIMUM = 1.0 /* General limit */
MISSING_CONSTANT = 65535.0
UNIT = "radians/s"
DESCRIPTION = "Juno Angular Velocity in Cartesian co ordinates
[AVx,AVy,AVz] (units radians/s).
(This is calculated with the SPICE ckgpav command
where ref=J2000. SPICE defines it as 'This is the
axis about which the reference frame tied to the
instrument is rotating in the right handed sense.')"
/* RJW, SC_VEL_ANGULAR J2000XYZ, f, 1, 3 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_SPIN_PERIOD
DATA_TYPE = PC_REAL
START_BYTE = 153173
BYTES = 4
VALID_MINIMUM = 0.0
VALID_MAXIMUM = 100 70.0
MISSING_CONSTANT = 65535.0
UNIT = "SECONDS"
DESCRIPTION = "Juno spin period (seconds).
This is not useful during spacecraft maneuvers."
/* RJW, SC_SPIN_PERIOD, f, 1, 1 */
END_OBJECT = COLUMN

OBJECT = /* May want to refine later */COLUMN
NAME = SC_SPIN_PHASE
DATA_TYPE = PC_REAL
START_BYTE = 177
BYTES = 4
VALID_MINIMUM = 0.000
VALID_MAXIMUM = 360.000
MISSING_CONSTANT = 65535.0-000
UNIT = "SECONDSDegrees"
DESCRIPTION = "JunoJuno's spin period (seconds). phase at time
DIM0 UTC,
This is not useful during spacecraft maneuvers."in units of
degrees."
/* RJW, SC_SPIN_PERIODPHASE, f, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_SPIN_PHASE_UPPER
DATA_TYPE = PC_REAL
START_BYTE = 181
BYTES = 4
VALID_MINIMUM = 0.000
VALID_MAXIMUM = 360.000
MISSING_CONSTANT = 65535.000
UNIT = "Degrees"
DESCRIPTION = "Juno's spin phase at time DIM0 UTC UPPER,
in units of degrees."
/* RJW, SC_SPIN_PHASE_UPPER, f, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_SPIN_PHASE_LOWER

```

```

DATA TYPE      = PC_REAL
START_BYTE     = 185
BYTES          = 4
VALID_MINIMUM  = 0.000
VALID_MAXIMUM  = 360.000
MISSING_CONSTANT = 65535.000
UNIT           = "Degrees"
DESCRIPTION    = "Juno's spin phase at time DIM0 UTC LOWER,
                  in units of degrees."
/* RJW, SC SPIN PHASE LOWER, f, 1, 1 */
END_OBJECT     = COLUMN

```

```

OBJECT        = CONTAINER
NAME          = DESPUN_SC_TO_J2000_DIM1
START_BYTE    = 189
BYTES         = 12 /* = 3 * 4-bytes */
REPETITIONS   = 3
DESCRIPTION    = "DESPUN SC TO J2000 DIM1,
                  2D array of data, 1st and 2nd Dimensions."

```

```

OBJECT        = CONTAINER
NAME          = DESPUN_SC_TO_J2000_DIM2
START_BYTE    = 1
BYTES         = 4
REPETITIONS   = 3
DESCRIPTION    = "DESPUN SC TO J2000 DIM2,
                  1D array of data, 2nd Dimension."

```

```

OBJECT        = COLUMN
NAME          = DESPUN_SC_TO_J2000
DATA_TYPE     = PC_REAL
START_BYTE    = 1
ITEMS         = 1
ITEM_BYTES    = 4
BYTES         = 4
VALID_MINIMUM = -1.0
VALID_MAXIMUM = 1.0
MISSING_CONSTANT = 65535.0
DESCRIPTION    = "Rotation matrix from despun spacecraft
                  co-ordinates to J2000.
                  This is a 3x3 matrix, but if read in as a 1x9
                  stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                  and the 2D matrix would be [a,b,c
                  d,e,f
                  g,h,i]"
/* RJW, DESPUN SC TO J2000, f, 2, 3, 3 */
END_OBJECT     = COLUMN
END_OBJECT     = CONTAINER
END_OBJECT     = CONTAINER

```

```

OBJECT        = CONTAINER
NAME          = J2000_TO_JSSXYZ_DIM1
START_BYTE    = 225
BYTES         = 12 /* = 3 * 4-bytes */
REPETITIONS   = 3
DESCRIPTION    = "J2000 TO JSSXYZ DIM1,
                  2D array of data, 1st and 2nd Dimensions."

```

```

OBJECT        = CONTAINER
NAME          = J2000_TO_JSSXYZ_DIM2
START_BYTE    = 1
BYTES         = 4
REPETITIONS   = 3

```

```

DESCRIPTION          = "J2000 TO JSSXYZ DIM2,
                        1D array of data, 2nd Dimension."

OBJECT               = COLUMN
NAME                 = J2000 TO JSSXYZ
DATA TYPE            = PC_REAL
START BYTE           = 1
ITEMS                 = 1
ITEM BYTES           = 4
BYTES                 = 4
VALID MINIMUM        = -1.0
VALID MAXIMUM        = 1.0
MISSING CONSTANT     = 65535.0
DESCRIPTION          = "Rotation matrix from J2000 co-ordinates to JSS xyz
                        (JSS = Jupiter-De-Spun-Sun, see SIS for details).
                        This is a 3x3 matrix, but if read in as a 1x9
                        stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                        and the 2D matrix would be [a,b,c
                                                    d,e,f
                                                    g,h,i]"
/* RJW, J2000 TO JSSXYZ, f, 2, 3, 3 */
END OBJECT           = COLUMN
END OBJECT           = CONTAINER
END OBJECT           = CONTAINER

OBJECT               = CONTAINER
NAME                 = J2000 TO JSSRTP DIM1
START BYTE           = 261
BYTES                 = 12 /* = 3 * 4-bytes */
REPETITIONS          = 3
DESCRIPTION          = "J2000 TO JSSRTP DIM1,
                        2D array of data, 1st and 2nd Dimensions."

OBJECT               = CONTAINER
NAME                 = J2000 TO JSSRTP DIM2
START BYTE           = 1
BYTES                 = 4
REPETITIONS          = 3
DESCRIPTION          = "J2000 TO JSSRTP DIM2,
                        1D array of data, 2nd Dimension."

OBJECT               = COLUMN
NAME                 = J2000 TO JSSRTP
DATA TYPE            = PC_REAL
START BYTE           = 1
ITEMS                 = 1
ITEM BYTES           = 4
BYTES                 = 4
VALID MINIMUM        = -1.0
VALID MAXIMUM        = 1.0
MISSING CONSTANT     = 65535.0
DESCRIPTION          = "Rotation matrix from J2000 co-ordinates to
                        JSS RTP, where RTP is Jupiter centered right
                        handed R-Theta-Phi.
                        (JSS = Jupiter-De-Spun-Sun, see SIS for details.)
                        This is a 3x3 matrix, but if read in as a 1x9
                        stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                        and the 2D matrix would be [a,b,c
                                                    d,e,f
                                                    g,h,i]"
/* RJW, J2000 TO JSSRTP, f, 2, 3, 3 */
END OBJECT           = COLUMN
END OBJECT           = CONTAINER

```



```

END_OBJECT          = CONTAINER

OBJECT              = COLUMN
NAME                = MCP_VOLTAGE
DATA_TYPE           = PC_REAL
START_BYTE         = 157
BYTES              = 12 /* = 3 * 4 bytes */
REPETITIONS        = 3
DESCRIPTION         = "DESPUN_SC_TO_J2000_DIM1,
                    2D array of data, 1st and 2nd Dimensions."

OBJECT              = CONTAINER
NAME                = DESPUN_SC_TO_J2000_DIM2
START_BYTE         = 1
BYTES              = 4
REPETITIONS        = 3
DESCRIPTION         = "DESPUN_SC_TO_J2000_DIM2,
                    1D array of data, 2nd Dimension."

OBJECT              = COLUMN
NAME                = DESPUN_SC_TO_J2000
DATA_TYPE           = PC_REAL
START_BYTE         = 1
ITEMS              = 1
ITEM_BYTES         = 4
BYTES              = 4
VALID_MINIMUM      = -1.0
VALID_MAXIMUM      = 1.0
MISSING_CONSTANT   = 65535.0
DESCRIPTION         = "Rotation matrix from despun spacecraft
                    co-ordinates to J2000.
                    This is a 3x3 matrix, but if read in as a 1x9
                    stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                    and the 2D matrix would be [a,b,e
                                                d,e,f
                                                g,h,i]"

/* RJW, DESPUN_SC_TO_J2000, f, 2, 3, 3 */
END_OBJECT          = COLUMN
END_OBJECT          = CONTAINER
END_OBJECT          = CONTAINER

OBJECT              = CONTAINER
NAME                = J2000_TO_JSSXYZ_DIM1
START_BYTE         = 193
BYTES              = 12 /* = 3 * 4 bytes */
REPETITIONS        = 3
DESCRIPTION         = "J2000_TO_JSSXYZ_DIM1,
                    2D array of data, 1st and 2nd Dimensions."

OBJECT              = CONTAINER
NAME                = J2000_TO_JSSXYZ_DIM2
START_BYTE         = 1
BYTES              = 4
REPETITIONS        = 3
DESCRIPTION         = "J2000_TO_JSSXYZ_DIM2,
                    1D array of data, 2nd Dimension."

OBJECT              = COLUMN
NAME                = J2000_TO_JSSXYZ
DATA_TYPE           = PC_REAL
START_BYTE         = 1
ITEMS              = 1
ITEM_BYTES         = 4

```

```

----- BYTES ----- = 4
----- VALID_MINIMUM ----- = 1.0
----- VALID_MAXIMUM ----- = 1.0
----- MISSING_CONSTANT ----- = 65535.0
----- DESCRIPTION ----- = "Rotation matrix from J2000 co-ordinates to JSS xyz
                               (JSS = Jupiter De Spun Sun, see SIS for details).
                               This is a 3x3 matrix, but if read in as a 1x9
                               stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                               and the 2D matrix would be [a,b,e
                               d,e,f
                               g,h,i]"

/* RJW, J2000_TO_JSSXYZ, f, 2, 3, 3 */
----- END_OBJECT ----- = COLUMN
----- END_OBJECT ----- = CONTAINER
END_OBJECT ----- = CONTAINER

OBJECT ----- = CONTAINER
----- NAME ----- = J2000_TO_JSSRTP_DIM1
----- START_BYTE ----- = 229
----- BYTES ----- = 12 /* = 3 * 4 bytes */
----- REPETITIONS ----- = 3
----- DESCRIPTION ----- = "J2000_TO_JSSRTP_DIM1,
                               2D array of data, 1st and 2nd Dimensions."

----- OBJECT ----- = CONTAINER
----- NAME ----- = J2000_TO_JSSRTP_DIM2
----- START_BYTE ----- = 1
----- BYTES ----- = 4
----- REPETITIONS ----- = 3
----- DESCRIPTION ----- = "J2000_TO_JSSRTP_DIM2,
                               1D array of data, 2nd Dimension."

----- OBJECT ----- = COLUMN
----- NAME ----- = J2000_TO_JSSRTP
----- DATA_TYPE ----- = PC_REAL
----- START_BYTE ----- = 1
----- ITEMS ----- = 1
----- ITEM_BYTES ----- = 4
----- BYTES ----- = 4
----- VALID_MINIMUM ----- = 1.0
----- VALID_MAXIMUM ----- = 1.0
----- MISSING_CONSTANT ----- = 65535.0
----- DESCRIPTION ----- = "Rotation matrix from J2000 co-ordinates to
                               JSS RTP, where RTP is Jupiter centered right
                               handed R-Theta-Phi.
                               (JSS = Jupiter De Spun Sun, see SIS for details.)
                               This is a 3x3 matrix, but if read in as a 1x9
                               stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                               and the 2D matrix would be [a,b,e
                               d,e,f
                               g,h,i]"

/* RJW, J2000_TO_JSSRTP, f, 2, 3, 3 */
----- END_OBJECT ----- = COLUMN
----- END_OBJECT ----- = CONTAINER
END_OBJECT ----- = CONTAINER

OBJECT ----- = COLUMN
----- NAME ----- = MCP_VOLTAGE
----- DATA_TYPE ----- = PC_REAL
----- START_BYTE ----- = 265297
----- ITEMS ----- = 32
----- ITEM_BYTES ----- = 4
----- BYTES ----- = 128

```

```

VALID_MINIMUM      = -50004000.000          /* Will need
to refine these limits */
VALID_MAXIMUM      = 50004000.000          /* Will need
to refine these limits */
MISSING_CONSTANT   = 65535.000
UNIT               = "Volts"
DESCRIPTION        = "MCP Voltages on the threetwo electron sensors, in this
product, E0607, and E180 and E300 respectively."
/* RJW, MCP_VOLTAGE, f, 1, 2 */
END_OBJECT         = COLUMN

```

```

OBJECT             = CONTAINER
NAME               = ISSUES_CONTAINER
START_BYTE        = 3 /* 305
END_OBJECT         = COLUMN

```

```

OBJECT             = CONTAINER
NAME               = ISSUES_CONTAINER
START_BYTE        = 277
BYTES              = 4
REPETITIONS       = 1
DESCRIPTION        = "ISSUES_CONTAINER, size 1."
OBJECT            = COLUMN
NAME               = ISSUES
DATA_TYPE          = LSB_UNSIGNED_INTEGER
START_BYTE        = 1
ITEMS              = 1
ITEM_BYTES        = 4
BYTES              = 4
VALID_MINIMUM     = 0
VALID_MAXIMUM     = 4294967294
MISSING_CONSTANT  = 4294967295
DESCRIPTION        = "Issues or potential issues in this data record.

```

These are issues that can be identified within the JADE packet of data itself without any external information. e.g. timing issues due to the MAG time stutter, or any voltage pulsing, would not be included as there are no indicators to them within this JADE packet.

[For a more comprehensive list of potential issues from internal and external sources please see the Level 3 data.]

Level 2 issues of this JADE packet are flagged by individual bits, and several may be hit. If no issues are flagged then this 4-byte unsigned integer is zero. A value of 4294967295 is the MISSING\_CONSTANT and means that the issue status is currently unknown.

All bits at 0 implies all is okay as seen by this packet. If a bit is set to 1 then that bit is flagged, otherwise it is set to zero and unflagged.

The bits are set as followed, grouped in to seriousness:

Not very serious issues for doing science:

- Bit 0 = UTC time is predicted, yet to be finalized.
- Bit 1 = Position/Orientation values predicted, yet to be finalized. Level 3 (and above) data only.
- Bit 2 = TABLES\_VERSION object was altered on the ground to accurately reflect a 'commanded parameter update' outside the initial per-orbit commands JADE is returning.  
[If changed, the original downlinked

TABLES\_VERSION value can be found by cross-referencing the PARAM\_TABLE\_VER object in the JAD\_L20\_HSK\_ALL\_SHK files. Note here the PARAM\_TABLE\_VER value is given as a unsigned integer of Hex Major-Middle-Minor, such that a value of 770 decimal is in hex 0x302, meaning Table Version 3.02 ]

- Bit 3 = FSW\_VERSION 4.00 LRS/CAL Ion Species bug fixed on the ground by adjusting TIMESTAMP\_WHOLE, TIMESTAMP\_SUB, and ACCUMULATION\_TIME based on cross-referencing JADE commanding.
- Bit 4 = LRS/CAL Ion Species record with unobserved look directions (views) populated using views from neighboring record. See Bit 12 for uncorrected/unpopulated description.  
(Only possible if ACCUMULATION\_TIME = 30.)
- Bit 5 = TIMESTAMP\_WHOLE/SUB adjusted on the ground to mitigate any Juno time stutter affects. [Other TIMESTAMPS are susceptible to the onboard time stutter too, but only the JADE packet TIMESTAMP\_WHOLE/SUB is tracked here.]
- Bit 6 = Currently unused.
- Bit 7 = Warning, a leap second occurs during the accumulation period.

Data slightly different than expected, but can be used for science with a little extra coding:

- Bit 8 = ACCUM\_TRUNCATION object flagged.
- Bit 9 = Electron (HRS/LRS/CAL) MAG objects are not tracked, are either zeros or MISSING\_CONSTANT. [LRS and CAL did not have MAG objects prior to FSW\_VERSION 4.10, therefore those MAG objects here are set to MISSING\_CONSTANT when FSW\_VERSION < 4.10.]
- Bit 10 = TIMESTAMP\_WHOLE/SUB affected by a Juno onboard time stutter, JADE reported timestamp is likely 1 whole tick too large. [Other TIMESTAMPS are susceptible to the onboard time stutter too, but only the JADE packet TIMESTAMP\_WHOLE/SUB is tracked here.]
- Bit 11 = Currently unused.
- Bit 12 = LRS/CAL Ion Species record potentially has unobserved look directions (spin phase sectors or views) present in the data, meaning the record may not contain data for a full 4pi steradians field-of-view. Unobserved look directions have zero counts per view (or counts per second) in the data, although an observed look direction may also have zero counts if no ions were measured. Therefore there is a potential confusion over zero measured counts or simply unmeasured. e.g. if the spin period is 30.7 seconds, then not all of the 78 spin phase sectors will be sampled in 30 seconds. (Unobserved views are only possible if ACCUMULATION\_TIME <= 30.) See the JADE SIS for more information.
- Bit 13 = At least one anode is blanked. See SIS document for further information.
- Bit 14 = FSW\_VERSION 4.00 LRS/CAL Ion Species bug warning:  
Not fixed as yet - when fixed it will

become bit 3 of ISSUES instead.

Level 2 data only when FSW\_VERSION = 4.00, ACCUMULTION\_TIME object is MISSING CONSTANT. Also, TIMESTAMP\_WHOLE:TIMESTAMP\_SUB is the end of the packet rather than the usual start, see TIMESTAMP\_WHOLE object for more details. [Only affects data from 2015-089 to 2015-115.]

Bit 15 = Electron Anodes Reversed.

Level 2 data only when FSW\_VERSION < 4.10 and only electron packets. Electron anodes are reversed in order and need to be remapped, however electron Spin Phase data (LRS data) cannot be remapped. See the SIS document for more information about this. [Affects all electron data 2011 to 2015-115.]

Data very different than expected, may not be suitable for science - use with extreme caution.

Bit 16 = Data is not from flight instrument on Juno, see FLIGHT\_OR\_STL object.

Bit 17 = MCP\_NOT\_AT\_COMMANDED object flagged.

Electron HRS/CAL/HVE packets use all three electron sensors and therefore have three MCP\_NOT\_AT\_COMMANDED values per packet. Setting this flag means at least one of those three mcps is not at its commanded value.

Bit 18 = Data includes some JADE-E300 sensor data. (Only flagged for HRS, LRS, CAL and HVE data.)

E300 has a high voltage power supply issue and reported energy steps may be incorrect. If E300 is off but still reported in the data product, it may be zeros or fill values.

Bit 19 = Ion packet abruptly truncated.

This packet should not be used. It had an ACCUMULATION\_TIME = 1, ACCUM\_TRUNCATION = 1 and the DATA object is all zeros, with a timestamp that matches an earlier valid packet that was not truncated and has non-zero DATA. e.g. TOF and LOG example in level 2 data at TIMESTAMP\_WHOLE of 495879710 (UTC 2015-261).

Bit 20 = MCP Dipping Triggered, in one or more sensors.

If the sensor measures excessive counts, it temporarily lowers the MCP voltage to reduce the number of counts and protect the sensor. The MCP\_NOT\_AT\_COMMANDED object is also flagged (Bit 17 in ISSUES) since the MCP is no longer at the commanded voltage.

For HRS/CAL/HVE electrons (datasets where multiple sensors are on) it is possible that one sensor has been dipped, but the others are not and still providing good data.

(First MCP dip was HRS electrons, 2017-350.)

Bit 21 = MCP Dipped sensor's DATA set to fill values.

If MCP dipping has triggered (Bit 20 of ISSUES) then: DATA and BACKGROUND objects (and their \*\_SIGMAS) have been replaced with MISSING\_CONSTANT values.

(Never used for Level 2 data, which has the counts as measured in the dipped state.)

In addition, Bit 17 of the ISSUES object (i.e. MCP\_NOT\_AT\_COMMANDED object = 1) is set to zero, and, if it exists, the MCP\_NOT\_AT\_COMMANDED object itself is changed

(from 1) to be 0 for the offending sensor(s).

If the DATA object contains data from multiple sensors (HRS/CAL/HVE electrons) then only the elements of the DATA object for the dipped sensor are set to MISSING\_CONSTANT (as identified by the MCP\_NOT\_AT\_COMMANDED value for each sensor (prior to setting them to 0)).

[See Bit 22 for a similar flag.]

Bit 22 = 1 or more ELC sensor DATA set to fill values.

Affects only electron HRS/CAL/HVE products (i.e. products that use multiple sensors), and generally only when starting that mode. When switching to HRS/CAL/HVE from LRS, one JADE-E sensor is already on, and the other(s) have to turn on, then it takes some time for that sensor to reach the commanded voltage. For a given record, MCP\_NOT\_AT\_COMMANDED = 0 for one sensor but is still = 1 for others. That is one sensor is taking valid science but the other(s) are not there yet and for those sensors: DATA and BACKGROUND objects (and their \*\_SIGMAS) have been replaced with MISSING\_CONSTANT values.

(Never used for Level 2 data, which has the counts as measured in the dipped state.)

In addition, Bit 17 of the ISSUES object (i.e. MCP\_NOT\_AT\_COMMANDED object = 1) is set to zero, and, if it exists, the MCP\_NOT\_AT\_COMMANDED object itself is changed (from 1) to be 0 for the offending sensor(s).

Only the elements of the DATA object for the original MCP\_NOT\_AT\_COMMANDED = 1 sensor(s) (prior to setting them to 0) are set to MISSING\_CONSTANT.

[Bits 21 and 22 are essentially the same feature caused by an mcp voltage not being at the commanded value, but the reason why this is the case is different. The treatment is identical for both Bit 21 and Bit 22.]

Bit 23 = Currently unused.

Bit 24 = Currently unused.

Bit 25 = Currently unused.

Bit 26 = Currently unused.

Bit 27 = Currently unused.

Bit 28 = Currently unused.

Bit 29 = Currently unused.

Bit 30 = Currently unused.

Bit 31 = Reserved for MISSING\_CONSTANT use.

Each bit has a decimal value of  $2^{\{\text{bit number}\}}$ , and the Issues flag is the sum of  $2^{\{\text{flagged bit numbers}\}}$ .

For instance, if this ISSUES flag = 131329, then in binary that value is 00000000000000100000000100000001 showing bits 17, 8 and 0 are flagged.

[If a currently unused bit is set, please check the latest LBL file for this product that you can find to see if it now has a definition.]"

OBJECT = BIT\_COLUMN  
NAME = ISSUES\_BITS  
BIT\_DATA\_TYPE = BOOLEAN

```

        START_BIT      = 1
        BITS           = 32
        ITEMS          = 32
        ITEM_BITS      = 1
        MINIMUM        = 0
        MAXIMUM        = 1
        DESCRIPTION    = "See ISSUES column object for description of bits."
    END_OBJECT        = BIT_COLUMN
/* RJW, ISSUES, I, 1, 1 */
    END_OBJECT        = COLUMN
END_OBJECT           = CONTAINER

```

```

OBJECT              = COLUMN
    NAME             = TIMESTAMP_WHOLE
    DATA_TYPE       = LSB_UNSIGNED_INTEGER
    START_BYTE       = 284309
    ITEMS            = 1
    ITEM_BYTES       = 4
    BYTES            = 4
    VALID_MINIMUM    = 365774402 /* 2011-Aug-05: Juno Launch */
    VALID_MAXIMUM    = 599573000 /* ~ 2019-Jan-01 */
    MISSING_CONSTANT = 0
    DESCRIPTION      = "Timestamp (Whole Second) of JADE Level 2 packet
                        used to make this Level 3 record."
/* RJW, TIMESTAMP_WHOLE, I, 1, 1 */
END_OBJECT          = COLUMN

```

```

OBJECT              = COLUMN
    NAME             = TIMESTAMP_SUB
    DATA_TYPE       = LSB_UNSIGNED_INTEGER
    START_BYTE       = 285313
    ITEMS            = 1
    ITEM_BYTES       = 2
    BYTES            = 2
    VALID_MINIMUM    = 0
    VALID_MAXIMUM    = 65535
    MISSING_CONSTANT = 0
    DESCRIPTION      = "Timestamp (Subsecond) of JADE Level 2 packet
                        used to make this Level 3 record."
/* RJW, TIMESTAMP_SUB, H, 1, 1 */
END_OBJECT          = COLUMN

```

```

OBJECT              = CONTAINER
    NAME             = DATA_DIM1
    START_BYTE       = 287315
    BYTES            = 192 /* = 48128 /* = 32 * 4-bytes */
    REPETITIONS      = 64
    DESCRIPTION      = "DATA_DIM1,
                        2D array of data, 1st and 2nd Dimensions."

```

```

OBJECT              = CONTAINER
    NAME             = DATA_DIM2
    START_BYTE       = 1
    BYTES            = 4
    REPETITIONS      = 4832
    DESCRIPTION      = "DATA_DIM2,
                        1D array of data, 2nd Dimension."

```

```

OBJECT              = COLUMN
    NAME             = DATA
    DATA_TYPE       = PC_REAL
    START_BYTE       = 1
    ITEMS            = 1

```

```

ITEM_BYTES      = 4
BYTES           = 4
VALID_MINIMUM   = -999998 /* if background removed, can be <0 */
VALID_MAXIMUM   = 1000000 /* A guess! need to refine value later */ 2250000
MISSING_CONSTANT = -1 999999
UNIT            = "COUNTS/SECOND"
DESCRIPTION     = "DATA: Counts/Second
                  64 Energy x 4832 Look Directions.
                  "
/* RJW, DATA, f, 2, 64, 4832 */
  END_OBJECT    = COLUMN
  END_OBJECT    = CONTAINER
END_OBJECT     = CONTAINER

OBJECT         = CONTAINER
NAME           = DATA_SIGMA_DIM1
START_BYTE     = 125758507
BYTES          = 192 /* = 48128 /* = 32 * 4-bytes */
REPETITIONS    = 64
DESCRIPTION    = "DATA_SIGMA_DIM1,
                  2D array of data, 1st and 2nd Dimensions."

OBJECT         = CONTAINER
NAME           = DATA_SIGMA_DIM2
START_BYTE     = 1
BYTES          = 4
REPETITIONS    = 4832
DESCRIPTION    = "DATA_SIGMA_DIM2,
                  1D array of data, 2nd Dimension."

OBJECT         = COLUMN
NAME           = DATA_SIGMA
DATA_TYPE      = PC_REAL
START_BYTE     = 1
ITEMS          = 1
ITEM_BYTES     = 4
BYTES          = 4
VALID_MINIMUM   = 0
VALID_MAXIMUM   = 1000000 /* A guess! need to refine value later */ 100000
MISSING_CONSTANT = -1 999999
UNIT            = "COUNTS/SECOND"
DESCRIPTION    = "DATA_SIGMA
                  1-sigma uncertainties on values in object DATA,
                  such that true value = DATA +/- DATA_SIGMA.
                  See DATA entry above for size information."
/* RJW, DATA_SIGMA, f, 2, 64, 4832 */
  END_OBJECT    = COLUMN
  END_OBJECT    = CONTAINER
END_OBJECT     = CONTAINER

OBJECT         = CONTAINER
NAME           = BACKGROUND_DIM1
START_BYTE     = 2486316699
BYTES          = 192 /* = 48128 /* = 32 * 4-bytes */
REPETITIONS    = 64
DESCRIPTION    = "BACKGROUND_DIM1,
                  2D array of data, 1st and 2nd Dimensions."

OBJECT         = CONTAINER
NAME           = BACKGROUND_DIM2
START_BYTE     = 1
BYTES          = 4
REPETITIONS    = 4832

```



```

DESCRIPTION          = "BACKGROUND_DIM2,
                      1D array of data, 2nd Dimension."

OBJECT               = COLUMN
NAME                 = BACKGROUND
DATA_TYPE            = PC_REAL
START_BYTE           = 1
ITEMS                = 1
ITEM_BYTES           = 4
BYTES                = 4
VALID_MINIMUM        = 0
VALID_MAXIMUM        = 1000000 /* A guess! need to refine value later */ 2250000
MISSING_CONSTANT     = -1 999999
UNIT                 = "COUNTS/SECOND"
DESCRIPTION          = "Background value removed from DATA.
                      No further background removal is required.
                      If you wish to do your own background removal,
                      add this object to DATA then you can remove a
                      background via your own method.
                      The background values here were found from either
                      a background anode or JADE's own ground method."

/* RJW, BACKGROUND, f, 2, 64, 4832 */
END_OBJECT           = COLUMN
END_OBJECT           = CONTAINER
END_OBJECT           = CONTAINER

OBJECT               = CONTAINER
NAME                 = BACKGROUND_SIGMA_DIM1
START_BYTE           = 37151 24891
BYTES                = 192 /* = 48128 /* = 32 * 4-bytes */
REPETITIONS          = 64
DESCRIPTION          = "BACKGROUND_SIGMA_DIM1,
                      2D array of data, 1st and 2nd Dimensions."

OBJECT               = CONTAINER
NAME                 = BACKGROUND_SIGMA_DIM2
START_BYTE           = 1
BYTES                = 4
REPETITIONS          = 4832
DESCRIPTION          = "BACKGROUND_SIGMA_DIM2,
                      1D array of data, 2nd Dimension."

OBJECT               = COLUMN
NAME                 = BACKGROUND_SIGMA
DATA_TYPE            = PC_REAL
START_BYTE           = 1
ITEMS                = 1
ITEM_BYTES           = 4
BYTES                = 4
VALID_MINIMUM        = 0
VALID_MAXIMUM        = 1000000 /* A guess! need to refine value later */ 100000
MISSING_CONSTANT     = -1 999999
UNIT                 = "COUNTS/SECOND"
DESCRIPTION          = "BACKGROUND_SIGMA
                      1-sigma uncertainties on values in object
                      BACKGROUND, such that
                      true value = BACKGROUND +/- BACKGROUND_SIGMA.
                      See BACKGROUND entry above for size information."

/* RJW, BACKGROUND_SIGMA, f, 2, 64, 4832 */
END_OBJECT           = COLUMN
END_OBJECT           = CONTAINER
END_OBJECT           = CONTAINER

```

```

OBJECT          = CONTAINER
  NAME          = DIM1_E_DIM1
  START_BYTE   = 4943933083
  BYTES        = 192 /* = 48128 /* = 32 * 4-bytes */
  REPETITIONS  = 64
  DESCRIPTION   = "DIM1_E_DIM1,
                  2D array of data, 1st and 2nd Dimensions."

OBJECT          = CONTAINER
  NAME          = DIM1_E_DIM2
  START_BYTE   = 1
  BYTES        = 4
  REPETITIONS  = 4832
  DESCRIPTION   = "DIM1_E_DIM2,
                  1D array of data, 2nd Dimension."

OBJECT          = COLUMN
  NAME          = DIM1_E
  DATA_TYPE   = PC_REAL
  START_BYTE   = 1
  ITEMS        = 1
  ITEM_BYTES   = 4
  BYTES        = 4
  VALID_MINIMUM = 0.0
  VALID_MAXIMUM = 99000.0 /* Refine. Rounded up to whole keV/q */
  MISSING_CONSTANT = 99999.0
  UNIT         = "eV/q"
  DESCRIPTION   = "1st Dimension of DATA: Energy —(center) in eV/q-value
                  Upper and lower limits are given by the
                  objects DIM1_E_UPPER and DIM1_E_LOWER." ."
                  ."
```

---

```

/* RJW, DIM1_E, f, 2, 64, 4832 */
  END_OBJECT   = COLUMN
  END_OBJECT   = CONTAINER
END_OBJECT     = CONTAINER

OBJECT          = CONTAINER
  NAME          = DIM2_ELEVATION_DIM1_E_UPPER_DIM1
  START_BYTE   = 6172741275
  BYTES        = 192 /* = 48128 /* = 32 * 4-bytes */
  REPETITIONS  = 64
  DESCRIPTION   = "DIM2_ELEVATION_DIM1_E_UPPER_DIM1,
                  2D array of data, 1st and 2nd Dimensions."

OBJECT          = CONTAINER
  NAME          = DIM1_E_UPPER_DIM2_ELEVATION_DIM2
  START_BYTE   = 1
  BYTES        = 4
  REPETITIONS  = 4832
  DESCRIPTION   = "DIM1_E_UPPER_DIM2_ELEVATION_DIM2,
                  1D array of data, 2nd Dimension."
  1D array of data, 2nd Dimension."

OBJECT          = COLUMN
  NAME          = DIM1_E_UPPER_DIM2_ELEVATION
  DATA_TYPE   = PC_REAL
  START_BYTE   = 1
  ITEMS        = 1
  ITEM_BYTES   = 4
  BYTES        = 4
  VALID_MINIMUM = —090.0
  VALID_MAXIMUM = 9900090.0 /* Refine. Rounded up
  MISSING_CONSTANT = 65535.0
```

```

UNIT = "Degrees"
DESCRIPTION = "2nd Dimension of DATA: Spacecraft elevation -
center value. Spacecraft elevation (degs) is
analogous to whole keV/q */ latitude on a sphere. In
spacecraft
MISSING_CONSTANT = 99999.0
UNIT = "eV/q"
DESCRIPTION = "1st Dimension of DATA: Energy upper eV/q limit.
See DIM1_E for description."
xyz co-ords:
+z is equivalent to elevation = +90 degs
-z is equivalent to elevation = -90 degs
(The communication dish is directed along +z)
xy-plane at z = 0 is equivalent to elevation = 0

Note, 2nd dimension is really look direction
which has an elevation and azimuth; hence two
objects describe this: DIM2_ELEVATION and
DIM2_AZIMUTH_DESPUN."
/* RJW, DIM1_E_UPPERDIM2_ELEVATION, f, 2, 64, 48 */ 32 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER
END_OBJECT = CONTAINER

OBJECT = CONTAINER
NAME = DIM2_AZIMUTH_DESPUN_DIM1_E_LOWER_DIM1
START_BYTE = 7401549467
BYTES = 192 /* = 48128 /* = 32 * 4-bytes */
REPETITIONS = 64
DESCRIPTION = "DIM2_AZIMUTH_DESPUN_DIM1_E_LOWER_DIM1,
2D array of data, 1st and 2nd Dimensions."

OBJECT = CONTAINER
NAME = DIM1_E_LOWER_DIM2_AZIMUTH_DESPUN_DIM2
START_BYTE = 1
BYTES = 4
REPETITIONS = 4832
DESCRIPTION = "DIM1_E_LOWER_DIM2_AZIMUTH_DESPUN_DIM2,
1D array of data, 2nd Dimension."

7
1D array of data, 2nd Dimension."

OBJECT = COLUMN
NAME = DIM1_E_LOWER_DIM2_AZIMUTH_DESPUN
DATA_TYPE = PC_REAL
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = 0.0
VALID_MAXIMUM = 99000 360.0
MISSING_CONSTANT = 65535.0
UNIT = "Degrees"
DESCRIPTION = "2nd Dimension of DATA: /* Refine. Rounded up */ Despun S/C
azimuth -
center value. Spacecraft azimuth (degs) is
analogous to whole keV/q */ longitude on a sphere. In
spacecraft
MISSING_CONSTANT = 99999.0
UNIT = "eV/q"
DESCRIPTION = "1st Dimension of DATA: Energy - lower eV/q limit.
See DIM1_E for description."
xyz co-ords:

```

```

+x is equivalent to azimuth = 0 degs
+y is equivalent to azimuth = 90 degs
-x is equivalent to azimuth = 180 degs
-y is equivalent to azimuth = 270 degs
+x is equivalent to azimuth = 360 degs
+y is equivalent to azimuth = 450 degs
The 'Despun' azimuth angle varies because Juno
spins, where azimuth = 0 is defined as +x when
spin phase equals zero (e.g., despun x-z plane
contains the ECLIPJ2000 north).

```

```

The relationship between despun azimuth and spin
phase is simply:
Despun Azimuth = 360 degrees - Spin Phase

```

```

Note, 2nd dimension is really look direction
which has an elevation and azimuth; hence two
objects describe this: DIM2_ELEVATION and
DIM2_AZIMUTH DESPUN."

```

```

/* RJW, DIM1_E_LOWERDIM2_AZIMUTH DESPUN, f, 2, 64, 48 */ 32 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER
END_OBJECT = CONTAINER

```

```

OBJECT = CONTAINERCOLUMN
NAME = DIM2_ELEVATION_DIM1
START_BYTE = 86303
BYTES = 192 /* = 48 * 4 bytes */
REPETITIONS = 64
DESCRIPTION = "DIM2_ELEVATION_DIM1,
2D array of data, 1st and 2nd Dimensions."

```

```

OBJECT = CONTAINER
NAME = DIM2_ELEVATION_DIM2
START_BYTE = 1
BYTES = 4
REPETITIONS = 48
DESCRIPTION = "DIM2_ELEVATION_DIM2,
1D array of data, 2nd Dimension."

```

```

OBJECT = COLUMN
NAME = DIM2_ELEVATION
DATA_TYPE = DC_REAL
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = -90.0
VALID_MAXIMUM = 90.0
MISSING_CONSTANT = 65535.0
UNIT = "Degrees"
DESCRIPTION = "2nd Dimension of DATA: Spacecraft elevation
center value. Spacecraft elevation (degs) is
analogous to latitude on a sphere. In spacecraft
xyz co-ords:
+z is equivalent to elevation = +90 degs
-z is equivalent to elevation = -90 degs
(The communication dish is directed along +z)
xy plane at z = 0 is equivalent to elevation = 0

```

```

Note, 2nd dimension is really look direction
which has an elevation and azimuth; hence two
objects describe this: DIM2_ELEVATION and

```

```

----- DIM2_AZIMUTH_DESPUN."
/* RJW, DIM2_ELEVATION, f, 2, 64, 48 */
----- END_OBJECT ----- COLUMN
----- END_OBJECT ----- CONTAINER
----- END_OBJECT ----- CONTAINER

OBJECT ----- CONTAINER
NAME ----- DIM2_ELEVATION_UPPER_DIM1
START_BYTE ----- 98591
BYTES ----- 192 /* = 48 * 4-bytes */
REPETITIONS ----- 64
DESCRIPTION ----- "DIM2_ELEVATION_UPPER_DIM1,
----- 2D array of data, 1st and 2nd Dimensions."

----- OBJECT ----- CONTAINER
NAME ----- DIM2_ELEVATION_UPPER_DIM2
START_BYTE ----- 1
BYTES ----- 4
REPETITIONS ----- 48
DESCRIPTION ----- "DIM2_ELEVATION_UPPER_DIM2,
----- 1D array of data, 2nd Dimension."

OBJECT ----- COLUMN
NAME ----- DIM2_ELEVATION_UPPER
DATA_TYPE ----- PC_REAL
START_BYTE ----- 1
ITEMS ----- 1
ITEM_BYTES ----- 4
BYTES ----- 4
VALID_MINIMUM ----- 90.0
VALID_MAXIMUM ----- 90.0
MISSING_CONSTANT ----- 65535.0
UNIT ----- "Degrees"
DESCRIPTION ----- "2nd Dimension of DATA: S/C elevation upper
----- limit. See DIM2_ELEVATION for description."
/* RJW, DIM2_ELEVATION_UPPER, f, 2, 64, 48 */
----- END_OBJECT ----- COLUMN
----- END_OBJECT ----- CONTAINER
----- END_OBJECT ----- CONTAINER

OBJECT ----- CONTAINER
NAME ----- DIM2_ELEVATION_LOWER_DIM1
START_BYTE ----- 110879
BYTES ----- 192 /* = 48 * 4-bytes */
REPETITIONS ----- 64
DESCRIPTION ----- "DIM2_ELEVATION_LOWER_DIM1,
----- 2D array of data, 1st and 2nd Dimensions."

----- OBJECT ----- CONTAINER
NAME ----- DIM2_ELEVATION_LOWER_DIM2
START_BYTE ----- 1
BYTES ----- 4
REPETITIONS ----- 48
DESCRIPTION ----- "DIM2_ELEVATION_LOWER_DIM2,
----- 1D array of data, 2nd Dimension."

OBJECT ----- COLUMN
NAME ----- DIM2_ELEVATION_LOWER
DATA_TYPE ----- PC_REAL
START_BYTE ----- 1
ITEMS ----- 1
ITEM_BYTES ----- 4
BYTES ----- 4
VALID_MINIMUM ----- 90.0
VALID_MAXIMUM ----- 90.0

```

```

-----MISSING_CONSTANT = 65535.0
-----UNIT = "Degrees"
-----DESCRIPTION = "2nd Dimension of DATA: S/C elevation lower
----- limit. See DIM2_ELEVATION for description."
/* RJW, DIM2_ELEVATION_LOWER, f, 2, 64, 48 */
-----END_OBJECT = COLUMN
-----END_OBJECT = CONTAINER
-----END_OBJECT = CONTAINER

OBJECT = CONTAINER
-----NAME = DIM2_AZIMUTH_DESPUN_DIM1
-----START_BYTE = 123167
-----BYTES = 192 /* = 48 * 4 bytes */
-----REPETITIONS = 64
-----DESCRIPTION = "DIM2_AZIMUTH_DESPUN_DIM1,
----- 2D array of data, 1st and 2nd Dimensions."

OBJECT = CONTAINER
-----NAME = DIM2_AZIMUTH_DESPUN_DIM2
-----START_BYTE = 1
-----BYTES = 4
-----REPETITIONS = 48
-----DESCRIPTION = "DIM2_AZIMUTH_DESPUN_DIM2,
----- 1D array of data, 2nd Dimension."

OBJECT = COLUMN
-----NAME = DIM2_AZIMUTH_DESPUN
-----DATA_TYPE = PC_REAL
-----START_BYTE = 1
-----ITEMS = 1
-----ITEM_BYTES = 4
-----BYTES = 4
-----VALID_MINIMUM = 0.0
-----VALID_MAXIMUM = 720.0
-----MISSING_CONSTANT = 65535.0
-----UNIT = "Degrees"
-----DESCRIPTION = "2nd Dimension of DATA: Despun S/C azimuth
----- center value. Spacecraft azimuth (degs) is
----- analogous to longitude on a sphere. In spacecraft
----- xyz co-ords:
----- +x is equivalent to azimuth = 0 degs
----- +y is equivalent to azimuth = 90 degs
----- -x is equivalent to azimuth = 180 degs
----- -y is equivalent to azimuth = 270 degs
----- +x is equivalent to azimuth = 360 degs
----- +y is equivalent to azimuth = 450 degs
----- The 'Despun' azimuth angle varies because Juno
----- spins, where azimuth = 0 is defined as +x when
----- spin phase equals zero (e.g. despun x-z plane
----- contains the ECLIPJ2000 north).

----- The relationship between despun azimuth and spin
----- phase (which decreases during a spin) is simply:
----- Despun Azimuth = 360 degrees - Spin Phase

----- Because a lower to upper limit could occur over a
----- 360 degree boundary, the VALID_MINIMUM and
----- VALID_MAXIMUM go from 0 to +720 degrees:
----- e.g. [lower, center, upper] = [-10, 5, 20]
----- would be given instead as = [350, 365, 380]

----- Note, 2nd dimension is really look direction
----- which has an elevation and azimuth; hence two

```

```

objects describe this: DIM2_ELEVATION and
DIM2_AZIMUTH_DESPUN."
/* RJW, DIM2_AZIMUTH_DESPUN, f, 2, 64, 48 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER
END_OBJECT = CONTAINER

OBJECT = CONTAINER
NAME = DIM2_AZIMUTH_DESPUN_UPPER_DIM1
START_BYTE = 135455
BYTES = 192 /* = 48 * 4 bytes */
REPETITIONS = 64
DESCRIPTION = "DIM2_AZIMUTH_DESPUN_UPPER_DIM1,
2D array of data, 1st and 2nd Dimensions."

OBJECT = CONTAINER
NAME = DIM2_AZIMUTH_DESPUN_UPPER_DIM2
START_BYTE = 1
BYTES = 4
REPETITIONS = 48
DESCRIPTION = "DIM2_AZIMUTH_DESPUN_UPPER_DIM2,
1D array of data, 2nd Dimension."

OBJECT = COLUMN
NAME = DIM2_AZIMUTH_DESPUN_UPPER
DATA_TYPE = PC_REAL
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = 0.0
VALID_MAXIMUM = 720.0
MISSING_CONSTANT = 65535.0
UNIT = "Degrees"
DESCRIPTION = "2nd Dimension of DATA: Despun S/C azimuth - upper
limit. See DIM2_AZIMUTH_DESPUN for description."
/* RJW, DIM2_AZIMUTH_DESPUN_UPPER, f, 2, 64, 48 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER
END_OBJECT = CONTAINER

OBJECT = CONTAINER
NAME = DIM2_AZIMUTH_DESPUN_LOWER_DIM1
START_BYTE = 147743
BYTES = 192 /* = 48 * 4 bytes */
REPETITIONS = 64
DESCRIPTION = "DIM2_AZIMUTH_DESPUN_LOWER_DIM1,
2D array of data, 1st and 2nd Dimensions."

OBJECT = CONTAINER
NAME = DIM2_AZIMUTH_DESPUN_LOWER_DIM2
START_BYTE = 1
BYTES = 4
REPETITIONS = 48
DESCRIPTION = "DIM2_AZIMUTH_DESPUN_LOWER_DIM2,
1D array of data, 2nd Dimension."
OBJECT = COLUMN
NAME = DIM2_AZIMUTH_DESPUN_LOWER
DATA_TYPE = PC_REAL
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4

```

```

VALID_MINIMUM = 0.0
VALID_MAXIMUM = 720.0
MISSING_CONSTANT = 65535.0
UNIT = "Degrees"
DESCRIPTION = "2nd Dimension of DATA: Despun S/C azimuth - lower
limit. See DIM2_AZIMUTH_DESPUN for description."
/* RJW, DIM2_AZIMUTH_DESPUN_LOWER, f, 2, 64, 48 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER
END_OBJECT = CONTAINER

OBJECT = COLUMN
NAME = MAG VECTOR
DATA_TYPE = PC_REAL
START_BYTE = 16003157659
ITEMS = 3
ITEM_BYTES = 4
BYTES = 12
VALID_MINIMUM = -1600000.0
VALID_MAXIMUM = 1600000.0
MISSING_CONSTANT = 9990000.0
UNIT = "nT"
DESCRIPTION = "MAG vector in nT, 3 components [X, Y, Z]
MAG range is +/- 16 G, hence limits.
This xyz coordinate system is despun spacecraft; see
the definitions of DIM2_ELEVATION and DIM2_AZIMUTH:
+X is when [azimuth, elevation] = [ 0, 0] degrees,
+Y is when [azimuth, elevation] = [ 90, 0] degrees,
+Z is when elevation = 90 degrees."

/* RJW, MAG_VECTOR, f, 1, 3 */
END_OBJECT = COLUMN

```



## D.2 Sample FMT file for JAD\_L30\_HLS\_ION\_TOF\_CNT\_V02V04.FMT

```
/* Filename: Version02Version04/JAD_L30_HLS_ION_TOF_CNT_V02V04.FMT
*/
/* File written: 2018/01/24 14:08:23 */
/* Will code useful Python based letters to describe each object */
/* see http://docs.python.org/library/struct.html for codes */
/* formats will comma separated beginning with "RJV," as key then */
/* {NAME}, {FORMAT}, {Number of dims}, {Size Dim 1}, {Size Dim 2}, ... */
/* where {FORMAT} is the Python code for the type, i.e. I for uint32 */
/* and there are as many Size Dim's as number of dimensions. */
/* Remember to remove the comment markers at either end */

/* RJW, BYTES_PER_RECORD, 2021/10/22 16:29:57
*/
/* Will code useful Python based letters to describe each object */
/* see http://docs.python.org/library/struct.html for codes */
/* formats will comma separated beginning with "RJV," as key then */
/* {NAME}, {FORMAT}, {Number of dims}, {Size Dim 1}, {Size Dim 2}, ... */
/* where {FORMAT} is the Python code for the type, i.e. I for uint32 */
/* and there are as many Size Dim's as number of dimensions. */
/* Remember to remove the comment markers at either end */

/* RJW, BYTES_PER_RECORD, 100476 */98228 */
/* RJW, OBJECTS_PER_RECORD, 5658 */

OBJECT          = COLUMN
  NAME          = DIM0_UTC
  DATA_TYPE    = DATE /* ASCII character string */
  START_BYTE    = 1
  BYTES         = 21
  VALID_MINIMUM = 2011-217T00:00:00.001
                /* SC Clock 365774402:0, JUNO Launch */
  VALID_MAXIMUM = 20192026-001T00:00:00.000 /* Expect mission end in 20192025 */
  MISSING_CONSTANT = 0001-001T00:00:00.000
  DESCRIPTION   = "UTC timestamp at center (not start) of record.
                  Format is yyyy-dddTHH:MM:SS.sss
                  where yyyy = year, ddd = day of year,
                  HH = hour, MM = minute,
                  SS.sss = decimal seconds to millisecond resolution.
                  Note: Duration of record can be found in S.I. seconds
                  by DIM0_UTC_UPPER - DIM0_UTC_LOWER. Do not confuse
                  this with the ACCUMULATION_TIME object, which is the
                  number of spacecraft clock ticks for accumulation.
                  While 1 tick is approximately 1 second, it is not
                  identical."
/* RJW, DIM0_UTC, c, 1, 21 */
END_OBJECT     = COLUMN

OBJECT          = COLUMN
  NAME          = PACKETID
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 22
  BYTES         = 1
  VALID_MINIMUM = 105 /* (0x69) */
  VALID_MAXIMUM = 137 /* (0x89) */
  MISSING_CONSTANT = 255 /* Unknown, or a mix of packets */
  DESCRIPTION   = "Packet ID (DPID), Data Product Identifier
                  High and Low Rate Science - Ion Time Of Flight
                  PACKETID = 137 (0x89) = High Rate Science
                  PACKETID = 105 (0x69) = Low Rate Science"
/* RJW, PACKETID, B, 1, 1 */
```

```

END_OBJECT          = COLUMN

OBJECT              = COLUMN
  NAME               = DIM0.UTC_UPPER
  DATA_TYPE         = DATE /* ASCII character string */
  START_BYTE         = 23
  BYTES              = 21
  VALID_MINIMUM      = 2011-217T00:00:00.001
  VALID_MAXIMUM      = 20192026-001T00:00:00.000
  MISSING_CONSTANT   = 0001-001T00:00:00.000
  DESCRIPTION        = "0th Dimension of DATA: Time - upper limit.
                        See DIM0.UTC for description."
/* RJW, DIM0.UTC_UPPER, c, 1, 21 */
END_OBJECT          = COLUMN

OBJECT              = COLUMN
  NAME               = PACKET_MODE
  DATA_TYPE         = LSB_INTEGER
  START_BYTE         = 44
  BYTES              = 1
  VALID_MINIMUM      = 1
  VALID_MAXIMUM      = 2
  MISSING_CONSTANT   = 127
  DESCRIPTION        = "Packet Mode, describes type of data telemetry.
                        -2 = HSK / Housekeeping Engineering (Level 2 only)
                        -1 = HVE / High Voltage Engineering (Level 2 only)
                        0 = CAL / MCP Calibration Science (Level 2 only)
                        1 = LRS / Low Rate Science
                        2 = HRS / High Rate Science
                        3 = DRS / DeRived Science from LRS and/or HRS
                        127 = Unknown
                        254 = Wrong - but HSK, see below. (Level 2 only)
                        255 = Wrong - but HVE, see below. (Level 2 only)
                        (Note, this could also be calculated via PACKETID.)
                        If you have 254 or 255 then your code is incorrect,
                        check you read a signed byte, rather than unsigned."
/* RJW, PACKET_MODE, b, 1, 1 */
END_OBJECT          = COLUMN

OBJECT              = COLUMN
  NAME               = DIM0.UTC_LOWER
  DATA_TYPE         = DATE /* ASCII character string */
  START_BYTE         = 45
  BYTES              = 21
  VALID_MINIMUM      = 2011-217T00:00:00.001
  VALID_MAXIMUM      = 20192026-001T00:00:00.000
  MISSING_CONSTANT   = 0001-001T00:00:00.000
  DESCRIPTION        = "0th Dimension of DATA: Time - lower limit.
                        See DIM0.UTC for description."
/* RJW, DIM0.UTC_LOWER, c, 1, 21 */
END_OBJECT          = COLUMN

OBJECT              = COLUMN
  NAME               = PACKET_SPECIES
  DATA_TYPE         = LSB_INTEGER
  START_BYTE         = 66
  BYTES              = 1
  VALID_MINIMUM      = 9
  VALID_MAXIMUM      = 9
  MISSING_CONSTANT   = 127
  DESCRIPTION        = "Packet Species, describes type of plasma data.
                        -1 = electrons
                        0 = ion species 0, SP0

```

```

        1 = ion species 1, SP1
        2 = ion species 2, SP2
        3 = ion species 3, SP3
        4 = ion species 4, SP4
        5 = ion species 5, SP5
        6 = ion species 6, SP6
        7 = ion species 7, SP7
        8 = Sum of SP3, SP4 and SP5
        9 = All ions /* or any ion, e.g. ., TOF and LOG */
        10 = Single ion species derived from TOF data
        127 = Unknown
        255 = Wrong - but electrons, see below.
        If you have 255 then your code is incorrect,
        check you read a signed byte, rather than unsigned."
/* RJW, PACKET_SPECIES, b, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = ACCUMULATION_TIME
DATA_TYPE      = LSB_UNSIGNED_INTEGER
START_BYTE     = 67
BYTES          = 2
VALID_MINIMUM  = 1
VALID_MAXIMUM  = 1800
MISSING_CONSTANT = 65535
UNIT           = "SECONDS" /* Not S.I. Seconds, but SCLK ticks */
DESCRIPTION    = "Accumulation Time.
                  Number of seconds over which the data in this product
                  was collected (Science Program).
                  Note: Duration of record can be found in S.I. seconds
                  by DIM0.UTC_UPPER - DIM0.UTC_LOWER. Do not confuse
                  this with the ACCUMULATION_TIME object, which is the
                  number of spacecraft clock ticks for accumulation.
                  While 1 tick is approximately 1 second, it is not
                  identical.
                  ACCUMULATION TIME is left in spacecraft clock ticks to
                  both aid matching with the level 2 data and to help
                  filtering for data taken in a particular mode."

/* RJW, ACCUMULATION_TIME, H, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = DATA_UNITS
DATA_TYPE      = LSB_UNSIGNED_INTEGER
START_BYTE     = 69
BYTES          = 1
VALID_MINIMUM  = 2
VALID_MAXIMUM  = 2
MISSING_CONSTANT = 255
DESCRIPTION    = "Data units correspond to:
                  0 = All counts in the accumulation period
                  1 = All counts divided by number of views
                  2 = Counts per second
                     /* S.I. science units: */
                  3 = Differential Energy Flux [1/( m^2 sr s   )]
                  4 = Differential Number Flux [1/( m^2 sr s   J)]
                  5 = Phase Space Density   [   m^-6   s^3   ]
                     /* Convenient (non-S.I.) science units: */
                  6 = Differential Energy Flux [1/(cm^2 sr s   )]
                  7 = Differential Number Flux [1/(cm^2 sr s   keV)]
                  8 = Phase Space Density   [   cm^-6   s^3   ]
/* As new products are developed this list will increase */
/* If a number is not listed,                               */

```

```

                /* try a LBL/FMT file from a recent date. */
                255 = Unknown."
/* RJW, DATA_UNITS, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = SOURCE_BACKGROUND
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 70
  BYTES         = 1
  VALID_MINIMUM = 0
  VALID_MAXIMUM = ±
MISSING_CONSTANT = 255
DESCRIPTION      = "Source of Background values (see BACKGROUND object)
                  that have been removed from the DATA object.
                  0 = None: No background has been removed
                  1 = Background anode (electron sensors only)
/* As new background removal methods are developed this list will increase */
                255 = Unknown."
/* RJW, SOURCE_BACKGROUND, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = 4
  MISSING_CONSTANT = 255
  DESCRIPTION      = "Source of Background values (see BACKGROUND object)
                    that have been removed from the DATA object.
                    0 = None: No background has been removed
                    1 = Background anode (electron sensors only)
                    2 = Background anode (JADE-I only)
                    3 = Derived from Background anode : Method 1:
                        Background coefficients are time independent.
                        See file in CALIB directory for description.
                    4 = Derived from Background anode : Method 2:
                        Background coefficients are per orbit.
                        See file in CALIB directory for description.
/* As new background removal methods are developed this list will increase */
                255 = Unknown."
/* RJW, SOURCE_BACKGROUND, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = SOURCE_DEAD_TIME_SPECIES_REMAPPED
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 71
  BYTES         = 1
  VALID_MINIMUM = 0
  VALID_MAXIMUM = 0
  MISSING_CONSTANT = 255
  DESCRIPTION    = "Source of Dead Time Correction Method ion remapping
for ION TOF data products:
                    0 = None: Data has not been Dead Time corrected. remapped
on the ground.
                255 = Unknown."
/* RJW, SOURCE_DEAD_TIMESPECIES_REMAPPED, B, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = SOURCE_MAG
  DATA_TYPE    = LSB_UNSIGNED_INTEGER
  START_BYTE    = 72
  BYTES         = 1
  VALID_MINIMUM = 0

```

```

VALID_MAXIMUM      = 39
MISSING_CONSTANT  = 255
DESCRIPTION        = "Source of MAG data
                    Except case 0 and 1, PAYLOAD (pl) co-ordinate MAG files
                    were used at 1s (or 2s if no 1s) resolution.
                    0 = None: No MAG data in this product.
                    1 = From Juno JADE's Level 2 files.
                      (From spacecraft and therefore uncalibrated.)
                      This is independent to JADE Level 2 version
                      number as it does not change with versions.
                      [Note MAG data in JADE files may be affected
                      by the Juno time stutter.]
                    3n = Juno's MAG's Level 3 version n calibrated
                      files, e.g., 34 means version 4, so:
                    30 = From Juno MAG's Level 3 version 00 quicklook
                      payload files.
                      (These are temporary files not in PDS.)
                    31 = From Juno MAG's Level 3 version 01 calibrated
                      payload files.
                    32 = From Juno MAG's Level 3 version 02 calibrated
                      payload files.

                    30 = From Juno MAG's Level 3 version 00 quicklook
                      payload files.
                      (These are temporary files not in PDS.)
                    31 = From Juno MAG's Level 3 version 01 calibrated
                      payload files.
                    32 = From Juno MAG's Level 3 version 02 calibrated
                      payload files.

                    Likewise, 33 to 39 being Level 3 version 3 to 9.
                    255 = Unknown.

                    If you see a number not listed above, there may be
                    later versions of MAG data - find the latest
                    available LBL file for this product and see what that
                    has listed."
/* RJW, SOURCE_MAG, B, 1, 1 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = SOURCE_JADE_METAKERNEL
DATA_TYPE         = LSB_INTEGER
START_BYTE        = 73
BYTES             = 2
VALID_MINIMUM     = -32767
VALID_MAXIMUM     = 32767
MISSING_CONSTANT  = -32768
DESCRIPTION        = "The JADE SPICE metakernel used to get the time,
                    position, velocity, orientation and transformation
                    objects in this file. The metakernel lists the
                    many individual spice kernels used, which are
                    archived by NAIF and not in this PDS volume.
                    The JADE SPICE metakernel may be found in the CALIB
                    directory of this PDS volume, with filenames of:
                    JAD_L30_SPICE_METAKERNEL_nnnnn.TXT
                    where nnnnn is the SOURCE_JADE_METAKERNEL object
                    number (with leading zeros and positive).
                    If any of the kernels within the metakernel are not
                    reconstructed (but reference or predicted) for the
                    time in question, this value will be negative.
                    Within the JADE PDS archive this value should always
                    be positive."
/* RJW, SOURCE_JADE_METAKERNEL, h, 1, 1 */

```

```

END_OBJECT      = COLUMN

OBJECT          = COLUMN
  NAME          = SOURCE_JADE_CALIB
  DATA_TYPE    = LSB_INTEGER
  START_BYTE    = 75
  BYTES         = 2
  VALID_MINIMUM = - 0
  VALID_MAXIMUM = 32767
VALID_MAXIMUM = 32767
  MISSING_CONSTANT = -32768
  DESCRIPTION   = "The JADE calibration files list used to convert the
                    engineering units of Level 2 data to the scientific
                    units in this file.  Similar to the SPICE metakernel
                    list, this lists the many individual calibration files
                    used, each of which may be found in the CALIB
                    directory on this PDS volume.

```

This list may be found in the CALIB directory of this PDS volume, with filenames of:

JAD\_L30\_CALIB\_LIST\_nnnnn.TXT

where nnnnn is the SOURCE\_JADE\_CALIB object number (with leading zeros and positive).

If any of the calibration files listed are not final at the time in question, this value will be negative. (Newer calibration files will have a higher version and simply be listed in a newer SOURCE\_JADE\_CALIB file.)

Within the JADE PDS archive this value should always be positive. However, a version 00 file (for team use or uploaded to JSOC, not PDS) may have negative values with predicted positions/orientations/transformations."

```

/* RJW, SOURCE JADE CALIB, h, 1, 1 */
END_OBJECT      = COLUMN

```

```

OBJECT          = COLUMN
  NAME          = FSW_VERSION
  DATA_TYPE    = PC_REAL

```

~~a version 00 file (for team use or uploaded to JSOC, not PDS) may have negative values with predicted positions/orientations/transformations.~~

~~/\* Rob Note: ensure this file says which START BYTE =~~

```

77
  BYTES         = 4
  VALID_MINIMUM = 0.00
  VALID_MAXIMUM = 9.99
  MISSING_CONSTANT = -99.99
  DESCRIPTION   = "Flight Software version ef
                    Level 2 JADE files were used to make this L3 file. */".

```

```

/* RJW, SOURCE JADE CALIB, h, 1, 1 */
END_OBJECT      = COLUMN

```

```

OBJECT          = COLUMN
  NAME          = FSW_VERSION
  DATA_TYPE    = PC_REAL
  START_BYTE    = 77
  BYTES         = 4
  VALID_MINIMUM = 0.00
  VALID_MAXIMUM = 9.99
  MISSING_CONSTANT = 99.99
  DESCRIPTION   = "Flight Software version used.
                    Number should be to 2 decimal places, with rounding.


```

~~-----~~ ~~c.g.~~ ~~-----~~ Number should be to 2 decimal places, with rounding.

~~-----~~ e.g., 4.00, 4.10, 4.20. i.e., 4.1999998 means 4.20."  
/\* RJW, FSW VERSION, f, 1, 1 \*/  
~~-----~~ END OBJECT = COLUMN

~~-----~~ OBJECT = COLUMN  
~~-----~~ . " NAME = LUT VERSION  
/\* RJW, FSW VERSION, f, 1, 1 \*/  
~~-----~~ END OBJECT = COLUMN

~~-----~~ OBJECT = COLUMN  
~~-----~~ NAME = SC\_POS\_R  
DATA\_TYPE = PC\_REAL  
START\_BYTE = 81  
BYTES = 4  
VALID MINIMUM = 0.00  
VALID MAXIMUM = 9.99  
MISSING CONSTANT = -99.99  
DESCRIPTION = "LUT (Look Up Table) Version used on JADE.  
Number should be to 2 decimal places, with rounding.  
e.g., 4.00, 4.10, 4.20. i.e., 4.1999998 means 4.20."  
/\* RJW, LUT VERSION, f, 1, 1 \*/

~~-----~~ END OBJECT = COLUMN

~~-----~~ OBJECT = COLUMN  
~~-----~~ NAME = LUT VERSION SUB LETTER  
DATA TYPE = CHARACTER  
START BYTE = 85  
BYTES = 2  
FORMAT = "A2"  
DESCRIPTION = "The letter (if any) associated with the energy table  
used at the time of this record  
-- -> No sub letter for this LUT Version  
-A -> Sub letter is A for this LUT Version  
-B -> Sub letter is B for this LUT Version  
-C -> Sub letter is C for this LUT Version  
etc.  
For instance, the energy table files are in the CALIB  
directory of this PDS volume, with names like:  
LUT 4 00 ENERGY V01.CSV  
(LUT VERSION 4.00, no sub letter)  
or  
LUT 5 01 K ENERGY V01.CSV  
(LUT VERSION 5.01, sub letter K)."  
/\* RJW, LUT VERSION SUB LETTER, c, 1, 2 \*/

~~-----~~ END OBJECT = COLUMN

~~-----~~ OBJECT = COLUMN  
~~-----~~ NAME = LUT SWEEP TABLE  
DATA TYPE = LSB UNSIGNED INTEGER  
START BYTE = 87  
BYTES = 1  
VALID MINIMUM = 1  
VALID MAXIMUM = 23  
MISSING CONSTANT = 255  
DESCRIPTION = "The sweep tables the ion sensor used.  
A level 2 packet will report this as 0-3,  
However, it requires 2 packets (a ping and a pong)  
to make a level 3 record: either 0 and 1, or 2 and 3.  
Therefore, a value of 1 (= 01) means sweep tables  
0 and 1 were used, while a value of 23 means sweep  
tables 2 and 3 were used.

```

This object can only have the value of 1 or 23."
/* RJW, LUT_SWEEP_TABLE, B, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
  NAME = FILE_VERSION
  DATA_TYPE = LSB_UNSIGNED_INTEGER
  START_BYTE = 88
  BYTES = 1
  VALID_MINIMUM = 0
  VALID_MAXIMUM = 4
  MISSING_CONSTANT = 255
  DESCRIPTION = "The version number of the file this record came from.
e.g., if you loaded file
JAD L30 LRS ION ANY CNT 2016240 V04.DAT
then FILE_VERSION = 4.
[FILE_VERSION = 0 is never in the PDS, but is used by
the JADE team prior to having required calibrations.]"
/* RJW, FILE_VERSION, B, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
  NAME = SC_POS_R
  DATA_TYPE = PC_REAL
84
BYTES = 4
VALID_MINIMUM = START_BYTE = 89
  BYTES = 4
  VALID_MINIMUM = 0.000
  VALID_MAXIMUM = 140130.000 /* Excluding Cruise, can refine later */ to Jupiter
*/
  MISSING_CONSTANT = 65535.000
  UNIT = "
MISSING_CONSTANT = 65535.000
UNIT = "Jupiter Radii"
  DESCRIPTION = "Juno radial distance Jupiter Radii"
  DESCRIPTION = "Juno radial distance at time DIMO UTC, from
Jupiter-
(1, in units of Jupiter Radii (Rj=)).
(1 Rj = 71492.0 km)
[Values may be greater than VALID_MAXIMUM
during cruise to Jupiter before primary mission.]"
/* RJW, SC_POS_R, f, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
  NAME = SC_POS_R_UPPER
DATA_TYPE = PC_REAL
START_BYTE = 95
BYTES =
  DATA_TYPE = PC_REAL
  START_BYTE = 93
  BYTES = 4
  VALID_MINIMUM = 0.000
  VALID_MAXIMUM = 140130.000 /* Excluding Cruise, can refine later */ to Jupiter
*/
  MISSING_CONSTANT = 65535.000
  UNIT = "Jupiter Radii"
  DESCRIPTION = "Juno radial distance at time DIMO UTC UPPER, from Jupiter-
upper limit.
See SC_POS_R for description." Jupiter, in
units of Jupiter Radii (Rj).
(1 Rj = 71492.0 km)

```



```

SC POS R UPPER could be smaller or larger than
SC POS R, depending if moving inbound or outbound.
[Values may be greater than VALID MAXIMUM
during cruise to Jupiter before primary mission.]"
/* RJW, SC_POS_R_UPPER, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = SC_POS_R_LOWER
DATA_TYPE       = PC_REAL
START_BYTE      = 8997
BYTES           = 4
VALID_MINIMUM   = 0.000
VALID_MAXIMUM   = 140130.000 /* Excluding Cruise, can refine later */
MISSING_CONSTANT = 65535.000
UNIT              = "Jupiter Radii"
DESCRIPTION       = "Juno radial distance from to Jupiter lower limit."/
                  See SC_POS_R for description."
/* RJW, MISSING_CONSTANT = 65535.000
UNIT              = "Jupiter Radii"
DESCRIPTION       = "Juno radial distance at time DIMO UTC LOWER, from
Jupiter, in units of Jupiter Radii (Rj).
(1 Rj = 71492.0 km)
SC_POS_R_LOWER, f, 1, 1 */
could be smaller or larger than
SC POS R, depending if moving inbound or outbound.
[Values may be greater than VALID MAXIMUM
during cruise to Jupiter before primary mission.]"
/* RJW, SC_POS_R_LOWER, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = SC_POS_LAT
DATA_TYPE       = PC_REAL
START_BYTE      = 93101
BYTES           = 4
VALID_MINIMUM   = -90.000
VALID_MAXIMUM   = 90.000
MISSING_CONSTANT = 65535.000
UNIT            = "Degrees"
DESCRIPTION     = "Juno Latitude above Jupiter. at time
DIMO UTC, in both the
IAU JUPITER and JUNO JSS frames, in units of degrees.
(0 = Equatorial)"
(JUNO JSS is a despun version of IAU JUPITER, hence
they have identical latitudes.)"
/* RJW, SC_POS_LAT, f, 1, 1 */
END_OBJECT      = COLUMN

OBJECT          = COLUMN
NAME            = SC_POS_LAT_UPPER
DATA_TYPE       = PC_REAL
START_BYTE      = 97
BYTES           = 4
VALID_MINIMUM   = -90.000
VALID_MAXIMUM   = 90.000
MISSING_CONSTANT = 65535.000
UNIT            = "Degrees"
DESCRIPTION     = "Juno Latitude above Jupiter upper limit.
See SC_POS_LAT for description."
/* RJW, SC_POS_LAT_UPPER, f, 1, 1 */
END_OBJECT      = COLUMN

```

```

OBJECT = COLUMN
NAME = SC_POS_LAT_LOWER
DATA TYPE = PC_REAL
START_BYTE = 101
BYTES = 4
VALID MINIMUM = -90.000
VALID MAXIMUM = 90.000
MISSING_CONSTANT = 65535.000
UNIT = "Degrees"
DESCRIPTION = "Juno Latitude above Jupiter - lower limit.
See SC_POS_LAT for description."
/* RJW, SC_POS_LAT_LOWER, f, 1, 1 */
END_OBJECT = COLUMN

```

```

OBJECT = COLUMN
NAME = SC_POS_LOCAL_TIME
DATA TYPE = PC_REAL
START_BYTE = 105
BYTES = 4
VALID MINIMUM = -90.000
VALID MAXIMUM = 90.000
MISSING_CONSTANT = 65535.000
UNIT = "Degrees"
DESCRIPTION = "Juno Latitude
BYTES = 4
VALID MINIMUM = 0.000
VALID MAXIMUM = 24.000
MISSING_CONSTANT = 65535.000
UNIT = "Hours"

```

at time DIM0 UTC UPPER, in both the  
IAU JUPITER and JUNO JSS frames, in units of degrees.  
(0 = Equatorial)  
SC POS LAT UPPER could be smaller or larger than  
SC POS LAT.  
(JUNO JSS is a despun version of IAU JUPITER, hence  
they have identical latitudes.)"

```

/* RJW, SC POS LAT UPPER, f, 1, 1 */
END_OBJECT = COLUMN

```

```

OBJECT = COLUMN
NAME = SC_POS_LAT_LOWER
DATA TYPE = PC_REAL
START_BYTE = 109
BYTES = 4
VALID MINIMUM = -90.000
VALID MAXIMUM = 90.000
MISSING_CONSTANT = 65535.000
UNIT = "Degrees"
DESCRIPTION = "Juno Latitude at time DIM0 UTC LOWER, in both the
IAU JUPITER and JUNO JSS frames, in units of degrees.
(0 = Equatorial)
SC POS LAT LOWER could be smaller or larger than
SC POS LAT.
(JUNO JSS is a despun version of IAU JUPITER, hence
they have identical latitudes.)"

```

```

/* RJW, SC POS LAT LOWER, f, 1, 1 */
END_OBJECT = COLUMN

```

```

OBJECT = COLUMN
NAME = SC_POS_LOCAL_TIME
DATA TYPE = PC_REAL
START_BYTE = 113
BYTES = 4

```

```

VALID MINIMUM      =      0.000
VALID MAXIMUM      =      24.000
MISSING CONSTANT   = 65535.000
UNIT                = "Hours"
DESCRIPTION        = "Juno's (jovian) Local Time from Jupiter, at time DIM0 UTC,
                    in units of hours.
                    00 = Midnight
                    06 = Dawn
                    12 = Noon
                    18 = Dusk"
/* RJW, SC_POS_LOCAL_TIME, f, 1, 1 */
END_OBJECT         = COLUMN

```

```

OBJECT             = COLUMN
NAME               = SC_POS_LOCAL_TIME_UPPER
DATA TYPE        = PC_REAL
START_BYTE        = 109
BYTES             = 4
VALID MINIMUM     =      0.000
VALID MAXIMUM     =      24.000
MISSING CONSTANT  = 65535.000
UNIT              = "Hours"

```

```

DATA TYPE         = PC_REAL
START BYTE        = 117
BYTES             = 4
VALID MINIMUM     =      0.000
VALID MAXIMUM     =      24.000
MISSING CONSTANT  = 65535.000
UNIT              = "Hours"
DESCRIPTION        = "JunoJuno's (jovian) Local Time from Jupiter - upper limit,
                    at time DIM0 UTC UPPER,
                    in units of hours.
                    00 = Midnight
                    06 = Dawn
                    12 = Noon
                    18 = Dusk"
/* RJW, SC_POS_LOCAL_TIME_UPPER, f, 1, 1 */

```

```

END_OBJECT         = COLUMN

OBJECT             = COLUMN
NAME               = SC_POS_LOCAL_TIME_LOWER
DATA TYPE         = PC_REAL
START_BYTE        = 121
BYTES             = 4
VALID MINIMUM     =      0.000
VALID MAXIMUM     =      24.000
MISSING CONSTANT  = 65535.000
UNIT              = "Hours"
DESCRIPTION        = "Juno's (jovian) Local Time at time DIM0 UTC LOWER,
                    in units of hours.
                    00 = Midnight
                    06 = Dawn
                    12 = Noon
                    18 = Dusk"
/* RJW, SC_POS_LOCAL_TIME for description.
/* RJW, SC_POS_LOCAL_TIME_UPPER, f, 1, 1 */
END_OBJECT         = COLUMN

```

```

OBJECT             = COLUMN
NAME               = SC_POS_LOCAL_TIME_LOWER
DATA TYPE         = PC_REAL
START_BYTE        = 113

```

```

BYTES = 4
VALID_MINIMUM = 0.000
VALID_MAXIMUM = 24.000
MISSING_CONSTANT = 65535.000
UNIT = "Hours"
  LOWER, f, 1, 1 */
END OBJECT = COLUMN

OBJECT = COLUMN
  NAME = SC_POS_SYSIII_ELONG
  DATA_TYPE = PC_REAL
  START_BYTE = 125
  BYTES = 4
  VALID_MINIMUM = 0.000
  VALID_MAXIMUM = 360.000
  MISSING_CONSTANT = 65535.000
  UNIT = "Degrees"
  DESCRIPTION = "Juno Local Time from Jupiter lower limit. Juno's (jovian)
SYSIII (East) Longitude at time
See SC_POS_LOCAL_TIME for description."DIM0 UTC, in units of
degrees."
/* RJW, SC_POS_LOCAL_TIME_LOWERSYSIII_ELONG, f, 1, 1 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_POS_JUPITER_J2000XYZ
DATA_TYPE = PC_REAL
START_BYTE = 117
ITEMS = 3
ITEM_BYTES = 4
BYTES = 12
VALID_MINIMUM = 1000000.0 /* -140 Rj */
VALID_MAXIMUM = 1000000.0 /* +140 Rj */
MISSING_CONSTANT = 65535.0 /* +0.917 Rj */
UNIT = "km"
DESCRIPTION = "Juno position from Jupiter in J2000 Cartesian
co ordinates [x,y,z] (units km).
[Values may be outside of VALID_MIN/MAX range (-140Rj)
during cruise to Jupiter before primary mission.]"
/* RJW, SC_POS_JUPITER_J2000XYZ, f, 1, 3 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_VEL_JUPITER_J2000XYZ
DATA_TYPE = PC_REAL
START_BYTE = END OBJECT = COLUMN

OBJECT = COLUMN
  NAME = SC_POS_SYSIII_ELONG_UPPER
  DATA_TYPE = PC_REAL
  START_BYTE = 129
  BYTES = 4
  VALID_MINIMUM = 0.000
  VALID_MAXIMUM = 360.000
  MISSING_CONSTANT = 65535.000
  UNIT = "Degrees"
  DESCRIPTION = "Juno's (jovian) SYSIII (East) Longitude at time
DIM0 UTC UPPER, in units of degrees."
/* RJW, SC_POS_SYSIII_ELONG_UPPER, f, 1, 1 */
END OBJECT = COLUMN

OBJECT = COLUMN
  NAME = SC_POS_SYSIII_ELONG_LOWER

```

```

DATA TYPE      = PC REAL
START BYTE     = 133
BYTES         = 4
VALID MINIMUM  = 0.000
VALID MAXIMUM  = 360.000
MISSING CONSTANT = 65535.000
UNIT          = "Degrees"
DESCRIPTION    = "Juno's (jovian) SYSIII (East) Longitude at time
                DIMO UTC LOWER, in units of degrees."
/* RJW, SC POS SYSIII ELONG LOWER, f, 1, 1 */
END OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = SC POS JUPITER J2000XYZ
DATA TYPE     = PC REAL
START BYTE    = 137
ITEMS         = 3
ITEM BYTES    = 4
BYTES         = 12
VALID MINIMUM = -10008880.0 /* ~ -140 Rj */
VALID MAXIMUM = 10008880.0 /* ~ +140 Rj */
MISSING CONSTANT = 65535.0 /* ~ +0.917 Rj */
UNIT          = "km"
DESCRIPTION   = "Juno position from Jupiter in J2000 Cartesian
                co-ordinates [x,y,z] (units km).
                [Values may be outside of VALID MIN/MAX range (~140Rj)
                during cruise to Jupiter before primary mission.]"
/* RJW, SC POS JUPITER J2000XYZ, f, 1, 3 */
END OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = SC VEL JUPITER J2000XYZ
DATA TYPE     = PC REAL
START BYTE    = 149
ITEMS         = 3
ITEM BYTES    = 4
BYTES         = 12
VALID MINIMUM = -70.0
refine with V_mag during JOI */
VALID MAXIMUM = 70.0
MISSING CONSTANT = 65535.0
UNIT          = "km/s"
DESCRIPTION   = "Juno Velocity with respect to Jupiter in J2000
                Cartesian co-ordinates [Vx,Vy,Vz] (units km/s)."
/* RJW, SC VEL JUPITER J2000XYZ, f, 1, 3 */
END OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = SC VEL ANGULAR J2000XYZ
DATA TYPE     = PC REAL
START BYTE    = 161
ITEMS         = 3
ITEM BYTES    = 4
BYTES         = 12
VALID MINIMUM = -1.0 /* General limit */
VALID MAXIMUM = 1.0 /* General limit */
MISSING CONSTANT = 65535.0
UNIT          = "radians/s"
DESCRIPTION   = "Juno Angular Velocity in Cartesian co-ordinates
                [AVx,AVy,AVz] (units radians/s).
                (This is calculated with the SPICE ckqpav command
                where ref=J2000. SPICE defines it as 'This is the
                axis about which the reference frame tied to the

```

```

instrument is rotating in the right-handed sense.')"
/* RJW, SC VEL ANGULAR J2000XYZ, f, 1, 3 */
END OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_SPIN_PERIOD
DATA_TYPE = PC_REAL
START_BYTE = /* Need to refine with V_mag during JOI */
MISSING_CONSTANT = 65535.0
UNIT = "km/s"
DESCRIPTION = "Juno Velocity with respect to Jupiter in J2000
Cartesian co ordinates [Vx,Vy,Vz] (units km/s)."
/* RJW, SC VEL JUPITER J2000XYZ, f, 1, 3 */
END OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_VEL_ANGULAR_J2000XYZ
DATA_TYPE = PC_REAL
START_BYTE = 141
ITEMS = 3
ITEM_BYTES = 4
BYTES = 12
VALID_MINIMUM = 1.0 /* General limit */
VALID_MAXIMUM = 1.0 /* General limit */
MISSING_CONSTANT = 65535.0
UNIT = "radians/s"
DESCRIPTION = "Juno Angular Velocity in Cartesian co ordinates
[AVx,AVy,AVz] (units radians/s)
(This is calculated with the SPICE ckgpav command
where ref=J2000. SPICE defines it as 'This is the
axis about which the reference frame tied to the
instrument is rotating in the right handed sense.')"
/* RJW, SC VEL ANGULAR J2000XYZ, f, 1, 3 */
END OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_SPIN_PERIOD
DATA_TYPE = PC_REAL
START_BYTE = 153
BYTES = 4
VALID_MINIMUM = 0.173
VALID_MAXIMUM = 100.70.0
MISSING_CONSTANT = 65535.0
UNIT = "SECONDS"
/* May want to refine later */
MISSING_CONSTANT = 65535.0
UNIT = "SECONDS"
DESCRIPTION = "Juno spin period (seconds).
This is not useful during spacecraft maneuvers."
/* RJW, SC_SPIN_PERIOD, f, 1, 1 */
END OBJECT = COLUMN

OBJECT = DESCRIPTION = "Juno spin period (seconds).
This is not useful during spacecraft maneuvers."
/* RJW, SC_SPIN_PERIOD, f, 1, 1 */
END OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC_SPIN_PHASE
DATA_TYPE = PC_REAL
START_BYTE = 177

```

```

BYTES = 4
VALID MINIMUM = 0.000
VALID MAXIMUM = 360.000
MISSING CONSTANT = 65535.000
UNIT = "Degrees"
DESCRIPTION = "Juno's spin phase at time DIM0 UTC,
in units of degrees."
/* RJW, SC SPIN PHASE, f, 1, 1 */
END OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC SPIN PHASE_UPPER
DATA TYPE = PC_REAL
START BYTE = 181
BYTES = 4
VALID MINIMUM = 0.000
VALID MAXIMUM = 360.000
MISSING CONSTANT = 65535.000
UNIT = "Degrees"
DESCRIPTION = "Juno's spin phase at time DIM0 UTC UPPER,
in units of degrees."
/* RJW, SC SPIN PHASE UPPER, f, 1, 1 */
END OBJECT = COLUMN

OBJECT = COLUMN
NAME = SC SPIN PHASE_LOWER
DATA TYPE = PC_REAL
START BYTE = 185
BYTES = 4
VALID MINIMUM = 0.000
VALID MAXIMUM = 360.000
MISSING CONSTANT = 65535.000
UNIT = "Degrees"
DESCRIPTION = "Juno's spin phase at time DIM0 UTC LOWER,
in units of degrees."
/* RJW, SC SPIN PHASE LOWER, f, 1, 1 */
END OBJECT = COLUMN

OBJECT = CONTAINER
NAME = DESPUN_SC_TO_J2000_DIM1
START_BYTE = 189
BYTES = 12 /* = 3 * 4-bytes */
REPETITIONS = 3
DESCRIPTION = "DESPUN SC TO J2000 DIM1,
2D array of data, 1st and 2nd Dimensions."

OBJECT = CONTAINER
NAME = DESPUN_SC_TO_J2000_DIM2
START_BYTE = 1
BYTES = 4
REPETITIONS = 3
DESCRIPTION = "DESPUN SC TO J2000 DIM2,
1D array of data, 2nd Dimension."

OBJECT = COLUMN
NAME = DESPUN_SC_TO_J2000
DATA TYPE = PC_REAL
START_BYTE = 1
ITEMS = 1
ITEM BYTES = 4
BYTES = 4
VALID MINIMUM = -1.0
VALID MAXIMUM = 1.0

```

```

MISSING CONSTANT = 65535.0
DESCRIPTION      = "Rotation matrix from despun spacecraft
                  co-ordinates to J2000.
                  This is a 3x3 matrix, but if read in as a 1x9
                  stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                  and the 2D matrix would be [a,b,c
                  d,e,f
                  g,h,i]"
/* RJW, DESPUN SC TO J2000, f, 2, 3, 3 */
END OBJECT      = COLUMN
END OBJECT      = CONTAINER
END OBJECT      = CONTAINER

OBJECT          = CONTAINER
NAME            = J2000 TO JSSXYZ DIM1
START BYTE     = 225
BYTES          = 12 /* = 3 * 4-bytes */
REPETITIONS    = 3
DESCRIPTION    = "J2000 TO JSSXYZ DIM1,
                  2D array of data, 1st and 2nd Dimensions."

OBJECT          = CONTAINER
NAME            = J2000 TO JSSXYZ DIM2
START BYTE     = 1
BYTES          = 4
REPETITIONS    = 3
DESCRIPTION    = "J2000 TO JSSXYZ DIM2,
                  1D array of data, 2nd Dimension."

OBJECT          = COLUMN
NAME            = J2000 TO JSSXYZ
DATA TYPE      = PC REAL
START BYTE     = 1
ITEMS          = 1
ITEM BYTES     = 4
BYTES          = 4
VALID MINIMUM  = -1.0
VALID MAXIMUM  = 1.0
MISSING CONSTANT = 65535.0
DESCRIPTION    = "Rotation matrix from J2000 co-ordinates to JSS xyz
                  (JSS = Jupiter-De-Spun-Sun, see SIS for details).
                  This is a 3x3 matrix, but if read in as a 1x9
                  stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                  and the 2D matrix would be [a,b,c
                  d,e,f
                  g,h,i]"
/* RJW, J2000 TO JSSXYZ, f, 2, 3, 3 */
END OBJECT      = COLUMN
END OBJECT      = CONTAINER
END OBJECT      = CONTAINER

OBJECT          = CONTAINER
NAME            = J2000 TO JSSRTP DIM1
START BYTE     = 261
BYTES          = 12 /* = 3 * 4-bytes */
REPETITIONS    = 3
DESCRIPTION    = "J2000 TO JSSRTP DIM1,
                  2D array of data, 1st and 2nd Dimensions."

OBJECT          = CONTAINER
NAME            = J2000 TO JSSRTP DIM2
START BYTE     = 1
BYTES          = 4

```



```

REPETITIONS      = 3
DESCRIPTION      = "J2000 TO JSSRTP DIM2,
                  1D array of data, 2nd Dimension."

OBJECT          = COLUMN
NAME            = J2000 TO JSSRTP
DATA TYPE      = PC_REAL
START BYTE     = 1
ITEMS          = 1
ITEM BYTES     = 4
BYTES          = 4
VALID MINIMUM  = -1.0
VALID MAXIMUM  = 1.0
MISSING CONSTANT = 65535.0
DESCRIPTION    = "Rotation matrix from J2000 co-ordinates to
                  JSS RTP, where RTP is Jupiter centered right
                  handed R-Theta-Phi.
                  (JSS = Jupiter-De-Spun-Sun, see SIS for details.)
                  This is a 3x3 matrix, but if read in as a 1x9
                  stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                  and the 2D matrix would be [a,b,c
                  d,e,f
                  g,h,i]"

/* RJW, J2000 TO JSSRTP, f, 2, 3, 3 */
END OBJECT      = COLUMN
END OBJECT      = CONTAINER
END OBJECT      = CONTAINER

OBJECT          = 157
BYTES          = 12 /* = 3 * 4 bytes */
REPETITIONS    = 3
DESCRIPTION    = "DESPUN_SC_TO_J2000_DIM1,
                  2D array of data, 1st and 2nd Dimensions."

OBJECT          = CONTAINER
NAME            = DESPUN_SC_TO_J2000_DIM2
START BYTE     = 1
BYTES          = 4
REPETITIONS    = 3
DESCRIPTION    = "DESPUN_SC_TO_J2000_DIM2,
                  1D array of data, 2nd Dimension."

OBJECT          = COLUMN
NAME            = DESPUN_SC_TO_J2000
DATA TYPE      = PC_REAL
START BYTE     = 1
ITEMS          = 1
ITEM BYTES     = 4
BYTES          = 4
VALID MINIMUM  = 1.0
VALID MAXIMUM  = 1.0
MISSING CONSTANT = 65535.0
DESCRIPTION    = "Rotation matrix from deepun spacecraft
                  co ordinates to J2000.
                  This is a 3x3 matrix, but if read in as a 1x9
                  stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                  and the 2D matrix would be [a,b,c
                  d,e,f
                  g,h,i]"

/* RJW, DESPUN_SC_TO_J2000, f, 2, 3, 3 */
END OBJECT      = COLUMN
END OBJECT      = CONTAINER
END OBJECT      = CONTAINER

```

```

OBJECT = CONTAINER
NAME = J2000_TO_JSSXYZ_DIM1
START_BYTE = 193
BYTES = 12 /* = 3 * 4 bytes */
REPETITIONS = 3
DESCRIPTION = "J2000_TO_JSSXYZ_DIM1,
                2D array of data, 1st and 2nd Dimensions."

OBJECT = CONTAINER
NAME = J2000_TO_JSSXYZ_DIM2
START_BYTE = 1
BYTES = 4
REPETITIONS = 3
DESCRIPTION = "J2000_TO_JSSXYZ_DIM2,
                1D array of data, 2nd Dimension."

OBJECT = COLUMN
NAME = J2000_TO_JSSXYZ
DATA_TYPE = PC_REAL
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = 1.0
VALID_MAXIMUM = 1.0
MISSING_CONSTANT = 65535.0
DESCRIPTION = "Rotation matrix from J2000 co ordinates to JSS xyz
                (JSS = Jupiter De Spun Sun, see SIS for details).
                This is a 3x3 matrix, but if read in as a 1x9
                stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
                and the 2D matrix would be [a,b,c
                d,e,f
                g,h,i]"
/* RJW, J2000_TO_JSSXYZ, f, 2, 3, 3 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER
END_OBJECT = CONTAINER

OBJECT = CONTAINER
NAME = J2000_TO_JSSRTP_DIM1
START_BYTE = 229
BYTES = 12 /* = 3 * 4 bytes */
REPETITIONS = 3
DESCRIPTION = "J2000_TO_JSSRTP_DIM1,
                2D array of data, 1st and 2nd Dimensions."

OBJECT = CONTAINER
NAME = J2000_TO_JSSRTP_DIM2
START_BYTE = 1
BYTES = 4
REPETITIONS = 3
DESCRIPTION = "J2000_TO_JSSRTP_DIM2,
                1D array of data, 2nd Dimension."

OBJECT = COLUMN
NAME = J2000_TO_JSSRTP
DATA_TYPE = PC_REAL
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = 1.0

```

```

VALID_MAXIMUM = 1.0
MISSING_CONSTANT = 65535.0
DESCRIPTION = "Rotation matrix from J2000 co ordinates to
JSS RTP, where RTP is Jupiter centered right
handed R Theta Phi.
(JSS = Jupiter De Spun Sun, see SIC for details.)
This is a 3x3 matrix, but if read in as a 1x9
stream then the 1D stream is [a,b,c, d,e,f, g,h,i]
and the 2D matrix would be [a,b,c
d,e,f
g,h,i]"
/* RJW, J2000_TO_JSSRTP, f, 2, 3, 3 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER
END_OBJECT = CONTAINER

OBJECT = COLUMN
NAME = MCP_VOLTAGE
DATA_TYPE = PC_REAL
START_BYTE = 265 COLUMN
NAME = MCP_VOLTAGE
DATA_TYPE = PC_REAL
START_BYTE = 297
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = -50004000.000 /* Will need
to refine these limits */
VALID_MAXIMUM = 5000.000 /* Will need to refine these limits */4000.000
MISSING_CONSTANT = 65535.000
UNIT = "Volts"
DESCRIPTION = "MCP Voltage on sensor."
/* RJW, MCP_VOLTAGE, f, 1, 1 */
END_OBJECT = COLUMN

OBJECT = CONTAINER
NAME = ISSUES_CONTAINER
START_BYTE =
END_OBJECT = COLUMN 269

OBJECT = CONTAINER
NAME = ISSUES_CONTAINER
START_BYTE = 301
BYTES = 4
REPETITIONS = 2
DESCRIPTION = "ISSUES_CONTAINER, size 2."
OBJECT = COLUMN
NAME = ISSUES
DATA_TYPE = LSB_UNSIGNED_INTEGER
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = 0
VALID_MAXIMUM = 4294967294
MISSING_CONSTANT = 4294967295
DESCRIPTION = "Issues or potential issues in this data record.
[Two values for ions as this is the ISSUES object
from both the ping and pong level 2 packets used
to create this record.]
These are issues that can be identified within the JADE
packet of data itself without any external information.
e.g. timing issues due to the MAG time stutter, or any

```

voltage pulsing, would not be included as there are no indicators to them within this JADE packet.

[For a more comprehensive list of potential issues from internal and external sources please see the Level 3 data.]

Level 2 issues of this JADE packet are flagged by individual bits, and several may be hit. If no issues are flagged then this 4-byte unsigned integer is zero. A value of 4294967295 is the MISSING\_CONSTANT and means that the issue status is currently unknown.

All bits at 0 implies all is okay as seen by this packet. If a bit is set to 1 then that bit is flagged, otherwise it is set to zero and unflagged.

The bits are set as followed, grouped in to seriousness:

Not very serious issues for doing science:

- Bit 0 = UTC time is predicted, yet to be finalized.
- Bit 1 = Position/Orientation values predicted, yet to be finalized. Level 3 (and above) data only.
- Bit 2 = TABLES\_VERSION object was altered on the ground to accurately reflect a 'commanded parameter update' outside the initial per-orbit commands JADE is returning.  
[If changed, the original downlinked TABLES\_VERSION value can be found by cross-referencing the PARAM\_TABLE\_VER object in the JAD\_L20\_HSK\_ALL\_SHK files. Note here the PARAM\_TABLE\_VER value is given as a unsigned integer of Hex Major-Middle-Minor, such that a value of 770 decimal is in hex 0x302, meaning Table Version 3.02 ]
- Bit 3 = FSW\_VERSION 4.00 LRS/CAL Ion Species bug fixed on the ground by adjusting TIMESTAMP\_WHOLE, TIMESTAMP\_SUB, and ACCUMULATION\_TIME based on cross-referencing JADE commanding.
- Bit 4 = LRS/CAL Ion Species record with unobserved look directions (views) populated using views from neighboring record. See Bit 12 for uncorrected/unpopulated description.  
(Only possible if ACCUMULATION\_TIME = 30.)
- Bit 5 = TIMESTAMP\_WHOLE/SUB adjusted on the ground to mitigate any Juno time stutter affects.  
[Other TIMESTAMPS are susceptible to the onboard time stutter too, but only the JADE packet TIMESTAMP\_WHOLE/SUB is tracked here.]
- Bit 6 = Currently unused.
- Bit 7 = Warning, a leap second occurs during the accumulation period.

Data slightly different than expected, but can be used for science with a little extra coding:

- Bit 8 = ACCUM\_TRUNCATION object flagged.
- Bit 9 = Electron (HRS/LRS/CAL) MAG objects are not tracked, are either zeros or MISSING\_CONSTANT.  
[LRS and CAL did not have MAG objects prior to FSW\_VERSION 4.10, therefore those MAG objects here are set to MISSING\_CONSTANT when FSW\_VERSION < 4.10.]
- Bit 10 = TIMESTAMP\_WHOLE/SUB affected by a Juno

onboard time stutter, JADE reported timestamp is likely 1 whole tick too large.

[Other TIMESTAMPS are susceptible to the onboard time stutter too, but only the JADE packet `TIMESTAMP_WHOLE/SUB` is tracked here.]

- Bit 11 = Currently unused.
- Bit 12 = LRS/CAL Ion Species record potentially has unobserved look directions (spin phase sectors or views) present in the data, meaning the record may not contain data for a full  $4\pi$  steradians field-of-view.  
Unobserved look directions have zero counts per view (or counts per second) in the data, although an observed look direction may also have zero counts if no ions were measured. Therefore there is a potential confusion over zero measured counts or simply unmeasured. e.g. if the spin period is 30.7 seconds, then not all of the 78 spin phase sectors will be sampled in 30 seconds. (Unobserved views are only possible if `ACCUMULATION_TIME`  $\leq$  30.) See the JADE SIS for more information.
- Bit 13 = At least one anode is blanked.  
See SIS document for further information.
- Bit 14 = `FSW_VERSION` 4.00 LRS/CAL Ion Species bug warning:  
Not fixed as yet - when fixed it will become bit 3 of ISSUES instead.  
Level 2 data only when `FSW_VERSION` = 4.00, `ACCUMULTION_TIME` object is `MISSING_CONSTANT`. Also, `TIMESTAMP_WHOLE:TIMESTAMP_SUB` is the end of the packet rather than the usual start, see `TIMESTAMP_WHOLE` object for more details. [Only affects data from 2015-089 to 2015-115.]
- Bit 15 = Electron Anodes Reversed.  
Level 2 data only when `FSW_VERSION` < 4.10 and only electron packets. Electron anodes are reversed in order and need to be remapped, however electron Spin Phase data (LRS data) cannot be remapped. See the SIS document for more information about this. [Affects all electron data 2011 to 2015-115.]
- Data very different than expected, may not be suitable for science - use with extreme caution.
- Bit 16 = Data is not from flight instrument on Juno, see `FLIGHT_OR_STL` object.
- Bit 17 = `MCP_NOT_AT_COMMAND` object flagged.  
Electron HRS/CAL/HVE packets use all three electron sensors and therefore have three `MCP_NOT_AT_COMMAND` values per packet. Setting this flag means at least one of those three mcps is not at its commanded value.
- Bit 18 = Data includes some JADE-E300 sensor data. (Only flagged for HRS, LRS, CAL and HVE data.)  
E300 has a high voltage power supply issue and reported energy steps may be incorrect. If E300 is off but still reported in the data product, it may be zeros or fill values.
- Bit 19 = Ion packet abruptly truncated.  
This packet should not be used. It had an `ACCUMULATION_TIME` = 1, `ACCUM_TRUNCATION` = 1 and the `DATA` object is all zeros, with a

timestamp that matches an earlier valid packet that was not truncated and has non-zero DATA. e.g. TOF and LOG example in level 2 data at `TIMESTAMP_WHOLE` of 495879710 (UTC 2015-261).

Bit 20 = MCP Dipping Triggered, in one or more sensors.

If the sensor measures excessive counts, it temporarily lowers the MCP voltage to reduce the number of counts and protect the sensor. The `MCP_NOT_AT_COMMANDED` object is also flagged (Bit 17 in `ISSUES`) since the MCP is no longer at the commanded voltage.

For HRS/CAL/HVE electrons (datasets where multiple sensors are on) it is possible that one sensor has been dipped, but the others are not and still providing good data. (First MCP dip was HRS electrons, 2017-350.)

Bit 21 = MCP Dipped sensor's DATA set to fill values.

If MCP dipping has triggered (Bit 20 of `ISSUES`) then: `DATA` and `BACKGROUND` objects (and their `*_SIGMAS`) have been replaced with `MISSING_CONSTANT` values.

(Never used for Level 2 data, which has the counts as measured in the dipped state.)

In addition, Bit 17 of the `ISSUES` object (i.e. `MCP_NOT_AT_COMMANDED` object = 1) is set to zero, and, if it exists, the `MCP_NOT_AT_COMMANDED` object itself is changed (from 1) to be 0 for the offending sensor(s).

If the `DATA` object contains data from multiple sensors (HRS/CAL/HVE electrons) then only the elements of the `DATA` object for the dipped sensor are set to `MISSING_CONSTANT` (as identified by the `MCP_NOT_AT_COMMANDED` value for each sensor (prior to setting them to 0)).

[See Bit 22 for a similar flag.]

Bit 22 = 1 or more ELC sensor DATA set to fill values.

Affects only electron HRS/CAL/HVE products (i.e. products that use multiple sensors), and generally only when starting that mode. When switching to HRS/CAL/HVE from LRS, one JADE-E sensor is already on, and the other(s) have to turn on, then it takes some time for that sensor to reach the commanded voltage. For a given record, `MCP_NOT_AT_COMMANDED` = 0 for one sensor but is still = 1 for others. That is one sensor is taking valid science but the other(s) are not there yet and for those sensors: `DATA` and `BACKGROUND` objects (and their `*_SIGMAS`) have been replaced with `MISSING_CONSTANT` values.

(Never used for Level 2 data, which has the counts as measured in the dipped state.)

In addition, Bit 17 of the `ISSUES` object (i.e. `MCP_NOT_AT_COMMANDED` object = 1) is set to zero, and, if it exists, the `MCP_NOT_AT_COMMANDED` object itself is changed (from 1) to be 0 for the offending sensor(s).

Only the elements of the `DATA` object for the original `MCP_NOT_AT_COMMANDED` = 1 sensor(s) (prior to setting them to 0) are set to `MISSING_CONSTANT`.

[Bits 21 and 22 are essentially the same feature caused by an mcp voltage not being at

the commanded value, but the reason why this is the case is different. The treatment is identical for both Bit 21 and Bit 22.]

Bit 23 = Currently unused.  
 Bit 24 = Currently unused.  
 Bit 25 = Currently unused.  
 Bit 26 = Currently unused.  
 Bit 27 = Currently unused.  
 Bit 28 = Currently unused.  
 Bit 29 = Currently unused.  
 Bit 30 = Currently unused.  
 Bit 31 = Reserved for MISSING\_CONSTANT use.

Each bit has a decimal value of  $2^{\{\text{bit number}\}}$ , and the Issues flag is the sum of  $2^{\{\text{flagged bit numbers}\}}$ . For instance, if this ISSUES flag = 131329, then in binary that value is 00000000000000100000000100000001 showing bits 17, 8 and 0 are flagged.

[If a currently unused bit is set, please check the latest LBL file for this product that you can find to see if it now has a definition.]"

```

OBJECT          = BIT_COLUMN
NAME            = ISSUES_BITS
BIT_DATA_TYPE  = BOOLEAN
START_BIT      = 1
BITS           = 32
ITEMS          = 32
ITEM_BITS      = 1
MINIMUM        = 0
MAXIMUM        = 1
DESCRIPTION    = "See ISSUES column object for description of bits."
END_OBJECT     = BIT_COLUMN
/* RJW, ISSUES, I, 1, 2 */
END_OBJECT     = COLUMN
END_OBJECT     = CONTAINER

```

```

OBJECT          = COLUMN
NAME            = TIMESTAMP_WHOLE
DATA_TYPE      = LSB_UNSIGNED_INTEGER
START_BYTE     = 277309
ITEMS          = 2
ITEM_BYTES     = 4
BYTES          = 8
VALID_MINIMUM  = 365774402 /* 2011-Aug-05: Juno Launch */
VALID_MAXIMUM  = 599573000 /* ~ 2019-Jan-01 */
MISSING_CONSTANT = 0
DESCRIPTION    = "Timestamps (Whole Second) of JADE Level 2 packets
                  used to make this Level 3 record.
                  (Both the ping and pong level 2 packets.)"
/* RJW, TIMESTAMP_WHOLE, I, 1, 2 */
END_OBJECT     = COLUMN

```

```

OBJECT          = COLUMN
NAME            = TIMESTAMP_SUB
DATA_TYPE      = LSB_UNSIGNED_INTEGER
START_BYTE     = 285317
ITEMS          = 2
ITEM_BYTES     = 2
BYTES          = 4
VALID_MINIMUM  = 0

```

```

VALID_MAXIMUM      = 65535
MISSING_CONSTANT   = 0
DESCRIPTION        = "Timestamps (Subsecond) of JADE Level 2 packets
                    used to make this Level 3 record.
                    (Both the ping and pong level 2 packets.)"
/* RJW, TIMESTAMP_SUB, H, 1, 2 */
END_OBJECT        = COLUMN

OBJECT            = CONTAINER
NAME              = DATA_DIM1
START_BYTE       = 289321
BYTES            = 372 /* = 1 * 93 * 4-bytes */
REPETITIONS      = 64
DESCRIPTION      = "DATA_DIM1,
                    3D array of data, 1st, 2nd and 3rd Dimensions."

OBJECT            = CONTAINER
NAME              = DATA_DIM2
START_BYTE       = 1
BYTES            = 372 /* = 93 * 4-bytes */
REPETITIONS      = 1
DESCRIPTION      = "DATA_DIM2,
                    2D array of data, 2nd Dimension."

OBJECT            = CONTAINER
NAME              = DATA_DIM3
START_BYTE       = 1
BYTES            = 4
REPETITIONS      = 93
DESCRIPTION      = "DATA_DIM3,
                    1D array of data, 3rd Dimension."

OBJECT            = COLUMN
NAME              = DATA
DATA_TYPE        = PC_REAL
START_BYTE       = 1
ITEMS            = 1
ITEM_BYTES       = 4
BYTES            = 4
VALID_MINIMUM    = -999998 /* if background removed, can be <0 */
VALID_MAXIMUM    = 1000000 /* A guess! need to refine value later */2250000
MISSING_CONSTANT = -1-999999
UNIT             = "COUNTS/SECOND"
DESCRIPTION      = "DATA: Counts/Second
                    64 Energy x 1 Look Direction x 93 Channels.
                    The 93 elements collapse the original 128 TOF
                    channels as:
                    [ 0]: TOF channels 0 - 1
                    [ 1]: TOF channel 2
                    [ 2]: TOF channel 3
                    [ 3]: TOF channel 4
                    ...
                    [59]: TOF channel 60
                    [60]: TOF channel 61
                    [61]: TOF channels 62 - 63
                    [62]: TOF channels 64 - 65
                    ...
                    [70]: TOF channels 80 - 81
                    [71]: TOF channels 82 - 83
                    [72]: TOF channel 84
                    [73]: TOF channel 85
                    [74]: TOF channel 86
                    [75]: TOF channel 87

```



```

[76]: TOF channel 88
[77]: TOF channels 89 - 90
[78]: TOF channels 91 - 92
...
[89]: TOF channels 113 - 114
[90]: TOF channels 115 - 116
[91]: TOF channels 117 - 118
[92]: TOF channels 119 - 124

```

These channels are expressed as a duration in seconds in object DIM3\_TOF-  
Original TOF channels 125, 126, and 127 for more details see the TOF CHANNEL TO SECONDS HLC V04.CSV file in the CALIB directory of this PDS archive.  
The Level 2 data had 96 channels, those last 3 are now objects TOF\_WITH\_START\_OVERLOAD, TOF\_TOO\_SHORT and TOF\_TOO\_LONG respectively."

```

/* RJW, DATA, f, 3, 64, 1, 93 */
  END_OBJECT      = COLUMN
  END_OBJECT      = CONTAINER
  END_OBJECT      = CONTAINER
END_OBJECT        = CONTAINER

OBJECT            = CONTAINER
  NAME            = DATA_SIGMA_DIM1
  START_BYTE      = 24129
  BYTES           = 372 /* = 1 * 93 * 4-bytes */
  REPETITIONS     = 64
  DESCRIPTION     = "24097
  BYTES           = 372 /* = 1 * 93 * 4 bytes */
  REPETITIONS     = 64
  DESCRIPTION     = "DATA_SIGMA_DIM1,
                  3D array of data, 1st, 2nd and 3rd Dimensions."

OBJECT            = CONTAINER
  NAME            =
  DESCRIPTION     = "3D array of data, 1st, 2nd and 3rd Dimensions."

OBJECT            = CONTAINER
  NAME            = DATA_SIGMA_DIM2
  START_BYTE      = 1
  BYTES           = 372 /* = 93 * 4-bytes */
  REPETITIONS     = 1
  DESCRIPTION     = "DATA_SIGMA_DIM2,
                  2D array of data, 2nd Dimension."

OBJECT            = CONTAINER
  NAME            = DATA_SIGMA_DIM3
  START_BYTE      = 1
  BYTES           = 4
  REPETITIONS     = 93
  DESCRIPTION     = "DATA_SIGMA_DIM3,
                  1D array of data, 3rd Dimension."

OBJECT            = COLUMN
  NAME            =
  DESCRIPTION     = "1D array of data, 3rd Dimension."

OBJECT            = COLUMN
  NAME            = DATA_SIGMA
  DATA_TYPE      = PC_REAL
  START_BYTE      = 1
  ITEMS           = 1
  ITEM_BYTES      = 4

```

```

        BYTES                = 4
        VALID_MINIMUM        = 0
        VALID_MAXIMUM        = 1000000 /* A guess! need to refine value later */ 100000
        MISSING_CONSTANT     = -1 999999
        UNIT                  = "COUNTS/SECOND"
        DESCRIPTION          = "DATA_SIGMA
                               1-sigma uncertainties on values in object DATA,
                               such that true value = DATA +/- DATA_SIGMA.
                               See DATA entry above for size information."
/* RJW, DATA_SIGMA, f, 3, 64, 1, 93 */
        END_OBJECT          = COLUMN
        END_OBJECT          = CONTAINER
        END_OBJECT          = CONTAINER
END_OBJECT                  = CONTAINER

OBJECT                      = CONTAINER
NAME                        = BACKGROUND_DIM1
START_BYTE                  = 47905
BYTES                      = 372 /* = 1 * 93 * 4 bytes */
REPETITIONS                = 64
DESCRIPTION                = "47937
        BYTES                = 372 /* = 1 * 93 * 4-bytes */
        REPETITIONS          = 64
        DESCRIPTION          = "BACKGROUND_DIM1,
                               3D array of data, 1st, 2nd and 3rd Dimensions."

OBJECT                      = CONTAINER
NAME                        =
        3D array of data, 1st, 2nd and 3rd Dimensions."

OBJECT                      = CONTAINER
NAME                        = BACKGROUND_DIM2
START_BYTE                  = 1
BYTES                       = 372 /* = 93 * 4-bytes */
REPETITIONS                 = 1
DESCRIPTION                  = "BACKGROUND_DIM2,
                               2D array of data, 2nd Dimension."

OBJECT                      = CONTAINER
NAME                        = BACKGROUND_DIM3
START_BYTE                  = 1
BYTES                       = 4
REPETITIONS                 = 93
DESCRIPTION                  = "BACKGROUND_DIM3,
                               1D array of data, 3rd Dimension."

OBJECT                      = COLUMN
NAME                        =
        1D array of data, 3rd Dimension."

OBJECT                      = COLUMN
NAME                        = BACKGROUND
        DATA_TYPE          = PC_REAL
        START_BYTE          = 1
        ITEMS                = 1
        ITEM_BYTES           = 4
        BYTES                = 4
        VALID_MINIMUM        = 0
        VALID_MAXIMUM        = 1000000 /* A guess! need to refine value later */ 2250000
        MISSING_CONSTANT     = -1 999999
        UNIT                  = "COUNTS/SECOND"
        DESCRIPTION          = "Background value removed from DATA.
                               No further background removal is required."

```

```

                                If you wish to do your own background removal,
                                add this object to DATA then you can remove a
                                background via your own method.
                                The background values here were found from either
                                a background anode or JADE's own ground method."
/* RJW, BACKGROUND, f, 3, 64, 1, 93 */
    END_OBJECT      = COLUMN
    END_OBJECT      = CONTAINER
    END_OBJECT      = CONTAINER
END_OBJECT        = CONTAINER

OBJECT            = CONTAINER
NAME              = BACKGROUND_SIGMA_DIM1
START_BYTE       = 7171371745
BYTES            = 372 /* = 1 * 93 * 4-bytes */
REPETITIONS      = 64
DESCRIPTION       = "BACKGROUND_SIGMA_DIM1,
                    3D array of data, 1st, 2nd and 3rd Dimensions."

OBJECT            = CONTAINER
NAME              = BACKGROUND_SIGMA_DIM2
START_BYTE       = 1
BYTES            = 372 /* = 93 * 4-bytes */
REPETITIONS      = 1
DESCRIPTION       = "BACKGROUND_SIGMA_DIM2,
                    2D array of data, 2nd Dimension."

OBJECT            = CONTAINER
NAME              = BACKGROUND_SIGMA_DIM3
START_BYTE       = 1
BYTES            = 4
REPETITIONS      = 93
DESCRIPTION       = "BACKGROUND_SIGMA_DIM3,
                    1D array of data, 3rd Dimension."

OBJECT            = COLUMN
NAME              = BACKGROUND_SIGMA
DATA_TYPE        = PC_REAL
START_BYTE       = 1
ITEMS            = 1
ITEM_BYTES       = 4
BYTES            = 4
VALID_MINIMUM    = 0
VALID_MAXIMUM    = 1000000 /* A guess! need to refine value later */_100000
MISSING_CONSTANT = -1-999999
UNIT              = "COUNTS/SECOND"
DESCRIPTION       = "BACKGROUND_SIGMA
                    1-sigma uncertainties on values in object
                    BACKGROUND, such that
                    true value = BACKGROUND +/- BACKGROUND_SIGMA.
                    See BACKGROUND entry above for size information."
/* RJW, BACKGROUND_SIGMA, f, 3, 64, 1, 93 */
    END_OBJECT      = COLUMN
    END_OBJECT      = CONTAINER
    END_OBJECT      = CONTAINER
END_OBJECT        = CONTAINER

OBJECT            = CONTAINER
NAME              = DIM1_E_DIM1
START_BYTE       = 9552195553
BYTES            = 4
REPETITIONS      = 64
DESCRIPTION       = "DIM1_E_DIM1,

```

```

(2D array of size 64x1 = 1D array of size 64.)"

OBJECT      = COLUMN
NAME        = DIM1_E
DATA_TYPE   = PC_REAL
START_BYTE  = 1
ITEMS       = 1
ITEM_BYTES  = 4
BYTES       = 4
VALID_MINIMUM = 0.0
VALID_MAXIMUM = 50000.0 /* Refine. Rounded up to whole keV/q */
MISSING_CONSTANT = 99999.0
UNIT        = "eV/q"
DESCRIPTION = "1st Dimension of DATA: Energy ---(center) in eV/q value
Upper and lower limits are given by the
objects DIM1_E_UPPER and DIM1_E_LOWER."
*/ RJW, DIM1_E, f, 1, 64 */
END_OBJECT  = COLUMN
END_OBJECT  = CONTAINER

OBJECT      = CONTAINER
NAME        = DIM2_ELEVATION DIM1_E_UPPER_DIM1
START_BYTE  = 9577795809
BYTES       = 4
REPETITIONS = 64
DESCRIPTION = "DIM2_ELEVATION DIM1_E_UPPER_DIM1,
(2D array of size 64x1 = 1D array of size 64.)"

OBJECT      = COLUMN
NAME        = DIM1_E_UPPER DIM2_ELEVATION
DATA_TYPE   = PC_REAL
START_BYTE  = 1
ITEMS       = 1
ITEM_BYTES  = 4
BYTES       = 4
VALID_MINIMUM = 0.0
VALID_MAXIMUM = 50000.0 /* Refine. Rounded up to whole keV/q */
MISSING_CONSTANT = 99999.0
UNIT        = "eV/q"
DESCRIPTION = "1st Dimension of DATA: Energy upper eV/q limit.
See DIM1_E for description."
/* RJW, DIM1_E_UPPER, f, 1, 64 */
END_OBJECT  = COLUMN
END_OBJECT  = CONTAINER

OBJECT      = CONTAINER
NAME        = DIM1_E_LOWER_DIM1
START_BYTE  = 96033
BYTES       = 4
REPETITIONS = 64
DESCRIPTION = "DIM1_E_LOWER_DIM1,
(2D array of size 64x1 = 1D array of size 64.)"

OBJECT      = COLUMN
NAME        = DIM1_E_LOWER
DATA_TYPE   = PC_REAL
START_BYTE  = 1
ITEMS       = 1
ITEM_BYTES  = 4
BYTES       = 4
VALID_MINIMUM = 0.0
VALID_MAXIMUM = 50000.0 /* Refine. Rounded up to whole keV/q */
MISSING_CONSTANT = 99999.0

```

```

UNIT = "eV/q"
DESCRIPTION = "1st Dimension of DATA: Energy lower eV/q limit.
See DIM1_E for description."
/* RJW, DIM1_E_LOWER, f, 1, 64 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER

OBJECT = CONTAINER
NAME = DIM2_ELEVATION_DIM1
START_BYTE = 96289
BYTES = 4
REPETITIONS = 64
DESCRIPTION = "DIM2_ELEVATION_DIM1,
(2D array of size 64x1 = 1D array of size 64.)"

OBJECT = COLUMN
NAME = DIM2_ELEVATION
DATA_TYPE = PC_REAL
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = -90.0
/* 12 ion anodes cover 270 degs of elevation */
VALID_MAXIMUM = 180.0
MISSING_CONSTANT = 65535.0
UNIT = "Degrees"
DESCRIPTION = "2nd Dimension of DATA: Spacecraft elevation -
center value. Spacecraft elevation (degs) is
analogous to latitude on a sphere. In spacecraft
xyz co-ords:
+z is equivalent to elevation = +90 degs
-z is equivalent to elevation = -90 degs
(The communication dish is directed along +z)
xy-plane at z = 0 is equivalent to elevation = 0

Note, 2nd dimension is really look direction
which has an elevation and azimuth; hence two
objects describe this: DIM2_ELEVATION and
DIM2_AZIMUTH_DESPUN."
/* RJW, DIM2_ELEVATION, f, 1, 64 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER

OBJECT = CONTAINER
NAME = DIM2_ELEVATION_UPPER_DIM1
START_BYTE = 96545
BYTES = 4
REPETITIONS = 64
DESCRIPTION = "DIM2_ELEVATION_UPPER_DIM1,
(2D array of size 64x1 = 1D array of size 64.)"

OBJECT = COLUMN
NAME = DIM2_ELEVATION_UPPER
DATA_TYPE = PC_REAL
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = -90.0
/* 12 ion anodes cover 270 degs of elevation */
VALID_MAXIMUM = 180.0
MISSING_CONSTANT = 65535.0

```

```

UNIT = "Degrees"
DESCRIPTION = "2nd Dimension of DATA: S/C elevation upper
limit. See DIM2_ELEVATION for description."
/* RJW, DIM2_ELEVATION_UPPER, f, 1, 64 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER

OBJECT = CONTAINER
NAME = DIM2_ELEVATION_LOWER_DIM1
START_BYTE = 96801
BYTES = 4
REPETITIONS = 64
DESCRIPTION = "DIM2_ELEVATION_LOWER_DIM1,
(2D array of size 64x1 = 1D array of size 64.)"

OBJECT = COLUMN
NAME = DIM2_ELEVATION_LOWER
DATA_TYPE = PC_REAL
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = 90.0
/* 12 ion anodes cover 270 degs of elevation */
VALID_MAXIMUM = 180.0
MISSING_CONSTANT = 65535.0 UNIT
= "Degrees"
DESCRIPTION = "2nd Dimension of DATA: S/C elevation lower
limit. See DIM2_ELEVATION for description."
/* RJW, DIM2_ELEVATION_LOWER, f, 1, 64 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER

OBJECT = CONTAINER
NAME = DIM2_AZIMUTH_DESPUN_DIM1
START_BYTE = 9705796065
BYTES = 4
REPETITIONS = 64
DESCRIPTION = "DIM2_AZIMUTH_DESPUN_DIM1,
(2D array of size 64x1 = 1D array of size 64.)"

OBJECT = COLUMN
NAME = DIM2_AZIMUTH_DESPUN
DATA_TYPE = PC_REAL
START_BYTE = 1
ITEMS = 1
ITEM_BYTES = 4
BYTES = 4
VALID_MINIMUM = 0.0
VALID_MAXIMUM = 720360.0
MISSING_CONSTANT = 65535.0
UNIT = "Degrees"
DESCRIPTION = "2nd Dimension of DATA: Despun S/C azimuth -
center value. Spacecraft azimuth (degs) is
analogous to longitude on a sphere. In spacecraft
xyz co-ords:
+x is equivalent to azimuth = 0 degs
+y is equivalent to azimuth = 90 degs
-x is equivalent to azimuth = 180 degs
-y is equivalent to azimuth = 270 degs
+x is equivalent to azimuth = 360 degs
+y is equivalent to azimuth = 450 degs
The 'Despun' azimuth angle varies because Juno

```

spins, where azimuth = 0 is defined as +x when spin phase equals zero (e.g., despun x-z plane contains the ECLIPJ2000 north).

The relationship between despun azimuth and spin phase ~~(which decreases during a spin)~~ is simply:  
 Despun Azimuth = 360 degrees - Spin Phase

~~Because a lower to upper limit could occur over a 360 degree boundary, the VALID\_MINIMUM and VALID\_MAXIMUM go from 0 to +720 degrees: e.g. [lower, center, upper] = [10, 5, 20] would be given instead as = [350, 365, 380]~~

Note, 2nd dimension is really look direction which has an elevation and azimuth; hence two objects describe this: DIM2\_ELEVATION and DIM2\_AZIMUTH\_DESPUN."

```
/* RJW, DIM2_AZIMUTH_DESPUN, f, 1, 64 */
  END_OBJECT = COLUMN
END_OBJECT = CONTAINER
```

```
OBJECT = CONTAINER
  NAME = DIM2_AZIMUTH_DESPUN_UPPER_DIM1
  START_BYTE = 97313
  BYTES = 4
  REPETITIONS = 64
  DESCRIPTION = "DIM2_AZIMUTH_DESPUN_UPPER_DIM1,
                (2D array of size 64x1 = 1D array of size 64.)"
```

```
OBJECT = COLUMN
  NAME = DIM2_AZIMUTH_DESPUN_UPPER
  DATA_TYPE = PC_REAL
  START_BYTE = 1
  ITEMS = 1
  ITEM_BYTES = 4
  BYTES = 4
  VALID_MINIMUM = 0.0
  VALID_MAXIMUM = 720.0
  MISSING_CONSTANT = 65535.0
  UNIT = "Degrees"
  DESCRIPTION = "2nd Dimension of DATA: Despun S/C azimuth - upper
                limit. See DIM2_AZIMUTH_DESPUN for description."
```

```
/* RJW, DIM2_AZIMUTH_DESPUN_UPPER, f, 1, 64 */
  END_OBJECT = COLUMN
END_OBJECT = CONTAINER
```

```
OBJECT = CONTAINER
  NAME = DIM2_AZIMUTH_DESPUN_LOWER_DIM1
  START_BYTE = 97569
  BYTES = 4
  REPETITIONS = 64
  DESCRIPTION = "DIM2_AZIMUTH_DESPUN_LOWER_DIM1,
                (2D array of size 64x1 = 1D array of size 64.)"
```

```
OBJECT = COLUMN
  NAME = DIM2_AZIMUTH_DESPUN_LOWER
  DATA_TYPE = PC_REAL
  START_BYTE = 1
  ITEMS = 1
  ITEM_BYTES = 4
  BYTES = 4
  VALID_MINIMUM = 0.0
```

```

VALID_MAXIMUM = 720.0
MISSING_CONSTANT = 65535.0
UNIT = "Degrees"
DESCRIPTION = "2nd Dimension of DATA: Despun S/C azimuth - lower
limit. See DIM2_AZIMUTH_DESPUN for description."
/* RJW, DIM2_AZIMUTH_DESPUN_LOWER, f, 1, 64 */
END_OBJECT = COLUMN
END_OBJECT = CONTAINER

OBJECT = COLUMN
NAME = DIM3_TOF
DATA_TYPE = PC_REAL

DATA_TYPE = PC_REAL
START_BYTE = 9782596321
ITEMS = 93
ITEM_BYTES = 4
BYTES = 372
VALID_MINIMUM = 0.000000000
VALID_MAXIMUM = 0.000000330 /* = 330e-9 = 330 ns */
MISSING_CONSTANT = 65535.0
UNIT = "SECONDS"
DESCRIPTION = "3rd Dimension of DATA: Time Of Flight (center) value.
(Seconds)"
/* RJW, DIM3_TOF, f, 1, 93 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = DIM3_TOF_UPPER NAME =
TOF WITH START OVERLOAD
DATA_TYPE = PC_REAL
START_BYTE = 98197
ITEMS = 93
ITEM_BYTES = 4
BYTES = 372
VALID_MINIMUM = 0.000000000
VALID_MAXIMUM = 0.000000330 /* = 330e-9 = 330 ns */
MISSING_CONSTANT = 65535.0
UNIT = "SECONDS"
DESCRIPTION = "3rd Dimension of DATA: Time Of Flight - upper limit.
See DIM3_TOF for description."
/* RJW, DIM3_TOF_UPPER, f, 1, 93 */ 96693
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = DIM3_TOF_LOWER
DATA_TYPE = PC_REAL
START_BYTE = 98569
ITEMS = 93
ITEM_BYTES = 4
BYTES = 372
VALID_MINIMUM = 0.000000000
VALID_MAXIMUM = 0.000000330 /* = 330e-9 = 330 ns */
MISSING_CONSTANT = 65535.0
UNIT = "SECONDS"
DESCRIPTION = "3rd Dimension of DATA: Time Of Flight - lower limit.
See DIM3_TOF for description."
/* RJW, DIM3_TOF_LOWER, f, 1, 93 */
END_OBJECT = COLUMN

OBJECT = COLUMN
NAME = TOF_WITH_START_OVERLOAD
DATA_TYPE = PC_REAL

```



```

START_BYTE = 98941
ITEMS          = 64
ITEM_BYTES    = 4
BYTES         = 256
VALID_MINIMUM = 0          /* same value as for DATA object */
VALID_MAXIMUM = 1000000 /* same value as for DATA object */
MISSING_CONSTANT = -1     /* same value as for DATA object */
UNIT          = "COUNTS/SECOND"
DESCRIPTION   = "TOF with start overload: Counts/Second
                A signal pulse that is too strong (above a threshold)
                in the electronics. Multiple start-overloads that
                occur within a 330ns event window are counted each time
                in the Logicals Start Overload, but only once here."
/* RJW, TOF_WITH_START_OVERLOAD, f, 1, 64 */
END_OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = TOF_WITH_START_OVERLOAD_SIGMA
DATA_TYPE     = PC_REAL
START_BYTE    = 9919796949
ITEMS         = 64
ITEM_BYTES    = 4
BYTES         = 256
VALID_MINIMUM = 0          /* same value as for DATA object */
VALID_MAXIMUM = 1000000 /* same value as for DATA object */
MISSING_CONSTANT = -1     /* same value as for DATA object */
UNIT          = "COUNTS/SECOND"
DESCRIPTION   = "TOF with start overload uncertainty: Counts/Second
                1-sigma uncertainties on values in object
                TOF_WITH_START_OVERLOAD such that true value =
                TOF_WITH_START_OVERLOAD +/- TOF_WITH_START_OVERLOAD_SIGMA.
                See TOF_WITH_START_OVERLOAD entry above for size
                information."
/* RJW, TOF_WITH_START_OVERLOAD_SIGMA, f, 1, 64 */
END_OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = TOF_TOO_SHORT
DATA_TYPE     = PC_REAL
START_BYTE    = 9945397205
ITEMS         = 64
ITEM_BYTES    = 4
BYTES         = 256
VALID_MINIMUM = 0          /* same value as for DATA object */
VALID_MAXIMUM = 1000000 /* same value as for DATA object */
MISSING_CONSTANT = -1     /* same value as for DATA object */
UNIT          = "COUNTS/SECOND"
DESCRIPTION   = "TOF too short: Counts/Second
                TOF underflow: Count of TOF measurements that did not
                timeout, but resulted in a measurement smaller than
                the sensor could measure."
/* RJW, TOF_TOO_SHORT, f, 1, 64 */
END_OBJECT    = COLUMN

OBJECT        = COLUMN
NAME          = TOF_TOO_SHORT_SIGMA
DATA_TYPE     = PC_REAL
START_BYTE    = 9970997461
ITEMS         = 64
ITEM_BYTES    = 4
BYTES         = 256
VALID_MINIMUM = 0          /* same value as for DATA object */
VALID_MAXIMUM = 1000000 /* same value as for DATA object */

```

```

MISSING_CONSTANT = -1      /* same value as for DATA object */
UNIT              = "COUNTS/SECOND"
DESCRIPTION       = "TOF too short uncertainty: Counts/Second
                    1-sigma uncertainties on values in object
                    TOF_TOO_SHORT such that true value =
                    TOF_TOO_SHORT +/- TOF_TOO_SHORT_SIGMA.
                    See TOF_TOO_SHORT entry above for size information."
/* RJW, TOF_TOO_SHORT_SIGMA, f, 1, 64 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = TOF_TOO_LONG
DATA_TYPE         = PC_REAL
START_BYTE        = 9996597717
ITEMS             = 64
ITEM_BYTES        = 4
BYTES            = 256
VALID_MINIMUM     = 0      /* same value as for DATA object */
VALID_MAXIMUM     = 1000000 /* same value as for DATA object */
MISSING_CONSTANT  = -1    /* same value as for DATA object */
UNIT              = "COUNTS/SECOND"
DESCRIPTION       = "TOF too long: Counts/Second
                    TOF overflow: Count of TOF measurements that resulted
                    in no stop signal arriving within 330ns of the start
                    signal."
/* RJW, TOF_TOO_LONG, f, 1, 64 */
END_OBJECT        = COLUMN

OBJECT            = COLUMN
NAME              = TOF_TOO_LONG_SIGMA
DATA_TYPE         = PC_REAL
START_BYTE        = 10022197973
ITEMS             = 64
ITEM_BYTES        = 4
BYTES            = 256
VALID_MINIMUM     = 0      /* same value as for DATA object */
VALID_MAXIMUM     = 1000000 /* same value as for DATA object */
MISSING_CONSTANT  = -1    /* same value as for DATA object */
UNIT              = "COUNTS/SECOND"
DESCRIPTION       = "TOF too long uncertainty: Counts/Second
                    1-sigma uncertainties on values in object
                    TOF_TOO_LONG such that true value =
                    TOF_TOO_LONG +/- TOF_TOO_LONG_SIGMA.
                    See TOF_TOO_LONG entry above for size information."
/* RJW, TOF_TOO_LONG_SIGMA, f, 1, 64 */
END_OBJECT        = COLUMN

```

## **Appendix E Level 5 data record formats**

This section describes the format of the Level 5 data files.